

Schedule of Items

Proposal ID: C0000125648N01

Oversight/State Project No.: PM9K-053-F25, N501

Order No.: 971

Federal Project No.: NONE

Contractor: \_\_\_\_\_

SECTION: 0001

REGULAR BID ITEM

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	303	303SD20-0030 INLET PROTECTION TYPE A	2.000 EA	_____	_____	_____	_____
0020	303	303SD20-0031 INLET PROTECTION TYPE B	61.000 EA	_____	_____	_____	_____
0030	ATTD	305SP20-0003 AGR. BASE MAT. TY.I OR II NO. 21A OR 21B	145.000 TON	_____	_____	_____	_____
0040	310	310SD20-0001 TACK COAT	23,950.000 GAL	_____	_____	_____	_____
0050	315	315SD20-0024 ASPH. CONC. TY. SM-9.0A MAINT	1,914.870 TON	_____	_____	_____	_____
0060	315	315SD20-0040 ASPH. CONC. TY. IM-19.0A MAINT	1,218.860 TON	_____	_____	_____	_____
0070	ATTD	315SP20-0006 PAVEMENT SHOULDER WEDGE PREP. CONST	7,392.000 LF	_____	_____	_____	_____
0080	315	315SP20-0048 ASPH. CONC. BMD P+VO SM- 9.5A	9,138.070 TON	_____	_____	_____	_____
0090	315	315SP20-0049 ASPH. CONC. BMD P+VO SM- 9.5D	12,091.610 TON	_____	_____	_____	_____
0100	323	323SD20-0041 SURFACE PREPARATION AND RESTORATION TYPE II	699.000 TON	_____	_____	_____	_____
0110	512	512SD20-0027 FLAGGER SERVICE	2,696.000 HR	_____	_____	_____	_____
0120	512	512SD20-0042 ERADICATE LINEAR PVMT MRKG	18,905.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000125648N01

Oversight/State Project No.: PM9K-053-F25, N501

Order No.: 971

Federal Project No.: NONE

Contractor: \_\_\_\_\_

SECTION: 0001

REGULAR BID ITEM

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0130	512	512SD20-0043 ERADICATE NONLINEAR PVMT MRKG	1,874.000 SF	_____	_____	_____	_____
0140	512	512SD20-0046 TEMP. PVMT MRKG TY. A, 4"	105,386.000 LF	_____	_____	_____	_____
0150	512	512SD20-0047 TEMP. PVMT MRKG TY. A, 6"	1,238.000 LF	_____	_____	_____	_____
0160	512	512SD20-0049 TEMP. PVMT MRKG TY. A, 12"	592.000 LF	_____	_____	_____	_____
0170	512	512SD20-0050 TEMP. PVMT MRKG TY. A, 24"	1,159.000 LF	_____	_____	_____	_____
0180	512	512SD20-0052 TEMP. PVMT. SYMB. MRKG SNGL TURN ARROW TY. A	12.000 EA	_____	_____	_____	_____
0190	512 ATTD	512SP20-0002 MAINTENANCE OF TRAFFIC MOT	LUMP SUM	LUMP SUM	_____	_____	_____
0200	515	515SD20-0011 FLEX. PAVE. TIE-IN PLANING 0"-2"	274.560 SY	_____	_____	_____	_____
0210	515	515SD20-0013 FLEXIBLE PAVE.PLANING 0"- 2"	219,024.130 SY	_____	_____	_____	_____
0220	515	515SD20-0014 FLEXIBLE PAVEMENT PLANING ABOVE 2"-4"	9,949.870 SY	_____	_____	_____	_____
0230	ATTD	515SX20-0001 FLEX.PAVE.EDGE PLANING MAINT	140.800 SY	_____	_____	_____	_____
0240	700	700SD20-0118 14/1 CONDUCTOR CABLE ENCLOSED	5,373.000 LF	_____	_____	_____	_____
0250	700	700SD20-0183 CONDUIT METAL 1"	45.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000125648N01

Oversight/State Project No.: PM9K-053-F25, N501

Order No.: 971

Federal Project No.: NONE

Contractor: \_\_\_\_\_

SECTION: 0001

REGULAR BID ITEM

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0260	703	703SD20-0042 LOOP SAW CUT 3/8"	1,782.000 LF	_____	_____	_____	_____
0270	703	703SD20-0043 LOOP SAW CUT 5/8"	405.000 LF	_____	_____	_____	_____
0280	704	704SD20-0006 TYPE B CLASS I PVMT LINE MRKG 4"	76,948.000 LF	_____	_____	_____	_____
0290	704	704SD20-0007 TYPE B CLASS I PVMT LINE MRKG 6"	9,027.000 LF	_____	_____	_____	_____
0300	704	704SD20-0008 TYPE B CLASS I PVMT LINE MRKG 8"	370.000 LF	_____	_____	_____	_____
0310	704	704SD20-0009 TYPE B CLASS I PVMT LINE MRKG 12"	722.000 LF	_____	_____	_____	_____
0320	704	704SD20-0010 TYPE B CLASS I PVMT LINE MRKG 24"	2,343.000 LF	_____	_____	_____	_____
0330	704	704SD20-0035 PVMT MSG. MARK. "ONLY" TY B, CL. I, 6'	2.000 EA	_____	_____	_____	_____
0340	704	704SD20-0047 PVMT SYMB MRKG SGL TURN ARR. TY B CL I	93.000 EA	_____	_____	_____	_____
0350	704	704SD20-0049 MRKG DBL TURN ARR. THRU/LT OR RT TY A	9.000 EA	_____	_____	_____	_____
0360	704	704SD20-0050 DBL TURN ARR. THRU/LT OR RT TY B, CL I	13.000 EA	_____	_____	_____	_____
0370	704	704SD20-0058 SYMG MRKG LANE REDUCTION ARROW TY A	2.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000125648N01

Oversight/State Project No.: PM9K-053-F25, N501

Order No.: 971

Federal Project No.: NONE

Contractor: \_\_\_\_\_

SECTION: 0001 REGULAR BID ITEM

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0380	704	704SD20-0059 SYMB MRKG LANE REDUCTION ARR TY B CL I	2.000 EA	_____	_____	_____	_____
0390	704	704SD20-0095 SYMB MRKG BICYCLE THRU ARROW TY B CL I	38.000 EA	_____	_____	_____	_____
0400	704	704SD20-0101 SYMB MRKG HELMETED BICYCLIST TY B CL I	38.000 EA	_____	_____	_____	_____
0410	704	704SD20-0107 PVMT MSG. MARK. "ONLY" TY B, CL. I, 8'	4.000 EA	_____	_____	_____	_____
<b>Section: 0001</b>				<b>Total:</b>	_____	_____	_____

SECTION: 0002 ALTERNATE ITEM

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0420	ATTD	305SX20-0006 SELECT MATERIAL ALTERNATE SHOULDER MATERIALS	1.000 TON	_____	_____	_____	_____
<b>Section: 0002</b>				<b>Total:</b>	_____	_____	_____
				<b>Total Bid:</b>	_____	_____	_____