

Schedule of Items

Proposal ID: CM325PMB125044    Oversight/State Project No.: PM3B-M09-F25, N501  
 Order No.: 332    Federal Project No.: PM03(384)

Contractor: \_\_\_\_\_

SECTION: 0001    REGULAR BID ITEMS

Cat Alt Set ID:    Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	308	308SD20-0008 AGGR. MATL. NO. 25 OR 26	5,392.400 TON	_____	_____	_____	_____
0020	310	310SD20-0001 TACK COAT	43,843.000 GAL	_____	_____	_____	_____
0030	315	315SD20-0100 ASPHALT CONCRETE BASE COURSE BM-25.0	4,590.430 TON	_____	_____	_____	_____
0040	315	315SP20-0049 ASPH. CONC. BMD P+VO SM-9.5D	17,586.810 TON	_____	_____	_____	_____
0050	315	315SP20-0051 ASPH. CONC. BMD P+VO SM-12.5D	30,366.610 TON	_____	_____	_____	_____
0060	ATTD	316SX20-0004 PAVEMENT LIQUID ASPHALT COATING (PAVEMENT MARKER GROOVES)	405.000 SY	_____	_____	_____	_____
0070	512	512SD20-0027 FLAGGER SERVICE	1,600.000 HR	_____	_____	_____	_____
0080	512	512SD20-0042 ERADICATE LINEAR PVMT MRKG	123,898.000 LF	_____	_____	_____	_____
0090	512	512SD20-0043 ERADICATE NONLINEAR PVMT MRKG	247.000 SF	_____	_____	_____	_____
0100	512	512SD20-0046 TEMP. PVMT MRKG TY. A, 4"	880,647.000 LF	_____	_____	_____	_____
0110	512	512SD20-0050 TEMP. PVMT MRKG TY. A, 24"	1,370.000 LF	_____	_____	_____	_____
0120	512	512SD20-0051 TEMP. PVMT. SYMB. MRKG THRU ARROW TY. A	14.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: CM325PMB125044 Oversight/State Project No.: PM3B-M09-F25, N501

Order No.: 332

Federal Project No.: PM03(384)

Contractor: \_\_\_\_\_

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0130	512	512SD20-0052 TEMP. PVMT. SYMB. MRKG SNGL TURN ARROW TY. A	39.000 EA	_____	_____	_____	_____
0140	512	512SD20-0053 TEMP. PVMT. SYMB. MRKG R/R CROSSING TY. A	1.000 EA	_____	_____	_____	_____
0150	ATTD	512SP20-0001 PORTABLE TEMPORARY RUMBLE STRIP ARRAY	150.000 DAY	_____	_____	_____	_____
0160	ATTD	512SP20-0002 MAINTENANCE OF TRAFFIC PLANT MIX	LUMP SUM	LUMP SUM	_____	_____	_____
0170	515	515SD20-0011 FLEX. PAVE. TIE-IN PLANING 0"-2"	2,050.400 SY	_____	_____	_____	_____
0180	515	515SD20-0013 FLEXIBLE PAVE.PLANING 0"- 2"	368,478.610 SY	_____	_____	_____	_____
0190	515	515SD20-0014 FLEXIBLE PAVEMENT PLANING ABOVE 2"-4"	19,958.400 SY	_____	_____	_____	_____
0200	704	704SD20-0001 TYPE A PVMT LINE MRKG 4"	173,726.000 LF	_____	_____	_____	_____
0210	704	704SD20-0002 TYPE A PVMT LINE MRKG 6"	57,038.000 LF	_____	_____	_____	_____
0220	704	704SD20-0006 TYPE B CLASS I PVMT LINE MRKG 4"	5,614.000 LF	_____	_____	_____	_____
0230	704	704SD20-0007 TYPE B CLASS I PVMT LINE MRKG 6"	193,689.000 LF	_____	_____	_____	_____
0240	704	704SD20-0009 TYPE B CLASS I PVMT LINE MRKG 12"	1,334.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: CM325PMB125044 Oversight/State Project No.: PM3B-M09-F25, N501

Order No.: 332

Federal Project No.: PM03(384)

Contractor: \_\_\_\_\_

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0250	704	704SD20-0014 TYPE B CLASS II PVMT LINE MRKG 12"	712.000 LF	_____	_____	_____	_____
0260	704	704SD20-0015 TYPE B CLASS II PVMT LINE MRKG 24"	1,477.000 LF	_____	_____	_____	_____
0270	704	704SD20-0027 TYPE B CLASS VI PVMT LINE MRKG 6"	17,812.000 LF	_____	_____	_____	_____
0280	704	704SD20-0028 TYPE B CLASS VI PVMT LINE MRKG 8"	2,720.000 LF	_____	_____	_____	_____
0290	704	704SD20-0029 TYPE B CLASS VI PVMT LINE MRKG 12"	2,270.000 LF	_____	_____	_____	_____
0300	ATTD	704SD20-0032 INLAID PAVEMENT MARKER ASPHALT	1,113.000 EA	_____	_____	_____	_____
0310	704	704SD20-0042 PVMT MSG. MARK. R/R CROSSING TY. B, CL. II	1.000 EA	_____	_____	_____	_____
0320	704	704SD20-0045 PVMT SYMB MRKG THRU ARROW TY B, CL II	7.000 EA	_____	_____	_____	_____
0330	704	704SD20-0048 PVMT SYMB MRKG SGL TURN ARR. TY B CL II	27.000 EA	_____	_____	_____	_____
0340	ATTD	704SX20-0005 PAVE. MESSAGE MARKING - VARIOUS	11.000 EA	_____	_____	_____	_____
<b>Section: 0001</b>				<b>Total:</b>	_____	_____	_____

Schedule of Items

Proposal ID: CM325PMB125044 Oversight/State Project No.: PM3B-M09-F25, N501

Order No.: 332

Federal Project No.: PM03(384)

Contractor: \_\_\_\_\_

SECTION: 0002 ALTERNATE BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0350	ATTD	305SX20-0006 SELECT MATERIAL ALTERNATE SHOULDER MATERIA	1.000 TON	_____	_____	_____	_____
<b>Section: 0002</b>				<b>Total:</b>		_____	_____
				<b>Total Bid:</b>		_____	_____