

Schedule of Items

Proposal ID: CM625PMG125781 Oversight/State Project No.: PM6G-966-F25, P401

Order No.: 657

Federal Project No.: PM06(406)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	ATTD	305SP20-0003 AGR. BASE MAT. TY.I OR II NO. 21A OR 21B	3,737.100 TON	_____	_____	_____	_____
0020	310	310SD20-0001 TACK COAT	39,639.000 GAL	_____	_____	_____	_____
0030	315	315SD20-0040 ASPH. CONC. TY. IM-19.0A MAINT	3,149.600 TON	_____	_____	_____	_____
0040	ATTD	315SP20-0006 PAVEMENT SHOULDER WEDGE PREP. CONST	169,910.000 LF	_____	_____	_____	_____
0050	315	315SP20-0048 ASPH. CONC. BMD P+VO SM- 9.5A	33,699.140 TON	_____	_____	_____	_____
0060	323	323SD20-0030 TRAVEL LANE PATCHING (PATCH MIX TYPE) IM-19.0A	2,370.000 TON	_____	_____	_____	_____
0070	512	512SD20-0042 ERADICATE LINEAR PVMT MRKG	209,020.000 LF	_____	_____	_____	_____
0080	512	512SD20-0043 ERADICATE NONLINEAR PVMT MRKG	678.000 SF	_____	_____	_____	_____
0090	512	512SD20-0046 TEMP. PVMT MRKG TY. A, 4"	494,912.000 LF	_____	_____	_____	_____
0100	ATTD	512SP20-0002 MAINTENANCE OF TRAFFIC PLANT MIX	LUMP SUM	LUMP SUM	_____	_____	_____
0110	ATTD	512SX20-0045 SAFETY SHORT-TERM ALTERNATING LANE CLOSURE FLAGGING/AFAD SERVICE	2,397.000 HR	_____	_____	_____	_____
0120	515	515SD20-0011 FLEX. PAVE. TIE-IN PLANING 0"-2"	4,229.800 SY	_____	_____	_____	_____

Schedule of Items

Proposal ID: CM625PMG125781 Oversight/State Project No.: PM6G-966-F25, P401
 Order No.: 657 Federal Project No.: PM06(406)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0130	515	515SD20-0013 FLEXIBLE PAVE.PLANING 0"-2"	28,641.000 SY	_____	_____	_____	_____
0140	704	704SD20-0006 TYPE B CLASS I PVMT LINE MRKG 4"	221,118.000 LF	_____	_____	_____	_____
0150	704	704SD20-0007 TYPE B CLASS I PVMT LINE MRKG 6"	13,526.000 LF	_____	_____	_____	_____
0160	704	704SD20-0010 TYPE B CLASS I PVMT LINE MRKG 24"	244.000 LF	_____	_____	_____	_____
0170	704	704SD20-0038 PVMT MSG. MARK. "SCHOOL" TY B, CL I, 6'	1.000 EA	_____	_____	_____	_____
0180	704	704SD20-0047 PVMT SYMB MRKG SGL TURN ARR. TY B CL I	1.000 EA	_____	_____	_____	_____
0190	704	704SD20-0050 DBL TURN ARR.THRU/LT OR RT TY B, CL I	1.000 EA	_____	_____	_____	_____
0200	704	704SX20-0005 PAVE. MESSAGE MARKING STOP AHEAD	1.000 EA	_____	_____	_____	_____
Section: 0001				Total:	_____	_____	_____

Schedule of Items

Proposal ID: CM625PMG125781 Oversight/State Project No.: PM6G-966-F25, P401

Order No.: 657

Federal Project No.: PM06(406)

Contractor: _____

SECTION: 0002 ALTERNATE ITEM

Cat Alt Set ID: _____ Cat Alt Mbr ID: _____

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0210	ATTD	305SX20-0006 SELECT MATERIAL ALTERNATE SHOULDER MATERIAL	1.000 TON	_____	_____	_____	_____
Section: 0002				Total:		_____	_____
				Total Bid:		_____	_____