

Schedule of Items

Proposal ID: C0000120440C01 Oversight/State Project No.: 0095-106-178,C501

Order No.: M39

Federal Project No.: NHPP-095-1(385)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	302	302SD20-0013 ENDWALL EW-12	3.000 EA	_____	_____	_____	_____
0020	303	303SD20-0001 REGULAR EXCAVATION	170.000 CY	_____	_____	_____	_____
0030	303	303SD20-0029 SILTATION CONTROL EXCAVATION	322.000 CY	_____	_____	_____	_____
0040	303	303SD20-0031 INLET PROTECTION TYPE B	2.000 EA	_____	_____	_____	_____
0050	303	303SD20-0034 TEMP. SILT FENCE TYPE A	1,826.000 LF	_____	_____	_____	_____
0060	308	308SD20-0012 AGGR. BASE MATL. TY. I NO. 21B	95.000 TON	_____	_____	_____	_____
0070	315	315SD20-0003 ASPHALT CONCRETE TY. SM-12.5E CONST	314.000 TON	_____	_____	_____	_____
0080	315	315SD20-0006 ASPHALT CONCRETE TY. IM-19.0E CONST	363.000 TON	_____	_____	_____	_____
0090	315	315SD20-0010 ASPHALT CONCRETE BM-25.0	95.000 TON	_____	_____	_____	_____
0100	315	315SD20-0015 RUMBLE STRIP CYLINDRICAL ASPHALT	131.000 LF	_____	_____	_____	_____
0110	315	315SX20-0011 SAW-CUT ASPH CONC Saw Cut	458.000 LF	_____	_____	_____	_____
0120	ATTD	410SX20-0011 PIER PROTECTION SYSTEM 54", CONST	58.000 LF	_____	_____	_____	_____
0130	414	414SD20-0004 EROSION CTRL. STONE CL. I, EC-1	5.000 SY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000120440C01

Oversight/State Project No.: 0095-106-178,C501

Order No.: M39

Federal Project No.: NHPP-095-1(385)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0140	501	501SD20-0001 UNDERDRAIN UD-1	263.000 LF	_____	_____	_____	_____
0150	501	501SD20-0007 CROSSDRAIN CD-2	10.000 LF	_____	_____	_____	_____
0160	501	501SD20-0009 OUTLET PIPE	85.000 LF	_____	_____	_____	_____
0170	502	502SD20-0020 CURB, ASPHALT MC-3B	41.000 LF	_____	_____	_____	_____
0180	505	505SD20-0011 GUARDRAIL GR-MGS1	262.000 LF	_____	_____	_____	_____
0190	505	505SD20-0017 GUARDRAIL TERMINAL GR-MGS2	1.000 EA	_____	_____	_____	_____
0200	505	505SD20-0019 GUARDRAIL HEIGHT TRANSITION GR-MGS4	1.000 EA	_____	_____	_____	_____
0210	505	505SD20-0030 GUARDRAIL GR-2	35.000 LF	_____	_____	_____	_____
0220	505	505SD20-0053 FIXED OBJECT ATTACH. GR-FOA-2 TY. I	1.000 EA	_____	_____	_____	_____
0230	505	505SD20-0055 FIXED OBJECT ATTACH. GR-FOA-5	2.000 EA	_____	_____	_____	_____
0240	505	505SD20-0073 REMOVE EXISTING GUARDRAIL	414.000 LF	_____	_____	_____	_____
0250	505	505SP20-0001 IMPACT ATTEN. TY.1 TL-3, LOW MAINTENANCE	1.000 EA	_____	_____	_____	_____
0260	508	508SD20-0004 DEMO. OF PAVEMENT FLEXIBLE	103.000 SY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000120440C01 Oversight/State Project No.: 0095-106-178,C501

Order No.: M39

Federal Project No.: NHPP-095-1(385)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0270	510	510SX20-0033 ADJUST EXIST. DROP INLET Adjust Existing Inlet.	1.000 EA	_____	_____	_____	_____
0280	511	511SD20-0001 ALLAYING DUST	25.000 HR	_____	_____	_____	_____
0290	512	512SD20-0014 TEMPORARY SIGN	344.000 SF	_____	_____	_____	_____
0300	512	512SD20-0023 TRUCK MOUNTED ATTENUATOR	192.000 HR	_____	_____	_____	_____
0310	512	512SD20-0024 GROUP 2 CHANNELIZING DEVICES	180.000 DAY	_____	_____	_____	_____
0320	512	512SD20-0025 PORT.CHANGEABLE MESS. SIGN	1,008.000 HR	_____	_____	_____	_____
0330	512	512SD20-0026 ELECTRONIC ARROW BOARD	192.000 HR	_____	_____	_____	_____
0340	512	512SD20-0029 WARNING LIGHT TY. B	60.000 DAY	_____	_____	_____	_____
0350	512	512SD20-0031 TRAFFIC BARRIER SER. CONC. MB-7D PC	850.000 LF	_____	_____	_____	_____
0360	512	512SD20-0042 ERADICATE LINEAR PVMT MRKG	2,119.000 LF	_____	_____	_____	_____
0370	513	513SD20-0001 MOBILIZATION	LUMP SUM	LUMP SUM	_____	_____	_____
0380	515	515SD20-0014 FLEXIBLE PAVEMENT PLANING ABOVE 2"-4"	2,326.000 SY	_____	_____	_____	_____
0390	515	515SD20-0015 FLEXIBLE PAVEMENT PLANING ABOVE 4"	275.000 SY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000120440C01 Oversight/State Project No.: 0095-106-178,C501

Order No.: M39

Federal Project No.: NHPP-095-1(385)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0400	517	517SD20-0001 CONSTRUCTION SURVEYING CONSTR.	LUMP SUM	LUMP SUM			
0410	602	602SD20-0004 TOPSOIL CLASS B	73.000 CY				
0420	603	603SD20-0002 TEMPORARY SEED	18.000 LB				
0430	603	603SD20-0003 REGULAR SEED	48.000 LB				
0440	603	603SD20-0004 OVERSEEDING	38.000 LB				
0450	603	603SD20-0005 LEGUME SEED	2.000 LB				
0460	603	603SD20-0006 LEGUME OVERSEEDING	2.000 LB				
0470	603	603SD20-0008 HYDRAULIC EROSION CONTROL PRODUCT TYPE 2	1,057.000 SY				
0480	603	603SD20-0009 HYDRAULIC EROSION CONTROL PRODUCT TYPE 3	871.000 SY				
0490	603	603SD20-0014 FERTILIZER NITROGEN - N	18.000 LB				
0500	603	603SD20-0015 FERTILIZER PHOSPHOROUS - P	12.000 LB				
0510	603	603SD20-0016 FERTILIZER POTASSIUM - K	12.000 LB				
0520	603	603SD20-0017 LIME	1.000 TON				

Schedule of Items

Proposal ID: C0000120440C01 Oversight/State Project No.: 0095-106-178,C501

Order No.: M39

Federal Project No.: NHPP-095-1(385)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0530	700	700SD20-0003 REMOVE EXISTING 1 POST SIGN STRUCTURE	1.000 EA	_____	_____	_____	_____
0540	700	700SD20-0037 SIGN POST STP-1, 2 1/2", 12 GAUGE	10.000 LF	_____	_____	_____	_____
0550	700	700SD20-0038 CONC. FOUND. STP-1, TY. A	1.000 EA	_____	_____	_____	_____
0560	701	701SD20-0001 SIGN PANEL	16.000 SF	_____	_____	_____	_____
0570	702	702SD20-0009 BARRIER DELINEATOR	12.000 EA	_____	_____	_____	_____
0580	704	704SD20-0012 TYPE B CLASS II PVMT LINE MRKG 6"	707.000 LF	_____	_____	_____	_____
0590	704	704SD20-0014 TYPE B CLASS II PVMT LINE MRKG 12"	359.000 LF	_____	_____	_____	_____
0600	704	704SD20-0027 TYPE B CLASS VI PVMT LINE MRKG 6"	1,207.000 LF	_____	_____	_____	_____
0610	ATTD	704SD20-0032 INLAID PAVEMENT MARKER ASPHALT	35.000 EA	_____	_____	_____	_____
Section: 0001				Total:		_____	
				Total Bid:		_____	