

Schedule of Items

Proposal ID: C0000124570B63

Oversight/State Project No.: 0095-123-162, B663, B664

Order No.: M42

Federal Project No.: BFP-095-1(397)

Contractor: _____

SECTION: 0001 BRIDGE ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	315	315SD20-0015 RUMBLE STRIP CYLINDRICAL ASPHALT	2,750.000 LF	_____	_____	_____	_____
0020	315	315SD20-0036 ASPH. CONC. TY. SM-12.5E MAINT	349.000 TON	_____	_____	_____	_____
0030	315	315SD20-0043 ASPH. CONC. TY. IM-19.0D MAINT	2,361.000 TON	_____	_____	_____	_____
0040	404	404SD20-0020 BRIDGE DECK GROOVING MAINT.	3,103.000 SY	_____	_____	_____	_____
0050	411	411SX20-0001 PRE. & SPOT COAT EX. STR. (VA STRUCT. NO 2820)	778.000 SF	_____	_____	_____	_____
0060	411	411SX20-0001 PRE. & SPOT COAT EX. STR. (VA STRUCT. NO. 2836)	987.000 SF	_____	_____	_____	_____
0070	412	412SD20-0013 CRACK REPAIR TYPE B	126.000 LF	_____	_____	_____	_____
0080	412	412SD20-0017 EMBEDDED GALVANIC ANODES	160.000 EA	_____	_____	_____	_____
0090	412	412SD20-0032 H.E.S. PATCHING TYPE A	12.000 SY	_____	_____	_____	_____
0100	412	412SD20-0034 H.E.S. PATCHING TYPE B	40.000 SY	_____	_____	_____	_____
0110	412	412SD20-0048 JACKING AND BLOCKING BEAM	49.000 EA	_____	_____	_____	_____
0120	412	412SD20-0061 CONCRETE SUBSTRUCT. SURFACE REPAIR	4.000 SY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000124570B63

Oversight/State Project No.: 0095-123-162, B663, B664

Order No.: M42

Federal Project No.: BFP-095-1(397)

Contractor: _____

SECTION: 0001

BRIDGE ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0130	412,426, ATTD	412SX20-0009 SUPERSTR. WID./REPAIR CLEAN AND PAINT BEARING ASSEMBLY	36.000 EA	_____	_____	_____	_____
0140	412,426, ATTD	412SX20-0009 SUPERSTR. WID./REPAIR RESET EXPANSION BEARING	13.000 EA	_____	_____	_____	_____
0150	412,426, ATTD	412SX20-0012 SUPERSTR. WID./REPAIR STRUCTURAL STEEL REPAIR	10,355.000 LB	_____	_____	_____	_____
0160	412, ATTD	412SX20-0028 RECONSTR. EXPAN. JOINT (LMC-VE)	308.000 LF	_____	_____	_____	_____
0170	416	416SD20-0003 WATERPROOFING – EPOXY RESIN TYPE EP-3B/EP-3T	256.000 SY	_____	_____	_____	_____
0180	421	421SD20-0006 ELASTOMERIC EXPANS. DAM 0" TO 2" SPRSTR MAINT	308.000 LF	_____	_____	_____	_____
0190	425	425SD20-0001 REMOVE ASPHALT CONCRETE OVERLAY	3,103.000 SY	_____	_____	_____	_____
0200	425	425SD20-0002 TYPE A MILLING 1/2"	3,103.000 SY	_____	_____	_____	_____
0210	425	425SD20-0015 PLACE VERY EARLY MOD.CONC.OVERLAY	3,103.000 SY	_____	_____	_____	_____
0220	425	425SD20-0022 TYPE A HYDRO-DEMOLITION 1/2"	3,103.000 SY	_____	_____	_____	_____
0230	425, ATTD	425SX20-0004 FURN VERY EARLY LATEX MOD CONC. (2 3/4" - 3 1/4")	122.000 CY	_____	_____	_____	_____
0240	425, ATTD	425SX20-0004 FURN VERY EARLY LATEX MOD CONC. (3 1/2" TO 4")	166.000 CY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000124570B63

Oversight/State Project No.: 0095-123-162, B663, B664

Order No.: M42

Federal Project No.: BFP-095-1(397)

Contractor: _____

SECTION: 0001

BRIDGE ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0250	426	426SD20-0001 REPLACE BEARING	36.000 EA	_____	_____	_____	_____
0260	426	426SD20-0007 ULTRASONIC IMPACT TREATMENT	67.000 LF	_____	_____	_____	_____
0270	426	426SD20-0019 FIELD WELDING - FILLET WELD 1/4"	84.000 LF	_____	_____	_____	_____
0280	430	430SX20-0001 NBIS ACCESS, UNDER BRIDGE (STR. NO. 2820)	3.000 DAY	_____	_____	_____	_____
0290	430	430SX20-0001 NBIS ACCESS, UNDER BRIDGE (STRUCT. NO. 2836)	3.000 DAY	_____	_____	_____	_____
0300	512	512SD20-0013 TYPE 3 BARRICADE 8'	3.000 EA	_____	_____	_____	_____
0310	512	512SD20-0014 TEMPORARY SIGN	1,679.000 SF	_____	_____	_____	_____
0320	512	512SD20-0023 TRUCK MOUNTED ATTENUATOR	1,650.000 HR	_____	_____	_____	_____
0330	512	512SD20-0024 GROUP 2 CHANNELIZING DEVICES	13,560.000 DAY	_____	_____	_____	_____
0340	512	512SD20-0025 PORT.CHANGEABLE MESS. SIGN	2,688.000 HR	_____	_____	_____	_____
0350	512	512SD20-0026 ELECTRONIC ARROW BOARD	840.000 HR	_____	_____	_____	_____
0360	512	512SD20-0027 FLAGGER SERVICE	2,430.000 HR	_____	_____	_____	_____
0370	512	512SD20-0042 ERADICATE LINEAR PVMT MRKG	36,090.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000124570B63

Oversight/State Project No.: 0095-123-162, B663, B664

Order No.: M42

Federal Project No.: BFP-095-1(397)

Contractor: _____

SECTION: 0001

BRIDGE ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0380	512	512SD20-0042 ERADICATE LINEAR PVMT MRKG	20,200.000 LF	_____	_____	_____	_____
0390	512	512SD20-0062 TEMP. PVMT MRKG TY. D, CL. III, 6"	10,970.000 LF	_____	_____	_____	_____
0400	512	512SD20-0063 TEMP. PVMT MRKG TY. D, CL. III, 8"	26,420.000 LF	_____	_____	_____	_____
0410	512	512SD20-0064 TEMP. PVMT MRKG TY. D, CL. III, 12"	1,600.000 LF	_____	_____	_____	_____
0420	ATTD	512SX20-0019 TRAFFIC CONTROL ADDITIONAL PCMS	2.000 EA	_____	_____	_____	_____
0430	ATTD	512SX20-0019 TRAFFIC CONTROL ADDITIONAL SENSOR	2.000 EA	_____	_____	_____	_____
0440	ATTD	512SX20-0030 WORK AREA QUEUE WARNING SYSTEM	91.000 DAY	_____	_____	_____	_____
0450	513	513SD20-0001 MOBILIZATION	LUMP SUM	LUMP SUM	_____	_____	_____
0460	515	515SD20-0012 FLEX. PAVE.TIE-IN PLANING ABOVE 2"-4"	2,534.000 SY	_____	_____	_____	_____
0470	515	515SD20-0015 FLEXIBLE PAVEMENT PLANING ABOVE 4"	8,585.000 SY	_____	_____	_____	_____
0480	517	517SD20-0001 CONSTRUCTION SURVEYING CONSTR.	LUMP SUM	LUMP SUM	_____	_____	_____
0490	704	704SD20-0027 TYPE B CLASS VI PVMT LINE MRKG 6"	26,045.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000124570B63

Oversight/State Project No.: 0095-123-162, B663, B664

Order No.: M42

Federal Project No.: BFP-095-1(397)

Contractor: _____

SECTION: 0001 BRIDGE ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0500	704	704SD20-0029 TYPE B CLASS VI PVMT LINE MRKG 12"	2,100.000 LF	_____	_____	_____	_____
0510	704	704SD20-0031 TYPE B CLASS VI CONTRAST PVMT LINE MRKG 6"	1,120.000 LF	_____	_____	_____	_____
Section: 0001				Total:		_____	
				Total Bid:		_____	