

Schedule of Items

Proposal ID: C0000123071M01 Oversight/State Project No.: 0354-051-596, D601, M501
 Order No.: M41 Federal Project No.: STP-BR06(296)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	301	301SD20-0001 CLEARING AND GRUBBING FOR RTE 354 (UPC 123071)	LUMP SUM	LUMP SUM			
0020	301	301SD20-0001 CLEARING AND GRUBBING FOR RTE 636 (UPC 123070)	LUMP SUM	LUMP SUM			
0030	302	302SD20-0670 TEMP. DIVE. CHANNEL LINING CL. A	140.000 SY				
0040	302	302SD20-0672 TEMP. DIVE. CHANNEL EXCAVATION	290.000 CY				
0050	302	302SX20-0005 PRECAST BOX CULVERT PRECAST 8'x6' BOX CULVERT	124.000 LF				
0060	303	303SD20-0001 REGULAR EXCAVATION	77.000 CY				
0070	303	303SD20-0007 BORROW EXCAVATION	320.000 CY				
0080	303	303SD20-0017 MINOR STR. EXCAV. BOX CULVERT	1,416.000 CY				
0090	303	303SD20-0019 EROSION CONTROL MULCH	200.000 SY				
0100	303	303SD20-0028 DEWATERING BASIN EC-8	4.000 EA				
0110	303	303SD20-0029 SILTATION CONTROL EXCAVATION	215.000 CY				
0120	303	303SD20-0034 TEMP. SILT FENCE TYPE A	1,189.000 LF				
0130	308	308SD20-0012 AGGR. BASE MATL. TY. I NO. 21B	261.000 TON				

Schedule of Items

Proposal ID: C0000123071M01 Oversight/State Project No.: 0354-051-596, D601, M501
 Order No.: M41 Federal Project No.: STP-BR06(296)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0140	315	315SD20-0001 ASPHALT CONCRETE TY. SM-12.5A CONST	42.000 TON	_____	_____	_____	_____
0150	315	315SD20-0004 ASPHALT CONCRETE TY. IM-19.0A CONST	42.000 TON	_____	_____	_____	_____
0160	315	315SX20-0011 SAW-CUT ASPH CONC (FULL DEPTH)	83.000 LF	_____	_____	_____	_____
0170	401	401SD20-0007 COFFERDAM	4.000 EA	_____	_____	_____	_____
0180	402	402SD20-0004 TEMPORARY SHEET PILING	7,300.000 SF	_____	_____	_____	_____
0190	ATTD	410SX20-0014 BRIDGE INCIDENTALS EXIST. SHEET PILE REMOVAL AND COORDINATION FOR ROUTE 636 PROJECT	LUMP SUM	LUMP SUM	_____	_____	_____
0200	414	414SD20-0003 EROSION CTRL. STONE CL. I, EC-1	327.000 TON	_____	_____	_____	_____
0210	414	414SD20-0012 DRY RIPRAP CL.I 26"	207.000 TON	_____	_____	_____	_____
0220	502	502SD20-0036 MEDIAN BARRIER MB-7D	96.000 LF	_____	_____	_____	_____
0230	503	503SD20-0002 R/W MONUMENT RM-2	10.000 EA	_____	_____	_____	_____
0240	504	504SD20-0008 BEDDING MATL. OPEN GRADED COURSE AGGREGATE NO. 3	348.000 TON	_____	_____	_____	_____
0250	505	505SD20-0011 GUARDRAIL GR-MGS1	550.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000123071M01

Oversight/State Project No.: 0354-051-596, D601, M501

Order No.: M41

Federal Project No.: STP-BR06(296)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0260	505	505SD20-0017 GUARDRAIL TERMINAL GR-MGS2	2.000 EA	_____	_____	_____	_____
0270	505	505SD20-0019 GUARDRAIL HEIGHT TRANSITION GR-MGS4	2.000 EA	_____	_____	_____	_____
0280	505	505SD20-0039 GUARDRAIL TER.SITE PREPARATION	2.000 EA	_____	_____	_____	_____
0290	505	505SD20-0073 REMOVE EXISTING GUARDRAIL	178.000 LF	_____	_____	_____	_____
0300	507	507SD20-0027 HIGH VISIBILITY FENCE, 4 FEET ORANGE SAFETY FENCE FOR WETLAND DELINEATION	400.000 LF	_____	_____	_____	_____
0310	508	508SD20-0004 DEMO. OF PAVEMENT FLEXIBLE	603.000 SY	_____	_____	_____	_____
0320	512	512SD20-0013 TYPE 3 BARRICADE 8'	22.000 EA	_____	_____	_____	_____
0330	512	512SD20-0014 TEMPORARY SIGN	1,044.000 SF	_____	_____	_____	_____
0340	512	512SD20-0015 AGGREGATE MATERIAL NO. 25 OR 26	85.000 TON	_____	_____	_____	_____
0350	512	512SD20-0024 GROUP 2 CHANNELIZING DEVICES	3,500.000 DAY	_____	_____	_____	_____
0360	512	512SD20-0025 PORT.CHANGEABLE MESS. SIGN	14,000.000 HR	_____	_____	_____	_____
0370	513	513SD20-0001 MOBILIZATION FOR RTE 354 (UPC 123071)	LUMP SUM	LUMP SUM	_____	_____	_____

Schedule of Items

Proposal ID: C0000123071M01 Oversight/State Project No.: 0354-051-596, D601, M501
 Order No.: M41 Federal Project No.: STP-BR06(296)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0380	513	513SD20-0001 MOBILIZATION FOR RTE 636 (UPC 123070)	LUMP SUM	LUMP SUM			
0390	517	517SD20-0002 CONSTRUCTION SURVEYING MIN. PLAN FOR RTE 354 (UPC 123071)	LUMP SUM	LUMP SUM			
0400	517	517SD20-0002 CONSTRUCTION SURVEYING MIN. PLAN FOR RTE 636 (UPC 123070)	LUMP SUM	LUMP SUM			
0410	602	602SD20-0003 TOPSOIL CLASS B 2"	0.370 ACRE				
0420	603	603SD20-0002 TEMPORARY SEED	37.000 LB				
0430	603	603SD20-0003 REGULAR SEED	56.000 LB				
0440	603	603SD20-0004 OVERSEEDING	45.000 LB				
0450	603	603SD20-0005 LEGUME SEED	5.000 LB				
0460	603	603SD20-0006 LEGUME OVERSEEDING	4.000 LB				
0470	603	603SD20-0007 HYDRAULIC EROSION CONTROL PRODUCT TYPE 1	1,229.000 SY				
0480	603	603SD20-0009 HYDRAULIC EROSION CONTROL PRODUCT TYPE 3	2,876.000 SY				
0490	603	603SD20-0014 FERTILIZER NITROGEN - N	36.000 LB				
0500	603	603SD20-0015 FERTILIZER PHOSPHOROUS - P	49.000 LB				

Schedule of Items

Proposal ID: C0000123071M01

Oversight/State Project No.: 0354-051-596, D601, M501

Order No.: M41

Federal Project No.: STP-BR06(296)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0510	603	603SD20-0016 FERTILIZER POTASSIUM - K	25.000 LB	_____	_____	_____	_____
0520	603	603SD20-0017 LIME	1.700 TON	_____	_____	_____	_____
0530	ATTD	605SX20-0001 WETLAND MITIGATION PLANTING NONTIDAL WETLAND TEMPORARY IMPACT RESTORATION FOR RTE 354 (UPC 123071)	LUMP SUM	LUMP SUM	_____	_____	_____
0540	606	606SD20-0001 ROLLED EROSION CTRL PRODUCT EC-2 TYPE 1	12.000 SY	_____	_____	_____	_____
0550	700	700SD20-0034 SIGN POST STP-1, 2", 14 GAUGE	82.000 LF	_____	_____	_____	_____
0560	700	700SD20-0038 CONC. FOUND. STP-1, TY. A	8.000 EA	_____	_____	_____	_____
0570	701	701SD20-0001 SIGN PANEL	16.000 SF	_____	_____	_____	_____
0580	704	704SD20-0007 TYPE B CLASS I PVMT LINE MRKG 6"	400.000 LF	_____	_____	_____	_____

Section: 0001

Total: _____

Total Bid: _____