

Schedule of Items

Proposal ID: C0000126627B01

Oversight/State Project No.: 1212-095-132,B674,C501

Order No.: M65

Federal Project No.: FEMA

Contractor: \_\_\_\_\_

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	301	301SD20-0002 CLEARING AND GRUBBING	0.620 ACRE	_____	_____	_____	_____
0020	303	303SD20-0028 DEWATERING BASIN EC-8	5.000 EA	_____	_____	_____	_____
0030	303	303SD20-0029 SILTATION CONTROL EXCAVATION	122.000 CY	_____	_____	_____	_____
0040	303	303SD20-0034 TEMP. SILT FENCE TYPE A	621.000 LF	_____	_____	_____	_____
0050	308	308SD20-0012 AGGR. BASE MATL. TY. I NO. 21B	21.000 TON	_____	_____	_____	_____
0060	315	315SD20-0004 ASPHALT CONCRETE TY. IM-19.0A CONST	8.000 TON	_____	_____	_____	_____
0070	315	315SD20-0007 ASPHALT CONCRETE TY. SM-9.5A CONST	26.000 TON	_____	_____	_____	_____
0080	315	315SD20-0010 ASPHALT CONCRETE BM-25.0	27.000 TON	_____	_____	_____	_____
0090	ATTD	315SX20-0011 SAW-CUT ASPH CONC FULL DEPTH SAWCUT	50.000 LF	_____	_____	_____	_____
0100	401	401SD20-0001 STRUCTURE EXCAVATION CONST.	535.000 CY	_____	_____	_____	_____
0110	401	401SD20-0002 SELECT BACKFILL ABUTMENT ZONE	835.000 TON	_____	_____	_____	_____
0120	401	401SD20-0004 GEOCOMPOSITE WALL DRAIN	85.000 SY	_____	_____	_____	_____
0130	401	401SD20-0005 PIPE UNDERDRAIN 6" CONST.	98.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000126627B01

Oversight/State Project No.: 1212-095-132,B674,C501

Order No.: M65

Federal Project No.: FEMA

Contractor: \_\_\_\_\_

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0140	401	401SD20-0007 COFFERDAM	5.000 EA				
0150	ATTD	401SX20-0002 TEMP. CAUSEWAY TEMPORARY WORK BRIDGE	LUMP SUM	LUMP SUM			
0160	403	403SD20-0006 STEEL PILES 12"	1,074.000 LF				
0170	403	403SX20-0016 PREBORING PILE PREBORING 12" STEEL PILES	1,014.000 LF				
0180	404	404SD20-0005 CONC. CL. A4 MOD. LOW SHRINK., SPR. STRUCT. CONST.	44.400 CY				
0190	404	404SD20-0009 BRIDGE DECK GROOVING CONST.	214.000 SY				
0200	404	404SD20-0010 COVER DEPTH SURVEY CONST.	214.000 SY				
0210	404	404SD20-0011 CONCRETE CLASS A3, SUBSTRUCT. CONST.	172.400 CY				
0220	ATTD	404SP20-0002 SHEAR KEYS	14.000 CF				
0230	ATTD, 404	404SP20-0003 VA ADJACENT MEMBER CONN. BLOCK-OUTS	66.000 CF				
0240	405	405SD20-0020 PREST. CONC. SLAB 4' X 15" X(+30'-35')	8.000 EA				
0250	405	405SX20-0001 PREST. CONCRETE BEAM PREST. CONC. SLAB 4' X 18" X(+50'-55')	4.000 EA				

Schedule of Items

Proposal ID: C0000126627B01

Oversight/State Project No.: 1212-095-132,B674,C501

Order No.: M65

Federal Project No.: FEMA

Contractor: \_\_\_\_\_

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0260	406	406SD20-0003 CR REINF. STEEL CL. I SPR. STRUCT. CONST.	6,700.000 LB	_____	_____	_____	_____
0270	406	406SD20-0006 REINFORCING STEEL SUBSTRUCT. CONST.	13,760.000 LB	_____	_____	_____	_____
0280	406	406SD20-0008 CR REINF. STEEL CL. I SUBSTRUCT. CONST.	15,100.000 LB	_____	_____	_____	_____
0290	ATTD	413SX20-0002 DISM.& REM. EX. STR. STR. NO. 6110	LUMP SUM	LUMP SUM	_____	_____	_____
0300	ATTD	413SX20-0004 MATERIAL DISPOSAL MATERIAL DISPOSAL	LUMP SUM	LUMP SUM	_____	_____	_____
0310	414	414SD20-0012 DRY RIPRAP CL.I 26"	247.000 TON	_____	_____	_____	_____
0320	430	430SX20-0001 NBIS ACCESS, UNDER BRIDGE B674	1.000 DAY	_____	_____	_____	_____
0330	505	505SD20-0011 GUARDRAIL GR-MGS1	20.000 LF	_____	_____	_____	_____
0340	505	505SD20-0074 GUARDRAIL, THRIE BEAM	250.000 LF	_____	_____	_____	_____
0350	ATTD	505SX20-0005 GUARDRAIL REMOVE AND REINSTALL EX GUARDRAIL	20.000 LF	_____	_____	_____	_____
0360	508	508SD20-0004 DEMO. OF PAVEMENT FLEXIBLE	20.000 SY	_____	_____	_____	_____
0370	ATTD	512SP20-0002 MAINTENANCE OF TRAFFIC STRUCTURE NO B674	LUMP SUM	LUMP SUM	_____	_____	_____

Schedule of Items

Proposal ID: C0000126627B01

Oversight/State Project No.: 1212-095-132,B674,C501

Order No.: M65

Federal Project No.: FEMA

Contractor: \_\_\_\_\_

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0380	513	513SD20-0001 MOBILIZATION	LUMP SUM	LUMP SUM			
0390	515	515SD20-0002 FLEX. PAVE. TIE-IN PLANING 0"-2"	170.000 SY				
0400	517	517SD20-0001 CONSTRUCTION SURVEYING CONSTR.	LUMP SUM	LUMP SUM			
0410	602	602SD20-0004 TOPSOIL CLASS B	168.900 CY				
0420	603	603SD20-0003 REGULAR SEED	217.000 LB				
0430	603	603SD20-0004 OVERSEEDING	173.600 LB				
0440	603	603SD20-0010 HYDRAULIC EROSION CONTROL PRODUCT TYPE 4	3,022.000 SY				
0450	603	603SD20-0014 FERTILIZER NITROGEN - N	62.000 LB				
0460	603	603SD20-0015 FERTILIZER PHOSPHOROUS - P	43.400 LB				
0470	603	603SD20-0016 FERTILIZER POTASSIUM - K	43.400 LB				
0480	603	603SD20-0017 LIME	2.200 TON				
0490	700	700SD20-0003 REMOVE EXISTING 1 POST SIGN STRUCTURE	1.000 EA				
0500	700	700SD20-0036 SIGN POST STP-1, 2 1/2", 10 GAUGE	40.000 LF				

Schedule of Items

Proposal ID: C0000126627B01

Oversight/State Project No.: 1212-095-132,B674,C501

Order No.: M65

Federal Project No.: FEMA

Contractor: \_\_\_\_\_

SECTION: 0001                      REGULAR BID ITEMS

Cat Alt Set ID:                      Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0510	701	701SD20-0001 SIGN PANEL	14.000 SF	_____	_____	_____	_____
<b>Section: 0001</b>				<b>Total:</b>		_____	_____
				<b>Total Bid:</b>		_____	_____