



Required Project Showing

Project No. (FO)0000-961-358, C501; (FO)0000-962-364, C501; (FO)0000-963-315, C501;
(FO)0000-964-370, C501; (FO)0000-965-232, C501; (FO)0000-966-237, C501;
(FO)0000-967-265, C501; (FO)0000-968-259, C501; (FO)0000-96A-344, C501

Jamie Surface

Project Manager

E-mail: Jamie.Surface@VDOT.Virginia.gov. Phone (804) 786-2199

➤ **Project Showing Agenda:**

- Overview / Project Team
- Locations
- Traffic Control
- Identification and Marking
- Owner Supplied Materials
- Civil Rights / Labor
- Schedule
- Questions

Overview / Project Team

- **These Projects will identify, mark and replace GR-9 end treatments Across all Nine Districts.**
- **Each Contract will be administered by the District Staff as follows**
 - **Area Construction Engineer**
 - **Construction Manager**
 - **Inspector**

Locations

Interstate routes in all Districts except Lynchburg which has select Primary Routes.

Tables in each proposal list the Route locations with termini.

SCHEDULE OF ROUTES

District	Route Name	From	To	Centerline Miles
Richmond	R-VA IS00195NB	0.00	3.50	3.50
Richmond	R-VA IS00195SB	0.00	3.50	3.50
Richmond	R-VA IS00295NB	0.00	53.16	53.16
Richmond	R-VA IS00295SB	0.00	52.94	52.94
Richmond	R-VA IS00064EB	147.76	157.94	10.18
Richmond	R-VA IS00064WB	148.05	158.05	10.00
Richmond	R-VA IS00064EB	162.50	224.69	62.19
Richmond	R-VA IS00064WB	162.69	224.69	62.00
Richmond	R-VA IS00085NB	0.00	69.12	69.12
Richmond	R-VA IS00085SB	0.00	68.94	68.94
Richmond	R-VA IS00095NB	34.74	101.33	66.59
Richmond	R-VA IS00095SB	34.71	101.33	66.62

Traffic Control

All shoulder or lane closures shall adhere to requirements set forth in the contract and the WAPM to include

- **Time of day restrictions**
- **Location restrictions**
- **Mobile and fixed lane closures**



Identification and Marking

IDENTIFY AND CATEGORIZE GR-9 TERMINALS FOR REMOVAL, INSTALLING, OR REPLACEMENT

December 9, 2014

I. DESCRIPTION

This work shall consist of identifying, categorizing, and providing the location of existing GR-9 terminal end sections.

This work will start 1 week ahead of the “Remove, Replace, and Install” GR-9 Terminal work and shall be completed within 120 days of the “Notice to Proceed” or as directed by the Engineer.

II. MATERIALS

Materials to complete this work shall consist of a standard stencil kit for three-inch high characters, a digital camera, Global Positioning System (GPS) location equipment or other approved data collection unit used for recording the latitude and longitude data, computer with the ability to open Microsoft Excel 2010 files, black water-resistant spray paint and tape measure.



Identification and Marking Cont.

IV. MEASUREMENT AND PAYMENT

Identify and categorize GR-9 terminals will be paid for at the contract lump sum price. This price shall include traffic control, camera, GPS location equipment, computer equipment, stencil kit, paint, tape measure and all materials, labor, tools, equipment, and incidentals necessary to complete the work.

Payment will be made under:

Pay Item	Pay Unit
Identify and Categorize GR-9 Terminals	Lump Sum

Identification and Marking Cont.

Example Data Entry

District (Name)	Maint. Jurisdiction	Route (No.)	Route Direction (NB /SB /EB / WB)	Side of Road (Right /Left)	Latitude (Y) Degrees. Decimals	Longitude (X) Degrees. Decimals	Terminal Manuf.	Terminal Model Number	Top Rail Width (inches)
Hampton Roads	064-Norfolk	I-64	EB	Right	36.842902	76.208926	Trinty	ET-Plus	4

Height (Inches. Decimals)	Replace (Y/N)	Replacement Date (Mo./day/Year)	Replacement Terminal Manuf.	Replacement Terminal Model No.	Replacement Height (Inches. Decimals)	Replacment Top Rail Width (Inches)	Terminal Offset (inches)	Remarks
28.5	Y	12/31/2014	Road Systems	SKT	28.25	5	12	



Materials for Replacement

Each contract will have District specific information

The Pay Item "Installing GR-9 Terminal" requires that the Department shall furnish the GR-9 Terminals according to Specifications Section 106.11. The Contractor shall make arrangements with the VDOT facility 48-hours prior to picking up the materials for installation. Prior to loading guardrail materials, the contractor shall inspect this material and report any damage to the Engineer.

The Pay Item "Replacing GR-9 Terminal" requires that the Contractor shall furnish the GR-9 Terminals according to Specifications Section 505.

VDOT FACILITY - PICK-UP /DELIVERY LOCATION

Description: District Lot across Railroad Tracks, 2430 Pine Forest Drive, Colonial Heights. VA. 23834

Deliveries received between 8 a.m. and 2:30 p.m. Monday through Friday except holidays.

Contracts are:

1. Chip Butterworth 804-524-6097 or 804-720-4133
2. Donna Robertson 804-524-6332 or 804-398-8350 (except Fridays)
3. Todd Shank 804-524-6173 or 804-397-5297

Civil Rights

- **Federal Projects**
- **No Trainees**
- **The projects all have DBE goals**
- **Complete C-111**
- **The Contractor shall include list of DBE activities in their progress schedule narrative.**

- **Certified Payrolls, Weekly**
 - EEO Law Poster
 - Contractor's EEO Policy
 - EEO/DBE Officer
 - Predetermined Wage Rate
- **Forms**
 - C-28 Hourly Wage Rates (due prior to 2nd estimate)
 - C-57 Total Project Employment (for the first three months)
 - C-63 DBE/MBE/WEB Enterprise Activities (due quarterly)
 - C-68 Total dollar amount paid to DBE

- Identifying, categorizing, and providing the location of existing GR-9 terminal end sections will start 1 week ahead of the “Remove, Replace, and Install” GR-9 Terminal work and shall be completed within 120 days of the “Notice to Proceed” or as directed by the Engineer.
- Fixed completion date varies on each contract

Questions

Any additional questions that arise after the project showing shall be addressed with the normal CABB process

Project Showing Minutes

GR-9 Identify and Replace Projects

December 22, 2014 -9am- Richmond District Training Center

Overview

Jamie Surface opened the meeting and read the names of the eligible bidders from the sign in sheet. He informed all attendees that the project showing is mandatory and in order to submit a bid as a prime contractor they needed to be in attendance. The showing consists of several parts and the presenters were;

Jamie Surface

- Will provide an overview of the projects and project teams
- Locations
- Traffic Control
- Identification
- Owner supplied materials
- Schedule

Leslie Evans

- Civil Rights
- Labor

Overview

The project consists of identification of all existing guardrail end treatments along the corridors as noted in each proposal. The Projects will be administered by District personnel.

Location

The Locations are noted in each proposal and are interstate routes in all Districts with the exception of Lynchburg which has limited access and select primary routes.

Traffic Control

Each project has specific traffic control requirements that reflect day and time restrictions.

Identification

The identification and marking of the Trinity end treatments to be replaced. Collecting the information, and reporting in an excel spreadsheet and submitted weekly.

Owner supplied materials

Each proposal includes location of the stockpiled end treatments for replacement and contact information for VDOT personnel.

Schedule

Each proposal has a fixed completion date based on anticipated quantities. The identification process should start at least a week ahead of the replacement work. Any changes will need to be approved by the engineer.

Civil Rights

These are federally funded projects with DBE goals.

Labor

The contractor must post all forms and adhere to all reporting requirements as set forth in the proposal.

Questions

Are the ramps included in the Interstate Routes shown in the contract? Yes

If we are not replacing the terminal, the contract calls for us to adjust tension and bolts. What exactly do you want done? Check tension in cable (1" max deflection), tighten if necessary.

Is it the Department's intent to use all the quantities in the contract? Yes, the intent is to replace all terminals that need replacing on the specified routes.

If the Trinity products pass the current testing, will these contracts be terminated? No, we plan to move forward regardless of the testing results.

Are the Department provided terminals complete? Yes, they will be complete 50 feet units.

Are all Districts receiving the X-Lite product? Yes

What if the existing terminals are at the wrong height? Will there be a work order to adjust the height? This will be a field decision.

The contract says we have to return the terminals within 72 hours, is this correct? More direction will be provided.

Contractors

Form C-15
Rev. 2-11-11
Sheet 1 of

COMMONWEALTH OF VIRGINIA

DEPARTMENT OF TRANSPORTATION

PROJECT SHOWING ATTENDANCE SHEET

CONTRACT ID. NO.: _____ PROJ. NO.: GR-9 REPLACEMENT AREA CONSTRUCTION ENGINEER: _____
 ROUTE: _____ COUNTY: _____ DATE: 12-22-14
 DISTRICT: _____ CONSTRUCTION AREA: _____ TIME: 9:00 AM

REPRESENTATIVE	COMPANY	COMPANY ADDRESS	EMAIL ADDRESS	PHONE NUMBER
Brian Schultz	RMD Holdings	53861 Gratiot Chesapeake	bbschultz@nationwidecos.com	580-431-4771
Justin Sayko	L.S. Lee	3008 Falling Creek Ave.	JSayko@LSLee.com	804-334-0374
Tim MURIN	ELDERLEE INC	725 CROSS ROAD OAKS CORNER, N.Y.	DDeJOHN@ELDERLEE.COM	315-789-6670
Derrick Kernr	MAKCO, LLC.	P.O. Box 1007 Fry, VA 22974	dkernr@makco-inc.com	434-962-0403
TUCK MALLOY	MAKCO, INC.	" " " "	TMALLOY@MAKCO-INC.COM	434-962-2709
RYAN CRAMER	PENNLIN	310 SCOTT AVE SCOTT AVE PA 15683	rcramer@pennline.com	724-887-2144
MIKE BERZENSKY	PENNLIN	3005 SCOTT AVE SCOTT AVE PA	mberzensky@pennline.com	614-644-9564
Steve Tennant	CMS INC.			252-473-2755
"	CAROLINA MARINE STRUCTURES	9443 CHARTWELL DR Forsyth NC 27948	Steve@Carolinamarinestructures.com	

(Continued)

COMMONWEALTH OF VIRGINIA
DEPARTMENT OF TRANSPORTATION
PROJECT SHOWING ATTENDANCE SHEET

CONTRACT ID. NO.: _____ PROJ. NO.: GR-9 REPLACEMENT AREA CONSTRUCTION ENGINEER: _____
ROUTE: _____ COUNTY: _____ DATE: 12-22-14
DISTRICT: _____ CONSTRUCTION AREA: _____ TIME: 9:00 am

REPRESENTATIVE	COMPANY	COMPANY ADDRESS	EMAIL ADDRESS	PHONE NUMBER
<u>L. J. Gilley</u>	<u>VDOT</u>	<u>Richmond</u>		<u>786-2987</u>
<u>W. M. BARRET</u>	<u>VDOT</u>	<u>CO</u>		<u>371-2788</u>
<u>M. Hernandez</u>	<u>VDOT</u>	<u>C.O.</u>		<u>692-2134</u>
<u>K. BATES</u>	<u>VDOT</u>	<u>CO</u>		<u>371-4312</u>
<u>Matthew Cross</u>	<u>VDOT</u>	<u>CO</u>		<u>786-2577</u>
<u>Andy Kretsch</u>	<u>VDOT</u>	<u>CO</u>		<u>786-1166</u>
<u>LESLIE EVANS</u>	<u>VDOT CIV. Rights</u>	<u>Richmond District</u>		<u>434-755-1416</u>
<u>Khalil Askanyar</u>	<u>VDOT Nova Construction</u>			<u>703-828-1302</u>

(Continued)