

Schedule of Items

Proposal ID: C00078825B26

Oversight/State Project No.: 0522-034-739, M501, B626

Order No.: F23

Federal Project No.: STP-5138(208)

Contractor: _____

SECTION: 0001 REGULAR ITEMS

Cat Alt Set ID: _____ Cat Alt Mbr ID: _____

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	513	00100 MOBILIZATION	LUMP SUM	LUMP SUM			
0020	517	00102 CONSTRUCTION SURVEYING MIN.-PLAN	LUMP SUM	LUMP SUM			
0030	301	00110 CLEARING AND GRUBBING	LUMP SUM	LUMP SUM			
0040	303	00125 GRADING	LUMP SUM	LUMP SUM			
0050	303	00137 BORROW EXCAVATION MINIMUM CBR 15	4,402.000 CY				
0060	305	00355 GEOTEXTILE SUBGRADE STABILIZATION	870.000 SY				
0070	501	00591 CROSSDRAIN CD-2	73.000 LF				
0080	501	00595 OUTLET PIPE	18.000 LF				
0090	302	00596 ENDWALL EW-12	2.000 EA				
0100	302	01186 STORM SEWER PIPE 18"	132.000 LF				
0110	302	01246 STORM SEWER PIPE 24"	28.000 LF				
0120	302	01366 STORM SEWER PIPE 36"	80.000 LF				
0130	302	06181 18" END SECTION ES-1	1.000 EA				
0140	302	06361 36" END SECTION ES-1	1.000 EA				

Schedule of Items

Proposal ID: C00078825B26

Oversight/State Project No.: 0522-034-739, M501, B626

Order No.: F23

Federal Project No.: STP-5138(208)

Contractor: _____

SECTION: 0001 REGULAR ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0150	302	07506 DROP INLET DI-5	2.000 EA	_____	_____	_____	_____
0160	302	09056 MANHOLE MH-1 OR 2	15.400 LF	_____	_____	_____	_____
0170	302	09057 FRAME & COVER MH-1	2.000 EA	_____	_____	_____	_____
0180	414	09150 EROSION CONTROL STONE CLASS I, EC-1	8.000 TON	_____	_____	_____	_____
0190	308	10128 AGGR. BASE MATL. TY. I NO. 21B	1,369.000 TON	_____	_____	_____	_____
0200	315	10608 ASPHALT CONCRETE TY. SM-12.5D	727.000 TON	_____	_____	_____	_____
0210	515	10625 FLEXIBLE PAVE. TIE-IN PLANING 0" - 2"	1,252.000 SY	_____	_____	_____	_____
0220	315	10643 ASPHALT CONCRETE TY. BM-25.0D	1,589.000 TON	_____	_____	_____	_____
0230	315	11070 SAW-CUT ASPH CONC FULL DEPTH	498.000 LF	_____	_____	_____	_____
0240	505	13267 ADJUST EXISTING GUARDRAIL BEAM	800.000 LF	_____	_____	_____	_____
0250	505	13280 GUARDRAIL GR-MGS1	550.000 LF	_____	_____	_____	_____
0260	505	13286 GUARDRAIL TERMINAL GR-MGS2	1.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C00078825B26

Oversight/State Project No.: 0522-034-739, M501, B626

Order No.: F23

Federal Project No.: STP-5138(208)

Contractor: _____

SECTION: 0001 REGULAR ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0270	505	13288 GUARDRAIL HEIGHT TRANSITION GR-MGS4	1.000 EA	_____	_____	_____	_____
0280	505	13310 GUARDRAIL TERMINAL GR-6 NCHRP 350	50.000 LF	_____	_____	_____	_____
0290	505	13320 GUARDRAIL GR-2	50.000 LF	_____	_____	_____	_____
0300	505	13383 FIXED OBJECT ATTACH. GR- FOA-1 TY. I	4.000 EA	_____	_____	_____	_____
0310	505	13601 BULL NOSE BARRIER	1.000 EA	_____	_____	_____	_____
0320	512	24150 TYPE 3 BARRICADE 4'	1.000 EA	_____	_____	_____	_____
0330	512	24152 TYPE 3 BARRICADE 8'	10.000 EA	_____	_____	_____	_____
0340	512	24160 TEMPORARY (CONSTRUCTION) SIGN	904.000 SF	_____	_____	_____	_____
0350	ATTD	24262 PORTABLE TEMPORARY RUMBLE STRIP ARRAY	40.000 DAY	_____	_____	_____	_____
0360	512	24272 TRUCK MOUNTED ATTENUATOR	480.000 HR	_____	_____	_____	_____
0370	512	24278 GROUP 2 CHANNELIZING DEVICES	60,000.000 DAY	_____	_____	_____	_____
0380	512	24281 ELECTRONIC ARROW BOARD	1,400.000 HR	_____	_____	_____	_____
0390	512	24282 FLAGGER SERVICE	400.000 HR	_____	_____	_____	_____

Schedule of Items

Proposal ID: C00078825B26

Oversight/State Project No.: 0522-034-739, M501, B626

Order No.: F23

Federal Project No.: STP-5138(208)

Contractor: _____

SECTION: 0001 REGULAR ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0400	512	24290 TRAFFIC BARRIER SERVICE CONC. MB-7D PC	1,550.000 LF	_____	_____	_____	_____
0410	ATTD	24330 TRAFFIC CONTROL TEMPORARY RUMBLE STRIP	4.000 EA	_____	_____	_____	_____
0420	505	24600 REMOVE EXISTING GUARDRAIL	550.000 LF	_____	_____	_____	_____
0430	514	25506 FIELD OFFICE TY.II	14.000 MO	_____	_____	_____	_____
0440	ATTD	25565 PROGRESS SCHEDULE BASELINE	LUMP SUM	LUMP SUM	_____	_____	_____
0450	ATTD	25567 PROGRESS SCHEDULE UPDATES	28.000 EA	_____	_____	_____	_____
0460	ATTD	26100 ROCKFILL	250.000 TON	_____	_____	_____	_____
0470	414	26440 GROUTED RIPRAP CLASS II 38"	77.800 SY	_____	_____	_____	_____
0480	602	27024 TOPSOIL 3"	1.100 ACRE	_____	_____	_____	_____
0490	603	27101 TEMPORARY SEED	110.000 LB	_____	_____	_____	_____
0500	603	27102 REGULAR SEED	234.000 LB	_____	_____	_____	_____
0510	603	27103 OVERSEEDING	187.000 LB	_____	_____	_____	_____
0520	603	27111 HYDRAULIC EROSION CONTROL PRODUCT TYPE 2	6,050.000 SY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C00078825B26

Oversight/State Project No.: 0522-034-739, M501, B626

Order No.: F23

Federal Project No.: STP-5138(208)

Contractor: _____

SECTION: 0001 REGULAR ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0530	603	27112 HYDRAULIC EROSION CONTROL PRODUCT TYPE 3	5,929.000 SY	_____	_____	_____	_____
0540	603	27230 FERTILIZER NITROGEN - N	91.000 LB	_____	_____	_____	_____
0550	603	27231 FERTILIZER PHOSPHOROUS - P	58.000 LB	_____	_____	_____	_____
0560	603	27232 FERTILIZER POTASSIUM - K	58.000 LB	_____	_____	_____	_____
0570	603	27250 LIME	4.950 TON	_____	_____	_____	_____
0580	606	27319 ROLLED EROSION CTRL PRODUCT EC-2 TYPE 2	600.000 SY	_____	_____	_____	_____
0590	606	27320 ROLLED EROSION CTRL PRODUCT EC-2 TYPE 3	200.000 SY	_____	_____	_____	_____
0600	303	27415 CHECK DAM ROCK TY. II	29.000 EA	_____	_____	_____	_____
0610	303	27422 DEWATERING BASIN EC-8	2.000 EA	_____	_____	_____	_____
0620	303	27430 SILTATION CONTROL EXCAVATION	300.000 CY	_____	_____	_____	_____
0630	303	27500 GEOTEXTILE FABRIC	50.000 SY	_____	_____	_____	_____
0640	303	27504 TEMP. SILT FENCE TYPE B	150.000 LF	_____	_____	_____	_____
0650	303	27505 TEMP. SILT FENCE TYPE A	1,600.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C00078825B26

Oversight/State Project No.: 0522-034-739, M501, B626

Order No.: F23

Federal Project No.: STP-5138(208)

Contractor: _____

SECTION: 0001 REGULAR ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0660	704	54020 TYPE A PVMT LINE MRKG 4"	10,800.000 LF	_____	_____	_____	_____
0670	704	54028 TYPE A PAVEMENT LINE MRKG 24"	12.000 LF	_____	_____	_____	_____
0680	704	54032 TYPE B CLASS I PVMT LINE MRKG 4"	14,500.000 LF	_____	_____	_____	_____
0690	704	54079 TYPE B CLASS VI CONTRAST PVMT MRKG 4"	500.000 LF	_____	_____	_____	_____
0700	512	54105 ERADICATE EXIST. LINEAR PVMT MARKING	1,200.000 LF	_____	_____	_____	_____
0710	512	54240 TEMP. PAVE. MARKER 1 WAY	500.000 EA	_____	_____	_____	_____
0720	512	54542 TYPE D, CLASS III TEMP. PVMT MRKG 4"	18,000.000 LF	_____	_____	_____	_____
0730	404	60411 CONC. CLASS A4 MOD. LIGHTWEIGHT LOW SHRINKAGE	138.400 CY	_____	_____	_____	_____
0740	404	60490 BRIDGE DECK GROOVING	433.300 SY	_____	_____	_____	_____
0750	404	60495 COVER DEPTH SURVEY	456.400 SY	_____	_____	_____	_____
0760	406	61713 CORROSION RESISTANT REINF. STEEL CL. III	23,843.000 LB	_____	_____	_____	_____
0770	407	61812 STR. STEEL PLATE GIRDER ASTM A709 GRADE 50W	LUMP SUM	LUMP SUM	_____	_____	_____

Schedule of Items

Proposal ID: C00078825B26

Oversight/State Project No.: 0522-034-739, M501, B626

Order No.: F23

Federal Project No.: STP-5138(208)

Contractor: _____

SECTION: 0001 REGULAR ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0780	ATTD	62021 RAILING 42" CPSR-1 RAILING/PARAPET	208.000 LF	_____	_____	_____	_____
0790	431	62190 EPOXY OVERLAY	489.000 SY	_____	_____	_____	_____
0800	408	62533 BRIDGE SUPERSTRUCTURE LAMINATED ELASTOMERIC BEARING PADS	604.000 LB	_____	_____	_____	_____
0810	401	64011 STRUCTURE EXCAVATION	895.000 CY	_____	_____	_____	_____
0820	401	64015 SELECT BACKFILL ABUTMENT ZONE	1,141.000 TON	_____	_____	_____	_____
0830	ATTD	64021 ELASTIC INCLUSION	9.800 CY	_____	_____	_____	_____
0840	401	64032 GEOCOMPOSITE WALL DRAIN	55.500 SY	_____	_____	_____	_____
0850	401	64036 PIPE UNDERDRAIN 6"	122.000 LF	_____	_____	_____	_____
0860	ATTD	64102 DYNAMIC PILE TEST END BEARING PILES	2.000 EA	_____	_____	_____	_____
0870	403	64112 STEEL PILES 12"	400.000 LF	_____	_____	_____	_____
0880	403	64765 PILE POINT FOR 12" STEEL PILE	20.000 EA	_____	_____	_____	_____
0890	403	64768 DRIVING TEST FOR 12" STEEL PILE	40.000 LF	_____	_____	_____	_____
0900	404	65013 CONCRETE CLASS A3	113.400 CY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C00078825B26

Oversight/State Project No.: 0522-034-739, M501, B626

Order No.: F23

Federal Project No.: STP-5138(208)

Contractor: _____

SECTION: 0001 REGULAR ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0910	404	65095 CONCRETE CLASS A3 UNREINFORCED	28.500 CY	_____	_____	_____	_____
0920	406	65200 REINF. STEEL	8,057.000 LB	_____	_____	_____	_____
0930	ATTD	66115 TEMP. CAUSEWAY	LUMP SUM	LUMP SUM	_____	_____	_____
0940	401	66120 COFFERDAM	1.000 EA	_____	_____	_____	_____
0950	413	67900 DISM.& REM. EX. STR. 1027	LUMP SUM	LUMP SUM	_____	_____	_____
0960	413	68476 ENV.& WORK. PROTECTION STR. 1027	LUMP SUM	LUMP SUM	_____	_____	_____
0970	413	68492 MATERIAL DISPOSAL STR. 1027	LUMP SUM	LUMP SUM	_____	_____	_____
Section: 0001				Total:	_____	_____	_____
				Total Bid:	_____	_____	_____