

Schedule of Items

Proposal ID: CM221PMI118471 Oversight/State Project No.: PM2I-011-F21, P401

Order No.: 293

Federal Project No.: PM02(461)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	310	10417 TACK COAT	2,674.000 GAL	_____	_____	_____	_____
0020	315	10700 RUMBLE STRIP CYLINDRICAL ASPHALT	7,764.000 LF	_____	_____	_____	_____
0030	315	10701 LIQUID ASPHALT RUMBLE STRIP COATING	835.000 SY	_____	_____	_____	_____
0040	ATTD	16242 AGGR. BASE MATL. TY. I OR II NO. 21A OR 21B	20.000 TON	_____	_____	_____	_____
0050	315	16340 ASPHALT CONC. TY. SM-9.5D	1,163.880 TON	_____	_____	_____	_____
0060	ATTD	16368 PAVEMENT SHOULDER WEDGE PREP.	5,174.000 LF	_____	_____	_____	_____
0070	315	16370 ASPHALT CONC. TY. IM-19.0D	1,933.940 TON	_____	_____	_____	_____
0080	515	16522 FLEXIBLE PAVEMENT PLANING 0" - 2"	207.000 SY	_____	_____	_____	_____
0090	515	16523 FLEXIBLE PAVEMENT PLANING ABOVE 2" - 4"	13,223.460 SY	_____	_____	_____	_____
0100	ATTD	24265 MAINTENANCE OF TRAFFIC PLANT MIX	LUMP SUM	LUMP SUM	_____	_____	_____
0110	512	24282 FLAGGER SERVICE	100.000 HR	_____	_____	_____	_____
0120	704	54034 TYPE B CLASS I PVMT LINE MRKG 6"	11,643.000 LF	_____	_____	_____	_____
0130	512	54428 TEMP. PVMT MRKG, TY. A, 4"	23,286.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: CM221PMI118471 Oversight/State Project No.: PM2I-011-F21, P401
 Order No.: 293 Federal Project No.: PM02(461)

Contractor: _____

Section: 0001 Total: _____

SECTION: 0002 ALTERNATE BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0140	ATTD	16243 SHOULDER MAINTENANCE MATERIAL	1.000 TON	_____	_____	_____	_____
Section: 0002				Total:		_____	
				Total Bid:		_____	