

Schedule of Items

Proposal ID: C0000106701N01

Oversight/State Project No.: 9999-009-348, M501

Order No.: F78

Federal Project No.: HRRR-009-2(063)

Contractor: \_\_\_\_\_

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

| Proposal Line Number | Spec No. | Item ID Description                          | Approximate Quantity and Units | Unit Price |       | Bid Amount |       |
|----------------------|----------|--|--------------------------------|------------|-------|------------|-------|
|                      |          |  |                                | Dollars    | Cents | Dollars    | Cents |
| 0010                 | 513      | 00099<br>MOBILIZATION BASE BID               | LUMP SUM                       | LUMP SUM   |       |            |       |
| 0020                 | 303      | 00120<br>REGULAR EXCAVATION                  | 3,000.000<br>CY                |            |       |            |       |
| 0030                 | 303      | 00136<br>BORROW EXCAVATION                   | 520.000<br>CY                  |            |       |            |       |
| 0040                 | 302      | 01150<br>15" PIPE                            | 55.000<br>LF                   |            |       |            |       |
| 0050                 | 302      | 01180<br>18" PIPE                            | 67.000<br>LF                   |            |       |            |       |
| 0060                 | 302      | 01186<br>STORM SEWER PIPE 18"                | 62.000<br>LF                   |            |       |            |       |
| 0070                 | 302      | 06180<br>18" END SECTION ES-1 OR 2           | 2.000<br>EA                    |            |       |            |       |
| 0080                 | 302      | 06181<br>18" END SECTION ES-1                | 1.000<br>EA                    |            |       |            |       |
| 0090                 | 414      | 09150<br>EROSION CONTROL STONE CLASS I, EC-1 | 33.000<br>TON                  |            |       |            |       |
| 0100                 | 308      | 10065<br>AGGR. MATL. NO. 1                   | 495.000<br>TON                 |            |       |            |       |
| 0110                 | 308      | 10128<br>AGGR. BASE MATL. TY. I NO. 21B      | 575.000<br>TON                 |            |       |            |       |
| 0120                 | 315      | 11070<br>SAW-CUT ASPH CONC FULL DEPTH        | 65.000<br>LF                   |            |       |            |       |
| 0130                 | ATTD     | 14260<br>CRUSHER RUN AGGREGATE NO. 25 OR 26  | 500.000<br>TON                 |            |       |            |       |
| 0140                 | 315      | 16340<br>ASPHALT CONC. TY. SM-9.5D           | 185.000<br>TON                 |            |       |            |       |

Schedule of Items

Proposal ID: C0000106701N01

Oversight/State Project No.: 9999-009-348, M501

Order No.: F78

Federal Project No.: HRRR-009-2(063)

Contractor: \_\_\_\_\_

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

| Proposal Line Number | Spec No. | Item ID Description                               | Approximate Quantity and Units | Unit Price |       | Bid Amount |       |
|----------------------|----------|---|--------------------------------|------------|-------|------------|-------|
|                      |          |   |                                | Dollars    | Cents | Dollars    | Cents |
| 0150                 | 315      | 16390<br>ASPH. CONC. TY. BM-25.0A                 | 360.000<br>TON                 | _____      | _____ | _____      | _____ |
| 0160                 | 507      | 23570<br>HIGH VISIBILITY FENCE, 4'                | 440.000<br>LF                  | _____      | _____ | _____      | _____ |
| 0170                 | 511      | 24100<br>ALLAYING DUST                            | 128.000<br>HR                  | _____      | _____ | _____      | _____ |
| 0180                 | 512      | 24152<br>TYPE 3 BARRICADE 8'                      | 2.000<br>EA                    | _____      | _____ | _____      | _____ |
| 0190                 | 512      | 24160<br>TEMPORARY<br>(CONSTRUCTION) SIGN         | 334.000<br>SF                  | _____      | _____ | _____      | _____ |
| 0200                 | ATTD     | 24262<br>PORTABLE TEMPORARY<br>RUMBLE STRIP ARRAY | 600.000<br>DAY                 | _____      | _____ | _____      | _____ |
| 0210                 | 512      | 24278<br>GROUP 2 CHANNELIZING<br>DEVICES          | 38,000.000<br>DAY              | _____      | _____ | _____      | _____ |
| 0220                 | 512      | 24279<br>PORTABLE CHANGEABLE<br>MESSAGE SIGN      | 4,032.000<br>HR                | _____      | _____ | _____      | _____ |
| 0230                 | 512      | 24282<br>FLAGGER SERVICE                          | 11,800.000<br>HR               | _____      | _____ | _____      | _____ |
| 0240                 | 508      | 24430<br>DEMOLITION OF PAVEMENT<br>FLEXIBLE       | 1,250.000<br>SY                | _____      | _____ | _____      | _____ |
| 0250                 | 602      | 27012<br>TOPSOIL CLASS A 2"                       | 1.050<br>ACRE                  | _____      | _____ | _____      | _____ |
| 0260                 | 603      | 27101<br>TEMPORARY SEED                           | 126.000<br>LB                  | _____      | _____ | _____      | _____ |
| 0270                 | 603      | 27102<br>REGULAR SEED                             | 578.000<br>LB                  | _____      | _____ | _____      | _____ |

## Schedule of Items

Proposal ID: C0000106701N01      Oversight/State Project No.: 9999-009-348, M501  
 Order No.: F78      Federal Project No.: HRRR-009-2(063)

Contractor: \_\_\_\_\_

SECTION: 0001      REGULAR BID ITEMS

Cat Alt Set ID:      Cat Alt Mbr ID:

| Proposal<br>Line<br>Number | Spec<br>No. | Item ID<br>Description                               | Approximate<br>Quantity and<br>Units | Unit Price |       | Bid Amount |       |
|----------------------------|-------------|--|--------------------------------------|------------|-------|------------|-------|
|                            |             |  |                                      | Dollars    | Cents | Dollars    | Cents |
| 0280                       | 603         | 27103<br>OVERSEEDING                                 | 462.000<br>LB                        | _____      | _____ | _____      | _____ |
| 0290                       | 603         | 27104<br>LEGUME SEED                                 | 26.000<br>LB                         | _____      | _____ | _____      | _____ |
| 0300                       | 603         | 27105<br>LEGUME OVERSEEDING                          | 21.000<br>LB                         | _____      | _____ | _____      | _____ |
| 0310                       | 603         | 27111<br>HYDRAULIC EROSION<br>CONTROL PRODUCT TYPE 2 | 3,509.000<br>SY                      | _____      | _____ | _____      | _____ |
| 0320                       | 603         | 27112<br>HYDRAULIC EROSION<br>CONTROL PRODUCT TYPE 3 | 14,278.000<br>SY                     | _____      | _____ | _____      | _____ |
| 0330                       | 603         | 27230<br>FERTILIZER NITROGEN - N                     | 189.000<br>LB                        | _____      | _____ | _____      | _____ |
| 0340                       | 603         | 27231<br>FERTILIZER PHOSPHOROUS<br>- P               | 126.000<br>LB                        | _____      | _____ | _____      | _____ |
| 0350                       | 603         | 27232<br>FERTILIZER POTASSIUM - K                    | 126.000<br>LB                        | _____      | _____ | _____      | _____ |
| 0360                       | 603         | 27250<br>LIME  | 9.450<br>TON                         | _____      | _____ | _____      | _____ |
| 0370                       | 606         | 27318<br>ROLLED EROSION CTRL<br>PRODUCT EC-2 TYPE 1  | 240.000<br>SY                        | _____      | _____ | _____      | _____ |
| 0380                       | 303         | 27415<br>CHECK DAM ROCK TY. II                       | 5.000<br>EA                          | _____      | _____ | _____      | _____ |
| 0390                       | 303         | 27430<br>SILTATION CONTROL<br>EXCAVATION             | 160.000<br>CY                        | _____      | _____ | _____      | _____ |
| 0400                       | 303         | 27505<br>TEMP. SILT FENCE TYPE A                     | 430.000<br>LF                        | _____      | _____ | _____      | _____ |

Schedule of Items

Proposal ID: C0000106701N01

Oversight/State Project No.: 9999-009-348, M501

Order No.: F78

Federal Project No.: HRRR-009-2(063)

Contractor: \_\_\_\_\_

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

| Proposal Line Number | Spec No. | Item ID Description  | Approximate Quantity and Units | Unit Price |       | Bid Amount |       |
|----------------------|----------|--|--------------------------------|------------|-------|------------|-------|
|                      |          |  |                                | Dollars    | Cents | Dollars    | Cents |
| 0410                 | 303      | 27545<br>STORM WATER MANAGEMENT BASIN EXCAVATION                                     | 500.000<br>CY                  | _____      | _____ | _____      | _____ |
| 0420                 | 302      | 27550<br>STORM WATER MANAGEMENT DRAINAGE STR. SWM-1                                  | 6.500<br>LF                    | _____      | _____ | _____      | _____ |
| 0430                 | ATTD     | 27553<br>PERMANENT SWM FACILITY AS-BUILT DOCUMENTATION CONSTRUCTION RECORD DOCUMENTS | LUMP SUM                       | LUMP SUM   | _____ | _____      | _____ |
| 0440                 | 701      | 50108<br>SIGN PANEL  | 92.000<br>SF                   | _____      | _____ | _____      | _____ |
| 0450                 | 700      | 50430<br>SIGN POST STP-1, 2", 14 GAUGE   | 90.000<br>LF                   | _____      | _____ | _____      | _____ |
| 0460                 | 700      | 50436<br>SIGN POST STP-1, 2 1/2", 12 GAUGE   | 30.000<br>LF                   | _____      | _____ | _____      | _____ |
| 0470                 | 700      | 50485<br>CONCRETE SIGN FOUNDATION STP-1, TYPE A                                      | 8.000<br>EA                    | _____      | _____ | _____      | _____ |
| 0480                 | 700      | 51930<br>REMOVE EXISTING SIGN STRUCTURE TYPE I AND DISPOSE                           | 7.000<br>EA                    | _____      | _____ | _____      | _____ |
| 0490                 | 704      | 54020<br>TYPE A PVMT LINE MRKG 4"  | 1,745.000<br>LF                | _____      | _____ | _____      | _____ |
| 0500                 | 704      | 54048<br>TYPE B CLASS II PAVE. LINE MARKING 24"                                      | 25.000<br>LF                   | _____      | _____ | _____      | _____ |
| 0510                 | 512      | 54466<br>TYPE E TEMP. PVMT MRKG 6"   | 500.000<br>LF                  | _____      | _____ | _____      | _____ |

Schedule of Items

Proposal ID: C0000106701N01      Oversight/State Project No.: 9999-009-348, M501  
 Order No.: F78      Federal Project No.: HRRR-009-2(063)

Contractor: \_\_\_\_\_

SECTION: 0001      REGULAR BID ITEMS

Cat Alt Set ID:      Cat Alt Mbr ID:

| Proposal<br>Line<br>Number | Spec<br>No. | Item ID<br>Description                           | Approximate<br>Quantity and<br>Units | Unit Price    |       | Bid Amount |       |
|----------------------------|-------------|--|--------------------------------------|---------------|-------|------------|-------|
|                            |             |  |                                      | Dollars       | Cents | Dollars    | Cents |
| 0520                       | 512         | 54543<br>TYPE D, CLASS III TEMP.<br>PVMT MRKG 6" | 1,000.000<br>LF                      | _____         | _____ | _____      | _____ |
| <b>Section: 0001</b>       |             |  |                                      | <b>Total:</b> | _____ | _____      | _____ |

Schedule of Items

Proposal ID: C0000106701N01      Oversight/State Project No.: 9999-009-348, M501  
 Order No.: F78      Federal Project No.: HRRR-009-2(063)

Contractor: \_\_\_\_\_

SECTION: 0002      ADDITIVE A

Cat Alt Set ID:      Cat Alt Mbr ID:

| Proposal Line Number | Spec No. | Item ID Description                            | Approximate Quantity and Units | Unit Price |       | Bid Amount |       |
|----------------------|----------|--|--------------------------------|------------|-------|------------|-------|
|                      |          |  |                                | Dollars    | Cents | Dollars    | Cents |
| 0530                 | 513      | 00099<br>MOBILIZATION ADDITIVE A               | LUMP SUM                       | LUMP SUM   |       |            |       |
| 0540                 | 303      | 00125<br>GRADING                               | LUMP SUM                       | LUMP SUM   |       |            |       |
| 0550                 | ATTD     | 10250<br>AGGR. MATERIAL NO. 357                | 595.000<br>TON                 |            |       |            |       |
| 0560                 | 315      | 10497<br>PAVEMENT CRACK SEALANT/FILLER TYPE B  | 580.000<br>LB                  |            |       |            |       |
| 0570                 | 315      | 10700<br>RUMBLE STRIP CYLINDRICAL ASPHALT      | 5,800.000<br>LF                |            |       |            |       |
| 0580                 | 315      | 10701<br>LIQUID ASPHALT RUMBLE STRIP COATING   | 970.000<br>SY                  |            |       |            |       |
| 0590                 | 315      | 11070<br>SAW-CUT ASPH CONC FULL DEPTH          | 5,800.000<br>LF                |            |       |            |       |
| 0600                 | 315      | 16340<br>ASPHALT CONC. TY. SM-9.5D             | 530.000<br>TON                 |            |       |            |       |
| 0610                 | 315      | 16390<br>ASPH. CONC. TY. BM-25.0A              | 445.000<br>TON                 |            |       |            |       |
| 0620                 | 515      | 16522<br>FLEXIBLE PAVEMENT PLANING 0" - 2"     | 1,925.000<br>SY                |            |       |            |       |
| 0630                 | ATTD     | 24262<br>PORTABLE TEMPORARY RUMBLE STRIP ARRAY | 170.000<br>DAY                 |            |       |            |       |
| 0640                 | 512      | 24265<br>MAINTENANCE OF TRAFFIC ADDITIVE A     | LUMP SUM                       | LUMP SUM   |       |            |       |
| 0650                 | 508      | 24430<br>DEMOLITION OF PAVEMENT FLEXIBLE       | 650.000<br>SY                  |            |       |            |       |

Schedule of Items

Proposal ID: C0000106701N01      Oversight/State Project No.: 9999-009-348, M501  
 Order No.: F78      Federal Project No.: HRRR-009-2(063)

Contractor: \_\_\_\_\_

SECTION: 0002      ADDITIVE A

Cat Alt Set ID:      Cat Alt Mbr ID:

| Proposal Line Number | Spec No. | Item ID Description                               | Approximate Quantity and Units | Unit Price |       | Bid Amount |       |
|----------------------|----------|---|--------------------------------|------------|-------|------------|-------|
|                      |          |   |                                | Dollars    | Cents | Dollars    | Cents |
| 0660                 | 602      | 27012<br>TOPSOIL CLASS A 2"                       | 0.800<br>ACRE                  | _____      | _____ | _____      | _____ |
| 0670                 | 603      | 27101<br>TEMPORARY SEED                           | 96.000<br>LB                   | _____      | _____ | _____      | _____ |
| 0680                 | 603      | 27102<br>REGULAR SEED                             | 441.000<br>LB                  | _____      | _____ | _____      | _____ |
| 0690                 | 603      | 27103<br>OVERSEEDING                              | 352.000<br>LB                  | _____      | _____ | _____      | _____ |
| 0700                 | 603      | 27104<br>LEGUME SEED                              | 20.000<br>LB                   | _____      | _____ | _____      | _____ |
| 0710                 | 603      | 27105<br>LEGUME OVERSEEDING                       | 16.000<br>LB                   | _____      | _____ | _____      | _____ |
| 0720                 | 603      | 27111<br>HYDRAULIC EROSION CONTROL PRODUCT TYPE 2 | 2,673.000<br>SY                | _____      | _____ | _____      | _____ |
| 0730                 | 603      | 27112<br>HYDRAULIC EROSION CONTROL PRODUCT TYPE 3 | 10,874.000<br>SY               | _____      | _____ | _____      | _____ |
| 0740                 | 603      | 27230<br>FERTILIZER NITROGEN - N                  | 144.000<br>LB                  | _____      | _____ | _____      | _____ |
| 0750                 | 603      | 27231<br>FERTILIZER PHOSPHOROUS - P               | 96.000<br>LB                   | _____      | _____ | _____      | _____ |
| 0760                 | 603      | 27232<br>FERTILIZER POTASSIUM - K                 | 96.000<br>LB                   | _____      | _____ | _____      | _____ |
| 0770                 | 603      | 27250<br>LIME                                     | 7.200<br>TON                   | _____      | _____ | _____      | _____ |
| 0780                 | 303      | 27430<br>SILTATION CONTROL EXCAVATION             | 730.000<br>CY                  | _____      | _____ | _____      | _____ |
| 0790                 | 303      | 27505<br>TEMP. SILT FENCE TYPE A                  | 4,260.000<br>LF                | _____      | _____ | _____      | _____ |

Schedule of Items

Proposal ID: C0000106701N01      Oversight/State Project No.: 9999-009-348, M501  
 Order No.: F78      Federal Project No.: HRRR-009-2(063)

Contractor: \_\_\_\_\_

SECTION: 0002      ADDITIVE A

Cat Alt Set ID:      Cat Alt Mbr ID:

| Proposal<br>Line<br>Number | Spec<br>No. | Item ID<br>Description            | Approximate<br>Quantity and<br>Units | Unit Price        |       | Bid Amount |       |
|----------------------------|-------------|-----------------------------------|--------------------------------------|-------------------|-------|------------|-------|
|                            |             |                                   |                                      | Dollars           | Cents | Dollars    | Cents |
| 0800                       | 704         | 54020<br>TYPE A PVMT LINE MRKG 4" | 5,800.000<br>LF                      | _____             | _____ | _____      | _____ |
| <b>Section: 0002</b>       |             |                                   |                                      | <b>Total:</b>     |       | _____      |       |
|                            |             |                                   |                                      | <b>Total Bid:</b> |       | _____      |       |