

Schedule of Items

Proposal ID: C0000113389B26

Oversight/State Project No.: 0001-012-781, B626, C501

Order No.: F64

Federal Project No.: NHPP-BR04(347)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	513	00100 MOBILIZATION	LUMP SUM	LUMP SUM			
0020	517	00101 CONSTRUCTION SURVEYING CONSTRUCTION	LUMP SUM	LUMP SUM			
0030	308	10128 AGGR. BASE MATL. TY. I NO. 21B	9.000 TON				
0040	315	10608 ASPHALT CONCRETE TY. SM-12.5D	25.000 TON				
0050	515	10628 FLEXIBLE PAVEMENT PLANING 0" - 2"	94.000 SY				
0060	316	11070 SAW-CUT ASPH CONC FULL DEPTH	158.000 LF				
0070	316	11071 SAW-CUT HYD.CEM.CON.PAV FULL DEPTH	158.000 LF				
0080	505	13292 GUARDRAIL GR-8A NCHRP 350 TL-3	100.000 LF				
0090	505	13294 GUARDRAIL GR-8B NCHRP 350 TL-3	100.000 LF				
0100	505	13320 GUARDRAIL GR-2	100.000 LF				
0110	505	13372 SP. DES. GR.BR.ATTACH BR-GR -3D	4.000 EA				
0120	512	13495 TRAF. BARR. SER. CONC. SINGLE FACE PAR.MB-10A	360.000 LF				

Schedule of Items

Proposal ID: C0000113389B26

Oversight/State Project No.: 0001-012-781, B626, C501

Order No.: F64

Federal Project No.: NHPP-BR04(347)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0130	512	13496 TRAF. BARR. SER. CONC. DOUBLE FACE PAR.MB-11A	160.000 LF	_____	_____	_____	_____
0140	506	13530 RETAINING WALL RW-3	17.000 CY	_____	_____	_____	_____
0150	512	13604 IMPACT ATTEN. SER. TY. 1 TL- 3, >=40 MPH	2.000 EA	_____	_____	_____	_____
0160	512	24152 TYPE 3 BARRICADE 8'	6.000 EA	_____	_____	_____	_____
0170	512	24160 TEMPORARY (CONSTRUCTION) SIGN	656.000 SF	_____	_____	_____	_____
0180	512	24278 GROUP 2 CHANNELIZING DEVICES	34,868.000 DAY	_____	_____	_____	_____
0190	512	24279 PORTABLE CHANGEABLE MESSAGE SIGN	6,288.000 HR	_____	_____	_____	_____
0200	512	24288 WARNING LIGHT TY. B	70.000 DAY	_____	_____	_____	_____
0210	512	24293 TRAFFIC BARR. SERVICE CONCRETE (TCB-1)	50.000 LF	_____	_____	_____	_____
0220	508	24410 DEMOLITION OF PAVEMENT COMBINATION	25.000 SY	_____	_____	_____	_____
0230	505	24600 REMOVE EXISTING GUARDRAIL	382.000 LF	_____	_____	_____	_____
0240	ATTD	25565 PROGRESS SCHEDULE BASELINE	LUMP SUM	LUMP SUM	_____	_____	_____

Schedule of Items

Proposal ID: C0000113389B26

Oversight/State Project No.: 0001-012-781, B626, C501

Order No.: F64

Federal Project No.: NHPP-BR04(347)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0250	ATTD	25567 PROGRESS SCHEDULE UPDATES	16.000 EA	_____	_____	_____	_____
0260	704	54075 TYPE B CLASS VI PVMT LINE MRKG 4"	404.000 LF	_____	_____	_____	_____
0270	704	54079 TYPE B CLASS VI CONTRAST PVMT MRKG 4"	202.000 LF	_____	_____	_____	_____
0280	512	54457 TEMP. PVMT SYMBOL MRKG SINGLE TURN ARROW TY. A	3.000 EA	_____	_____	_____	_____
0290	512	54466 TYPE E TEMP. PVMT MRKG 6"	797.000 LF	_____	_____	_____	_____
0300	512	54542 TYPE D, CLASS III TEMP. PVMT MRKG 4"	2,915.000 LF	_____	_____	_____	_____
0310	512	54543 TYPE D, CLASS III TEMP. PVMT MRKG 6"	1,314.000 LF	_____	_____	_____	_____
0320	512	54544 TYPE D, CLASS III TEMP. PVMT MRKG 8"	1,290.000 LF	_____	_____	_____	_____
0330	404	60495 COVER DEPTH SURVEY	565.000 SY	_____	_____	_____	_____
0340	419	67260 BRIDGE CONDUIT SYSTEM .	LUMP SUM	LUMP SUM	_____	_____	_____
0350	430	67910 NBIS ACCESS, UNDER BRIDGE ACCESS UNDER BRIDGE	1.000 DAY	_____	_____	_____	_____
0360	412 ATTD	68042 CONCRETE INCIDENTAL CONCRETE REPAIR	13.600 CY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000113389B26

Oversight/State Project No.: 0001-012-781, B626, C501

Order No.: F64

Federal Project No.: NHPP-BR04(347)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0370	404	68090 BRIDGE DECK GROOVING	565.000 SY	_____	_____	_____	_____
0380	412	68172 CRACK REPAIR TYPE B	40.000 LF	_____	_____	_____	_____
0390	412	68180 EMBEDDED GALVANIC ANODES	2,228.000 EA	_____	_____	_____	_____
0400	412	68190 CONCRETE SURFACE COLOR COATING	539.000 SY	_____	_____	_____	_____
0410	426	68192 REPLACE BEARING	24.000 EA	_____	_____	_____	_____
0420	425	68315 TYPE A MILLING 1-1/2"	565.000 SY	_____	_____	_____	_____
0430	412	68332 H.E.S. PATCHING TYPE C	24.000 SY	_____	_____	_____	_____
0440	412	68339 DECK SLAB CLOSURE	40.000 SY	_____	_____	_____	_____
0450	416	68404 WATERPROOFING - EPOXY RESIN TYPE EP-5LV	65.000 SY	_____	_____	_____	_____
0460	411	68455 PRE.& SPOT COAT EX. STR. VIRGINIA STR. NO. 1033	619.000 SF	_____	_____	_____	_____
0470	411	68472 RECOAT EX. STR. NO. 1033 (TYPE B)	LUMP SUM	LUMP SUM	_____	_____	_____
0480	413	68476 ENV.& WORK. PROTECTION STR. NO. 1033	LUMP SUM	LUMP SUM	_____	_____	_____
0490	413	68492 MATERIAL DISPOSAL STR. NO. 1033 (TYPE B)	LUMP SUM	LUMP SUM	_____	_____	_____

Schedule of Items

Proposal ID: C0000113389B26

Oversight/State Project No.: 0001-012-781, B626, C501

Order No.: F64

Federal Project No.: NHPP-BR04(347)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0500	ATTD	68574 CLEAN AND RESEAL EXPANSION JOINT	103.000 LF	_____	_____	_____	_____
0510	412	68579 RECONSTRUCT BACK WALL, HES	97.000 LF	_____	_____	_____	_____
0520	412	68590 JACKING AND BLOCKING BEAM	24.000 EA	_____	_____	_____	_____
0530	412	68600 CONCRETE SUPERSTRUCT. SURFACE REPAIR	19.000 SY	_____	_____	_____	_____
0540	425	68616 PLACE VERY EARLY STRENGTH LATEX MODIFIED CONCRETE OVERLAY	565.000 SY	_____	_____	_____	_____
0550	425	68621 FURNISH VERY EARLY STRENGTH LATEX MOD. CONC. (1.5" - 2")	31.400 CY	_____	_____	_____	_____
0560	425	68642 TYPE A HYDRO-DEMOLITION 1/2"	537.000 SY	_____	_____	_____	_____
0570	413	68900 REM. PORT. OF EX. STR. NO. 1033	LUMP SUM	LUMP SUM	_____	_____	_____
0580	ATTD	68902 SUPERSTR. WID./REPAIR FILLET WELD	451.000 LF	_____	_____	_____	_____
0590	ATTD	68902 SUPERSTR. WID./REPAIR FULL PENETRATION GROOVE WELD	45.000 LF	_____	_____	_____	_____
0600	412	68902 SUPERSTR. WID./REPAIR RECONSTRUCT DECK OVERHANG	18.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000113389B26

Oversight/State Project No.: 0001-012-781, B626, C501

Order No.: F64

Federal Project No.: NHPP-BR04(347)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0610	ATTD	68903 BR. SUPERSTR. WID./REPAIR REPLACE CONCRETE CORBELS	20.000 CY	_____	_____	_____	_____
0620	ATTD	68904 SUPERSTR. WID./REPAIR REMOVE BLAST PLATES	8.000 EA	_____	_____	_____	_____
0630	430	68907 SUPERSTR. WID./REPAIR STRUCTURAL STEEL	23,210.000 LB	_____	_____	_____	_____
0640	401	69009 POROUS BACKFILL	8.000 CY	_____	_____	_____	_____
0650	401	69011 STRUCTURE EXCAVATION	71.000 CY	_____	_____	_____	_____
0660	412	69500 CONCRETE SUBSTRUCT. SURFACE REPAIR	66.000 SY	_____	_____	_____	_____
0670	414	69625 DRY RIPRAP CL. AI 20"	780.000 TON	_____	_____	_____	_____
0680	416	69835 WATERPROOFING - EPOXY RESIN TYPE EP-3B/EP-3T	55.000 SY	_____	_____	_____	_____
0690	ATTD	69900 BR. SUBSTR. WID./REPAIR GROUT PRESSURE INJECTION	5.000 CY	_____	_____	_____	_____
Section: 0001				Total:	_____	_____	_____
				Total Bid:	_____	_____	_____