

Schedule of Items

Proposal ID: C0000097715B01

Oversight/State Project No.: 00172-114-220, C501, B619

Order No.: B34

Federal Project No.: STP-5A03(987), STP-5A03(986)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS - BASE

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	513	00100 MOBILIZATION	LUMP SUM	LUMP SUM			
0020	517	00101 CONSTRUCTION SURVEYING CONSTRUCTION	LUMP SUM	LUMP SUM			
0030	301	00110 CLEARING AND GRUBBING	LUMP SUM	LUMP SUM			
0040	303	00120 REGULAR EXCAVATION	13,272.000 CY				
0050	305	00142 BORROW EXCAVATION MIN. CBR-20	26,168.000 CY				
0060	303	00211 MINOR STRUCTURE EXCAV. PIPE CULVERT	10.000 CY				
0070	305	00355 GEOTEXTILE SUBGRADE STABILIZATION	10,352.000 SY				
0080	402	00515 TEMPORARY SHEET PILING	8,600.000 SF				
0090	302 504	00525 CONCRETE CLASS A3 MISC.	9.520 CY				
0100	302	01120 12" PIPE	214.000 LF				
0110	302	01126 STORM SEWER PIPE 12"	806.000 LF				
0120	302	01150 15" PIPE	285.000 LF				
0130	302	01156 STORM SEWER PIPE 15"	4,972.000 LF				
0140	302	01186 STORM SEWER PIPE 18"	1,602.000 LF				

Schedule of Items

Proposal ID: C0000097715B01

Oversight/State Project No.: 00172-114-220, C501, B619

Order No.: B34

Federal Project No.: STP-5A03(987), STP-5A03(986)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS - BASE

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0150	302	01216 STORM SEWER PIPE 21"	698.000 LF	_____	_____	_____	_____
0160	302	01240 24" PIPE	36.000 LF	_____	_____	_____	_____
0170	302	01246 STORM SEWER PIPE 24"	710.000 LF	_____	_____	_____	_____
0180	302	01276 STORM SEWER PIPE 27"	116.000 LF	_____	_____	_____	_____
0190	302	01306 STORM SEWER PIPE 30"	1,373.000 LF	_____	_____	_____	_____
0200	ATTD	02112 DRAINAGE BACKFLOW PREVENTOR	3.000 EA	_____	_____	_____	_____
0210	ATTD	02112 DRAINAGE PREFAB YARD INLET	14.000 EA	_____	_____	_____	_____
0220	ATTD	02112 DRAINAGE SIDEWALK DRAIN	5.000 EA	_____	_____	_____	_____
0230	302	06120 12" END SECTION ES-1 OR 2	1.000 EA	_____	_____	_____	_____
0240	302	06150 15" END SECTION ES-1 OR 2	6.000 EA	_____	_____	_____	_____
0250	302	06180 18" END SECTION ES-1 OR 2	3.000 EA	_____	_____	_____	_____
0260	302	06740 DROP INLET DI-1	2.000 EA	_____	_____	_____	_____
0270	302	06745 DROP INLET DI-2A	1.000 EA	_____	_____	_____	_____
0280	302	06747 DROP INLET DI-2B,L=4'	1.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000097715B01

Oversight/State Project No.: 00172-114-220, C501, B619

Order No.: B34

Federal Project No.: STP-5A03(987), STP-5A03(986)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS - BASE

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0290	302	06748 DROP INLET DI-2B,L=6'	3.000 EA	_____	_____	_____	_____
0300	302	06766 DROP INLET DI-2C,L=8'	1.000 EA	_____	_____	_____	_____
0310	302	06815 DROP INLET DI-3A	9.000 EA	_____	_____	_____	_____
0320	302	06817 DROP INLET DI-3B,L=4'	30.000 EA	_____	_____	_____	_____
0330	302	06818 DROP INLET DI-3B,L=6'	8.000 EA	_____	_____	_____	_____
0340	302	06835 DROP INLET DI-3C,L=6'	1.000 EA	_____	_____	_____	_____
0350	302	06836 DROP INLET DI-3C,L=8'	4.000 EA	_____	_____	_____	_____
0360	302	06838 DROP INLET DI-3C,L=12'	3.000 EA	_____	_____	_____	_____
0370	302	06840 DROP INLET DI-3C,L=16'	2.000 EA	_____	_____	_____	_____
0380	302	08924 DROP INLET DI-12B,L=4'	10.000 EA	_____	_____	_____	_____
0390	302	08926 DROP INLET DI-12B,L=6'	6.000 EA	_____	_____	_____	_____
0400	302	08936 DROP INLET DI-12B,L=14'	2.000 EA	_____	_____	_____	_____
0410	302	09056 MANHOLE MH-1 OR 2	82.500 LF	_____	_____	_____	_____
0420	302	09057 FRAME & COVER MH-1	20.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000097715B01

Oversight/State Project No.: 00172-114-220, C501, B619

Order No.: B34

Federal Project No.: STP-5A03(987), STP-5A03(986)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS - BASE

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0430	414	09150 EROSION CONTROL STONE CLASS I, EC-1	168.800 TON	_____	_____	_____	_____
0440	308	10128 AGGR. BASE MATL. TY. I NO. 21B	6,874.000 TON	_____	_____	_____	_____
0450	309	10239 AGGR. MATL. NO. 25 OR 26	135.000 TON	_____	_____	_____	_____
0460	310	10417 TACK COAT	3,395.000 GAL	_____	_____	_____	_____
0470	315	10607 ASPHALT CONCRETE TY. SM-12.5A	447.000 TON	_____	_____	_____	_____
0480	315	10610 ASPHALT CONCRETE TY. IM-19.0A	5,058.000 TON	_____	_____	_____	_____
0490	515	10628 FLEXIBLE PAVEMENT PLANING 0" - 2"	1,169.000 SY	_____	_____	_____	_____
0500	515	10629 FLEXIBLE PAVEMENT PLANING ABOVE 2" - 4"	18,399.000 SY	_____	_____	_____	_____
0510	316	11040 CONCRETE ENTRANCE PAVE. 7"	65.000 SY	_____	_____	_____	_____
0520	315	11070 SAW-CUT ASPH CONC FULL DEPTH	9,143.000 LF	_____	_____	_____	_____
0530	502	12020 STD. CURB CG-2	860.000 LF	_____	_____	_____	_____
0540	502	12022 RADIAL CURB CG-2	128.000 LF	_____	_____	_____	_____
0550	502	12025 CURB 2" CURB AND GUTTER	100.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000097715B01

Oversight/State Project No.: 00172-114-220, C501, B619

Order No.: B34

Federal Project No.: STP-5A03(987), STP-5A03(986)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS - BASE

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0560	502	12030 STD. CURB CG-3	176.000 LF	_____	_____	_____	_____
0570	502	12600 STD. COMB. CURB & GUTTER CG-6	6,993.000 LF	_____	_____	_____	_____
0580	502	12610 RADIAL COMB. CURB & GUTTER CG-6	1,473.000 LF	_____	_____	_____	_____
0590	502	12700 STD. COMB. CURB & GUTTER CG-7	53.000 LF	_____	_____	_____	_____
0600	502	12940 ENTRANCE GUTTER CG-9D	285.000 SY	_____	_____	_____	_____
0610	504	13108 CG-12 DETECTABLE WARNING SURFACE	68.000 SY	_____	_____	_____	_____
0620	504	13220 HYDRAULIC CEMENT CONC. SIDEWALK 4"	7,308.000 SY	_____	_____	_____	_____
0630	505	13280 GUARDRAIL GR-MGS1	100.000 LF	_____	_____	_____	_____
0640	505	13286 GUARDRAIL TERMINAL GR-MGS2	3.000 EA	_____	_____	_____	_____
0650	505	13288 GUARDRAIL HEIGHT TRANSITION GR-MGS4	3.000 EA	_____	_____	_____	_____
0660	505	13383 FIXED OBJECT ATTACH. GR-FOA-1 TY. I	3.000 EA	_____	_____	_____	_____
0670	512	13496 TRAF. BARR. SER. CONC. DOUBLE FACE PAR.MB-11A	1,763.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000097715B01

Oversight/State Project No.: 00172-114-220, C501, B619

Order No.: B34

Federal Project No.: STP-5A03(987), STP-5A03(986)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS - BASE

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0680	512	13604 IMPACT ATTEN. SER. TY. 1 TL-3, >=40 MPH	9.000 EA	_____	_____	_____	_____
0690	315	16335 ASPHALT CONC. TY. SM-9.5A	1,819.000 TON	_____	_____	_____	_____
0700	315	16390 ASPH. CONC. TY. BM-25.0A	2,793.000 TON	_____	_____	_____	_____
0710	ATTD	16393 ASPH. CONC. PATCH TY. IM-19.0A	200.000 TON	_____	_____	_____	_____
0720	507	23570 HIGH VISIBILITY FENCE, 4'	100.000 LF	_____	_____	_____	_____
0730	511	24100 ALLAYING DUST	1,600.000 HR	_____	_____	_____	_____
0740	512	24152 TYPE 3 BARRICADE 8'	7.000 EA	_____	_____	_____	_____
0750	512	24160 TEMPORARY (CONSTRUCTION) SIGN	819.000 SF	_____	_____	_____	_____
0760	512	24272 TRUCK MOUNTED ATTENUATOR	650.000 HR	_____	_____	_____	_____
0770	512	24278 GROUP 2 CHANNELIZING DEVICES	383,270.000 DAY	_____	_____	_____	_____
0780	512	24281 ELECTRONIC ARROW BOARD	1,400.000 HR	_____	_____	_____	_____
0790	512	24282 FLAGGER SERVICE	1,230.000 HR	_____	_____	_____	_____
0800	512	24332 MODIFY SIGNAL (LANGLEY BLVD)	LUMP SUM	LUMP SUM	_____	_____	_____

Proposal ID: C0000097715B01

Oversight/State Project No.: 00172-114-220, C501, B619

Order No.: B34

Federal Project No.: STP-5A03(987), STP-5A03(986)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS - BASE

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0810	508	24420 DEMOLITION OF PAVEMENT RIGID	15.000 SY	_____	_____	_____	_____
0820	508	24430 DEMOLITION OF PAVEMENT FLEXIBLE	9,159.000 SY	_____	_____	_____	_____
0830	516	24502 REMOVE EXIST. D-3	1.000 EA	_____	_____	_____	_____
0840	516	24502 REMOVE EXIST. D-6	1.000 EA	_____	_____	_____	_____
0850	516	24502 REMOVE EXIST. D-7	1.000 EA	_____	_____	_____	_____
0860	516	24502 REMOVE EXIST. D-700	1.000 EA	_____	_____	_____	_____
0870	516	24502 REMOVE EXIST. D-8	1.000 EA	_____	_____	_____	_____
0880	516	24502 REMOVE EXIST. D-900	1.000 EA	_____	_____	_____	_____
0890	516	24502 REMOVE EXIST. PARCEL 005, D-2	1.000 EA	_____	_____	_____	_____
0900	516	24502 REMOVE EXIST. PARCEL 005, D-705	1.000 EA	_____	_____	_____	_____
0910	516	24502 REMOVE EXIST. PARCEL 005, D-907	1.000 EA	_____	_____	_____	_____
0920	516	24502 REMOVE EXIST. PARCEL 006, D-706	1.000 EA	_____	_____	_____	_____
0930	516	24502 REMOVE EXIST. PARCEL 007, D-707	1.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000097715B01

Oversight/State Project No.: 00172-114-220, C501, B619

Order No.: B34

Federal Project No.: STP-5A03(987), STP-5A03(986)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS - BASE

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0940	516	24502 REMOVE EXIST. PARCEL 011, D-701	1.000 EA	_____	_____	_____	_____
0950	516	24502 REMOVE EXIST. PARCEL 012, D-702	1.000 EA	_____	_____	_____	_____
0960	516	24502 REMOVE EXIST. PARCEL 029, D-708	1.000 EA	_____	_____	_____	_____
0970	516	24502 REMOVE EXIST. PARCEL 044, D-709	1.000 EA	_____	_____	_____	_____
0980	510	24503 REMOVE EXIST. D-1	LUMP SUM	LUMP SUM	_____	_____	_____
0990	510	24503 REMOVE EXIST. D-4	LUMP SUM	LUMP SUM	_____	_____	_____
1000	505	24600 REMOVE EXISTING GUARDRAIL	1,439.000 LF	_____	_____	_____	_____
1010	504	25002 HANDRAIL HR-1 TYPE I	4.000 LF	_____	_____	_____	_____
1020	504	25004 HANDRAIL HR-1 TYPE III	55.000 LF	_____	_____	_____	_____
1030	514	25506 FIELD OFFICE TY.II	38.000 MO	_____	_____	_____	_____
1040	ATTD	25565 PROGRESS SCHEDULE BASELINE	LUMP SUM	LUMP SUM	_____	_____	_____
1050	ATTD	25567 PROGRESS SCHEDULE UPDATES	38.000 EA	_____	_____	_____	_____
1060	602	27022 TOPSOIL CLASS B 2"	4.130 ACRE	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000097715B01

Oversight/State Project No.: 00172-114-220, C501, B619

Order No.: B34

Federal Project No.: STP-5A03(987), STP-5A03(986)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS - BASE

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1070	603	27101 TEMPORARY SEED	413.000 LB	_____	_____	_____	_____
1080	603	27102 REGULAR SEED	620.000 LB	_____	_____	_____	_____
1090	603	27103 OVERSEEDING	496.000 LB	_____	_____	_____	_____
1100	603	27111 HYDRAULIC EROSION CONTROL PRODUCT TYPE 2	23,172.000 SY	_____	_____	_____	_____
1110	603	27112 HYDRAULIC EROSION CONTROL PRODUCT TYPE 3	21,804.000 SY	_____	_____	_____	_____
1120	603	27230 FERTILIZER NITROGEN - N	395.000 LB	_____	_____	_____	_____
1130	603	27231 FERTILIZER PHOSPHOROUS - P	542.000 LB	_____	_____	_____	_____
1140	603	27232 FERTILIZER POTASSIUM - K	271.000 LB	_____	_____	_____	_____
1150	603	27250 LIME	18.590 TON	_____	_____	_____	_____
1160	ATTD	27275 EROSION CONTROL ELASTIC SIMPLEX OIL CONTAINMENT BOOM OR EQUIVALENT	2,352.000 LF	_____	_____	_____	_____
1170	606	27318 ROLLED EROSION CTRL PRODUCT EC-2 TYPE 1	360.000 SY	_____	_____	_____	_____
1180	303	27415 CHECK DAM ROCK TY. II	67.000 EA	_____	_____	_____	_____
1190	303	27422 DEWATERING BASIN EC-8	4.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000097715B01

Oversight/State Project No.: 00172-114-220, C501, B619

Order No.: B34

Federal Project No.: STP-5A03(987), STP-5A03(986)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS - BASE

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1200	303	27430 SILTATION CONTROL EXCAVATION	3,429.000 CY	_____	_____	_____	_____
1210	303	27451 INLET PROTECTION TYPE A	43.000 EA	_____	_____	_____	_____
1220	303	27461 INLET PROTECTION TYPE B	72.000 EA	_____	_____	_____	_____
1230	303	27504 TEMP. SILT FENCE TYPE B	400.000 LF	_____	_____	_____	_____
1240	303	27505 TEMP. SILT FENCE TYPE A	14,077.000 LF	_____	_____	_____	_____
1250	303	27525 TURBIDITY CURTAIN, PERVIOUS	3,042.000 LF	_____	_____	_____	_____
1260	303	27580 TEMP. SEDIMENT BASIN EXCAVATION	272.000 CY	_____	_____	_____	_____
1270	ATTD	38953 LANDSCAPE PERMANENT VEGETATIVE COVER	LUMP SUM	LUMP SUM	_____	_____	_____
1280	520	40002 3/4" WATER SERVICE LINE	2,663.000 LF	_____	_____	_____	_____
1290	520	40003 1" WATER SERVICE LINE	110.000 LF	_____	_____	_____	_____
1300	520	40005 1 1/2" WATER SERVICE LINE	25.000 LF	_____	_____	_____	_____
1310	520	40006 2" WATER SERVICE LINE	67.000 LF	_____	_____	_____	_____
1320	520	40020 2" WATER MAIN	20.000 LF	_____	_____	_____	_____
1330	520	40061 6" DI WATER MAIN	140.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000097715B01

Oversight/State Project No.: 00172-114-220, C501, B619

Order No.: B34

Federal Project No.: STP-5A03(987), STP-5A03(986)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS - BASE

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1340	520	40081 8" DI WATER MAIN	277.000 LF	_____	_____	_____	_____
1350	520	40121 12" DI WATER MAIN	2,781.000 LF	_____	_____	_____	_____
1360	520	40908 8" OFFSET EXIST. PIPE	40.000 LF	_____	_____	_____	_____
1370	520	40912 12" OFFSET EXIST. PIPE	70.000 LF	_____	_____	_____	_____
1380	ATTD	40992 WATER UTILITY 2" BALL VALVE & BOX	1.000 EA	_____	_____	_____	_____
1390	520	41006 6" GATE VALVE & BOX	3.000 EA	_____	_____	_____	_____
1400	520	41008 8" GATE VALVE & BOX	1.000 EA	_____	_____	_____	_____
1410	520	41012 12" GATE VALVE & BOX	5.000 EA	_____	_____	_____	_____
1420	510	41104 ADJUST EXIST. VALVE BOX	4.000 EA	_____	_____	_____	_____
1430	520	41400 12"X6" TAPPING SLEEVE VALVE & BOX	4.000 EA	_____	_____	_____	_____
1440	520	41413 12"X12" TAPPING SLEEVE VALVE & BOX	1.000 EA	_____	_____	_____	_____
1450	520	41820 FIRE HYDRANT	8.000 EA	_____	_____	_____	_____
1460	520	41970 5/8" WATER METER & BOX	55.000 EA	_____	_____	_____	_____
1470	520	41971 3/4" WATER METER & BOX	7.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000097715B01

Oversight/State Project No.: 00172-114-220, C501, B619

Order No.: B34

Federal Project No.: STP-5A03(987), STP-5A03(986)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS - BASE

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1480	520	41972 1" WATER METER & BOX	2.000 EA	_____	_____	_____	_____
1490	520	41974 1 1/2" WATER METER & BOX	1.000 EA	_____	_____	_____	_____
1500	520	41975 2" WATER METER & BOX	2.000 EA	_____	_____	_____	_____
1510	510	41977 ADJUST EXIST. WATER METER BOX	1.000 EA	_____	_____	_____	_____
1520	ATTD	41983 WATER FACILITIES 12" WATER MAIN BRIDGE ATTACHMENT	LUMP SUM	LUMP SUM	_____	_____	_____
1530	520	42044 4" SANITARY SERVICE LATERAL CONNECTION	1,113.000 LF	_____	_____	_____	_____
1540	520	42047 4" SANITARY SEWER FORCE MAIN	41.000 LF	_____	_____	_____	_____
1550	520	42060 6" SAN. SEWER PIPE	268.000 LF	_____	_____	_____	_____
1560	520	42064 6" SANITARY SERVICE LATERAL CONNECTION	175.000 LF	_____	_____	_____	_____
1570	520	42067 6" SANITARY SEWER FORCE MAIN	44.000 LF	_____	_____	_____	_____
1580	520	42080 8" SAN. SEWER PIPE	485.000 LF	_____	_____	_____	_____
1590	520	42087 8" SANITARY SEWER FORCE MAIN	20.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000097715B01

Oversight/State Project No.: 00172-114-220, C501, B619

Order No.: B34

Federal Project No.: STP-5A03(987), STP-5A03(986)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS - BASE

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1600	520	42207 20" SANITARY SEWER FORCE MAIN	3,420.000 LF	_____	_____	_____	_____
1610	520	42492 20" BEND FORCE MAIN	14.000 EA	_____	_____	_____	_____
1620	520	42502 20" BRANCH FORCE MAIN	2.000 EA	_____	_____	_____	_____
1630	520	42512 20" PLUG OR CAP FORCE MAIN	2.000 EA	_____	_____	_____	_____
1640	520	42608 8" VALVE & BOX FORCE MAIN	4.000 EA	_____	_____	_____	_____
1650	520	42620 20" VALVE & BOX FORCE MAIN	3.000 EA	_____	_____	_____	_____
1660	510	42635 ADJUST EXISTING VALVE BOX-FORCE MAIN	3.000 EA	_____	_____	_____	_____
1670	520	42755 SANITARY SEWER MANHOLE	29.000 LF	_____	_____	_____	_____
1680	520	42764 MANHOLE FRAME & COVER F&C-1	5.000 EA	_____	_____	_____	_____
1690	510	42765 ADJUST EXIST FRAME & COVER	7.000 EA	_____	_____	_____	_____
1700	520	42788 2" AIR RELEASE VALVE & BOX FORCE MAIN	5.000 EA	_____	_____	_____	_____
1710	520	42845 4" SEWER CLEANOUT	35.000 EA	_____	_____	_____	_____
1720	520	42846 6" SEWER CLEANOUT	3.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000097715B01

Oversight/State Project No.: 00172-114-220, C501, B619

Order No.: B34

Federal Project No.: STP-5A03(987), STP-5A03(986)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS - BASE

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1730	ATTD	44301 SEWER UTILITY 2" FORCE MAIN CONNECTION	1.000 EA	_____	_____	_____	_____
1740	509	45640 FLOWABLE BACKFILL UTILITY	340.000 CY	_____	_____	_____	_____
1750	520	49000 SANITARY SEWER 2" PVC SANITARY SEWER FORCE MAIN	1,213.000 LF	_____	_____	_____	_____
1760	ATTD	49001 SANITARY SEWER 20" LINE STOP FORCE MAIN BY PASS	1.000 EA	_____	_____	_____	_____
1770	ATTD	49001 SANITARY SEWER 20" SOLID SLEEVE FORCE MAIN	2.000 EA	_____	_____	_____	_____
1780	ATTD	49005 SANITARY SEWER FLOW METER VAULT FORCE MAIN	LUMP SUM	LUMP SUM	_____	_____	_____
1790	701	50108 SIGN PANEL	715.300 SF	_____	_____	_____	_____
1800	700	50300 REMOVE EXISTING 1 POST SIGN STRUCTURE	27.000 EA	_____	_____	_____	_____
1810	700	50320 REMOVE EXISTING 1 POST SIGN PANEL	6.000 EA	_____	_____	_____	_____
1820	700	50322 REMOVE EXISTING 2 POST SIGN PANEL	1.000 EA	_____	_____	_____	_____
1830	700	50340 RELOCATE EXISTING 1 POST GROUND MOUNTED SIGN PANEL	6.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000097715B01

Oversight/State Project No.: 00172-114-220, C501, B619

Order No.: B34

Federal Project No.: STP-5A03(987), STP-5A03(986)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS - BASE

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1840	700	50381 SIGN STRUCTURE, OVERHEAD SPAN BRIDGE MOUNTED	2.000 EA	_____	_____	_____	_____
1850	700	50430 SIGN POST STP-1, 2", 14 GAUGE	34.000 LF	_____	_____	_____	_____
1860	700	50432 SIGN POST STP-1, 2 3/16", 10 GAUGE	60.000 LF	_____	_____	_____	_____
1870	700	50434 SIGN POST STP-1, 2 1/2", 10 GAUGE	116.000 LF	_____	_____	_____	_____
1880	700	50436 SIGN POST STP-1, 2 1/2", 12 GAUGE	145.500 LF	_____	_____	_____	_____
1890	700	50485 CONCRETE SIGN FOUNDATION STP-1, TYPE A	18.000 EA	_____	_____	_____	_____
1900	700	50486 CONCRETE SIGN FOUNDATION STP-1, TYPE B	11.000 EA	_____	_____	_____	_____
1910	703	51030 LOCAL CONTROLLER, TY. A	3.000 EA	_____	_____	_____	_____
1920	703	51184 TRAFFIC SIGNAL HEAD SECTION 12" LED	79.000 EA	_____	_____	_____	_____
1930	703	51198 PEDESTRIAN ACTUATION PA- 2	7.000 EA	_____	_____	_____	_____
1940	703	51200 PEDESTRIAN ACTUATION PA- 4	1.000 EA	_____	_____	_____	_____
1950	700	51238 CONCRETE FOUNDATION SIGNAL POLE PF-8	219.000 CY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000097715B01

Oversight/State Project No.: 00172-114-220, C501, B619

Order No.: B34

Federal Project No.: STP-5A03(987), STP-5A03(986)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS - BASE

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1960	700	51245 CONCRETE FOUNDATION CF-1	3.000 EA	_____	_____	_____	_____
1970	700	51246 CONCRETE FOUND. CF-2	1.000 EA	_____	_____	_____	_____
1980	700	51426 MAST ARM MAST ARM 35'	2.000 EA	_____	_____	_____	_____
1990	700	51426 MAST ARM MAST ARM 45'	1.000 EA	_____	_____	_____	_____
2000	700	51475 SIGNAL MAST ARM POLE MP-3, TYPE A	11.000 EA	_____	_____	_____	_____
2010	700	51477 SIGNAL MAST ARM POLE MP-3, TYPE B2	7.000 EA	_____	_____	_____	_____
2020	700	51478 SIGNAL MAST ARM POLE MP-3, TYPE C	1.000 EA	_____	_____	_____	_____
2030	700	51479 SIGNAL MAST ARM POLE MP-3, TYPE D	8.000 EA	_____	_____	_____	_____
2040	700	51482 SIGNAL MAST ARM POLE MP-3, TYPE F	1.000 EA	_____	_____	_____	_____
2050	700	51485 MAST ARM 30'	3.000 EA	_____	_____	_____	_____
2060	700	51486 MAST ARM 40'	4.000 EA	_____	_____	_____	_____
2070	700	51487 MAST ARM 49'	10.000 EA	_____	_____	_____	_____
2080	703	51524 EVP DETECTION SYSTEM 4-WAY	3.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000097715B01

Oversight/State Project No.: 00172-114-220, C501, B619

Order No.: B34

Federal Project No.: STP-5A03(987), STP-5A03(986)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS - BASE

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
2090	703	51525 EVP DETECTOR CABLE	1,250.000 LF	_____	_____	_____	_____
2100	700	51601 14/3 CONDUCTOR CABLE	684.000 LF	_____	_____	_____	_____
2110	700	51603 14/5 CONDUCTOR CABLE	4,506.000 LF	_____	_____	_____	_____
2120	700	51607 14/7 CONDUCTOR CABLE	2,052.000 LF	_____	_____	_____	_____
2130	703	51830 HANGER ASSEMBLY SM-3, ONE WAY	23.000 EA	_____	_____	_____	_____
2140	703	51838 HANGER ASSEMBLY SMB-3, ONE WAY	8.000 EA	_____	_____	_____	_____
2150	ATTD	51932 RELOCATE EXISTING SIGN PANEL AND SIGN STRUCTURE	1.000 EA	_____	_____	_____	_____
2160	703	51933 REMOVE EXISTING POLE	6.000 EA	_____	_____	_____	_____
2170	703	51934 REMOVE EXISTING FOUNDATION	6.000 EA	_____	_____	_____	_____
2180	703	51935 REMOVE EXISTING SIGNAL HEAD	14.000 EA	_____	_____	_____	_____
2190	703	51936 REMOVE EXISTING CONTROLLER	2.000 EA	_____	_____	_____	_____
2200	703	51994 UNINTERRUPTIBLE POWER SUPPLY TYPE 2	12.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000097715B01

Oversight/State Project No.: 00172-114-220, C501, B619

Order No.: B34

Federal Project No.: STP-5A03(987), STP-5A03(986)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS - BASE

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
2210	703	51995 UNINTERRUPTIBLE POWER SUPPLY BATTERY PACK	12.000 EA	_____	_____	_____	_____
2220	703	51996 UNINTERRUPTIBLE POWER SUPPLY CABINET ATTACHED	3.000 EA	_____	_____	_____	_____
2230	ATTD	52001 TRAFFIC SIGNALIZATION CATEGORY-6 OUTDOOR RATED CABLE	292.000 LF	_____	_____	_____	_____
2240	ATTD	52002 TRAFFIC SIGNALIZATION 360 DEGREE CAMERA MOUNTING BRACKET	3.000 EA	_____	_____	_____	_____
2250	ATTD	52002 TRAFFIC SIGNALIZATION 360 DEGREE VIDEO DETECTION CAMERA	3.000 EA	_____	_____	_____	_____
2260	ATTD	52002 TRAFFIC SIGNALIZATION ELECTRICAL SERVICE SE-1 TYPE B MODIFIED	7.000 EA	_____	_____	_____	_____
2270	ATTD	52002 TRAFFIC SIGNALIZATION ELECTRICAL SERVICE SE-6 MODIFIED	1.000 EA	_____	_____	_____	_____
2280	ATTD	52002 TRAFFIC SIGNALIZATION LANE USE CONTROL SIGNAL, LANE CONTROL SIGNS (LCS)	33.000 EA	_____	_____	_____	_____
2290	ATTD	52002 TRAFFIC SIGNALIZATION LANE USE CONTROL SIGNAL, REVERSIBLE LANE CONTROL SIGNS (RLC), TYPE 1	16.000 EA	_____	_____	_____	_____

Proposal ID: C0000097715B01

Oversight/State Project No.: 00172-114-220, C501, B619

Order No.: B34

Federal Project No.: STP-5A03(987), STP-5A03(986)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS - BASE

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
2300	ATTD	52002 TRAFFIC SIGNALIZATION LANE USE CONTROL SIGNAL, REVERSIBLE LANE CONTROL SIGNS (RLC), TYPE 2	2.000 EA	_____	_____	_____	_____
2310	ATTD	52002 TRAFFIC SIGNALIZATION LANE USE CONTROL SIGNAL, REVERSIBLE LANE CONTROL SIGNS (RLC), TYPE 3	1.000 EA	_____	_____	_____	_____
2320	ATTD	52002 TRAFFIC SIGNALIZATION LCS / RLC SIGNAL CONTROLLER AND CABINET	8.000 EA	_____	_____	_____	_____
2330	ATTD	52002 TRAFFIC SIGNALIZATION MAST ARM VIBRATION DAMPER	3.000 EA	_____	_____	_____	_____
2340	ATTD	52002 TRAFFIC SIGNALIZATION MONITOR	3.000 EA	_____	_____	_____	_____
2350	ATTD	52002 TRAFFIC SIGNALIZATION REVERSIBLE LANE USE CONTROL SIGNAL, LANE CONTROL SIGNS (RLC) TYPE 3	2.000 EA	_____	_____	_____	_____
2360	512	52002 TRAFFIC SIGNALIZATION TEMPORARY TRAFFIC CONTROL SIGNAL (VOYAGER DRIVE)	1.000 EA	_____	_____	_____	_____
2370	ATTD	52002 TRAFFIC SIGNALIZATION TYPE A LOCAL CONTROLLER (LANE CONTROL)	2.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000097715B01

Oversight/State Project No.: 00172-114-220, C501, B619

Order No.: B34

Federal Project No.: STP-5A03(987), STP-5A03(986)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS - BASE

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
2380	ATTD	52002 TRAFFIC SIGNALIZATION UNINTERRUPTIBLE POWER SUPPLY CABINET, POLE MOUNTED	9.000 EA	_____	_____	_____	_____
2390	ATTD	52002 TRAFFIC SIGNALIZATION USB MOUSE	3.000 EA	_____	_____	_____	_____
2400	ATTD	52002 TRAFFIC SIGNALIZATION VIDEO DETECTION UNIT	3.000 EA	_____	_____	_____	_____
2410	703	52404 PEDESTRIAN SIGNAL HEAD SP-9	8.000 EA	_____	_____	_____	_____
2420	700	52424 ELECTRICAL SERVICE SE-3 TYPE A	3.000 EA	_____	_____	_____	_____
2430	704	54032 TYPE B CLASS I PVMT LINE MRKG 4"	21,148.000 LF	_____	_____	_____	_____
2440	704	54034 TYPE B CLASS I PVMT LINE MRKG 6"	1,591.000 LF	_____	_____	_____	_____
2450	704	54040 TYPE B CLASS I PVMT LINE MRKG 12"	35.000 LF	_____	_____	_____	_____
2460	704	54042 TYPE B CLASS I PAVE. LINE MARKING 24"	1,208.000 LF	_____	_____	_____	_____
2470	512	54105 ERADICATE EXIST. LINEAR PVMT MARKING	19,054.000 LF	_____	_____	_____	_____
2480	512	54106 ERADICATE EXIST. NONLINEAR PVMT MRKG	615.000 SF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000097715B01

Oversight/State Project No.: 00172-114-220, C501, B619

Order No.: B34

Federal Project No.: STP-5A03(987), STP-5A03(986)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS - BASE

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
2490	ATTD	54219 INLAID PAVEMENT MARKER ASPHALT	236.000 EA	_____	_____	_____	_____
2500	704	54400 PVMT MESSAGE MARK. ONLY	1.000 EA	_____	_____	_____	_____
2510	512	54457 TEMP. PVMT SYMBOL MRKG SINGLE TURN ARROW TY. A	2.000 EA	_____	_____	_____	_____
2520	512	54512 TYPE D, CLASS II TEMP. PVMT MRKG 4"	28,412.000 LF	_____	_____	_____	_____
2530	512	54524 TYPE D, CLASS II TEMP. PVMT MRKG 24"	397.000 LF	_____	_____	_____	_____
2540	704	54574 PVMT SYMB MRKG SGL TURN ARROW TY B, CL I	10.000 EA	_____	_____	_____	_____
2550	704	54577 PVMT SYMB MRKG DBL TURN ARROW THRU/LT OR RT TY B, CL I	10.000 EA	_____	_____	_____	_____
2560	704	54589 PVMT SYMB MRKG LANE REDUCTION ARROW TY B, CL I	2.000 EA	_____	_____	_____	_____
2570	700	55080 8 CONDUCTOR CABLE	4,876.000 LF	_____	_____	_____	_____
2580	700	55126 CONDUCTOR CABLE, NO. 8 EGC	2,127.000 LF	_____	_____	_____	_____
2590	700	55179 LUMINAIRE ARM 12'	9.000 EA	_____	_____	_____	_____
2600	705	55352 CONTROL CENTER CCW-1 TYPE C	1.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000097715B01

Oversight/State Project No.: 00172-114-220, C501, B619

Order No.: B34

Federal Project No.: STP-5A03(987), STP-5A03(986)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS - BASE

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
2610	700	55385 ELECTRICAL SERVICE WORK PAD	14.000 EA	_____	_____	_____	_____
2620	705	55505 LUMINAIRE 59 WATT LED	19.000 EA	_____	_____	_____	_____
2630	700	55586 JUNCTION BOX JB-S1	22.000 EA	_____	_____	_____	_____
2640	700	55587 JUNCTION BOX JB-S2	24.000 EA	_____	_____	_____	_____
2650	700	55588 JUNCTION BOX JB-S3	14.000 EA	_____	_____	_____	_____
2660	700	56014 ELECT. SER. GRD. ELECTRODE 10'	55.000 EA	_____	_____	_____	_____
2670	700	56021 1" PVC CONDUIT	40.000 LF	_____	_____	_____	_____
2680	700	56026 1 1/4" METAL CONDUIT	42.000 LF	_____	_____	_____	_____
2690	700	56032 2" METAL CONDUIT	25.000 LF	_____	_____	_____	_____
2700	700	56040 4" METAL CONDUIT	155.000 LF	_____	_____	_____	_____
2710	ATTD	56042 CONDUIT 1" FLEXIBLE METAL CONDUIT TYPE LFMC	20.000 LF	_____	_____	_____	_____
2720	ATTD	56042 CONDUIT 2" FLEXIBLE METAL CONDUIT TYPE LFMC	50.000 LF	_____	_____	_____	_____
2730	700	56051 BORED CONDUIT 3"	1,235.000 LF	_____	_____	_____	_____
2740	700	56052 BORED CONDUIT 4"	1,781.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000097715B01

Oversight/State Project No.: 00172-114-220, C501, B619

Order No.: B34

Federal Project No.: STP-5A03(987), STP-5A03(986)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS - BASE

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
2750	700	56053 2" PVC CONDUIT	30.000 LF	_____	_____	_____	_____
2760	700	56054 3" PVC CONDUIT	4,234.000 LF	_____	_____	_____	_____
2770	700	56055 4" PVC CONDUIT	41.000 LF	_____	_____	_____	_____
2780	700	56200 TRENCH EXCAVATION ECI-1	4,508.000 LF	_____	_____	_____	_____
2790	700	56205 TEST BORE	19.000 EA	_____	_____	_____	_____
2800	801	57011 ITS CONTROLLER CABINET POLE MOUNTED	1.000 EA	_____	_____	_____	_____
2810	803	57060 CCTV CAMERA DIGITAL	6.000 EA	_____	_____	_____	_____
2820	803	57080 CCTV COMPOSITE CABLE ..	525.000 LF	_____	_____	_____	_____
2830	807	57191 900 MHZ WIRELESS ETHERNET DISTRIBUTION RADIO	2.000 EA	_____	_____	_____	_____
2840	808	57202 FIBER OPTIC CABLE 96 STRAND	9,265.000 LF	_____	_____	_____	_____
2850	808	57203 FIBER OPTIC DROP CABLE 12 STRAND	1,745.000 LF	_____	_____	_____	_____
2860	808	57204 PRE-TERMINATED FIBER PATCH PANEL	10.000 EA	_____	_____	_____	_____
2870	808	57210 UNDERGROUND SPLICE ENCLOSURE	10.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000097715B01

Oversight/State Project No.: 00172-114-220, C501, B619

Order No.: B34

Federal Project No.: STP-5A03(987), STP-5A03(986)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS - BASE

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
2880	808	57215 FIBER DISTRIBUTION CENTER	3.000 EA	_____	_____	_____	_____
2890	809	57227 DISTRIBUTION SFP MODULE 1Gbps, LC, AND SHORT HAUL	32.000 EA	_____	_____	_____	_____
2900	ATTD	59050 COMMUNICATION EQUIP. LAYER 2 ETHERNET SWITCH	13.000 EA	_____	_____	_____	_____
2910	ATTD	59050 COMMUNICATION EQUIP. LAYER 3 ETHERNET SWITCH	1.000 EA	_____	_____	_____	_____
2920	ATTD	59050 COMMUNICATION EQUIP. LAYER 3 SWITCH	2.000 EA	_____	_____	_____	_____
2930	ATTD	59050 COMMUNICATION EQUIP. WRONG WAY DETECTION SYSTEM	3.000 EA	_____	_____	_____	_____
2940	ATTD	59060 COMMUNICATION EQUIP. ADVANCED TRAFFIC MANAGEMENT SYSTEM SERVER AND SOFTWARE	LUMP SUM	LUMP SUM	_____	_____	_____
2950	ATTD	59060 COMMUNICATION EQUIP. DEMONSTRATION TEST	LUMP SUM	LUMP SUM	_____	_____	_____
2960	ATTD	59060 COMMUNICATION EQUIP. EXISTING FIBER OPTIC CABLE TESTING	LUMP SUM	LUMP SUM	_____	_____	_____
2970	ATTD	59060 COMMUNICATION EQUIP. WRONG WAY DETECTION MANAGEMENT SOFTWARE AND SERVER	LUMP SUM	LUMP SUM	_____	_____	_____

Schedule of Items

Proposal ID: C0000097715B01

Oversight/State Project No.: 00172-114-220, C501, B619

Order No.: B34

Federal Project No.: STP-5A03(987), STP-5A03(986)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS - BASE

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
2980	ATTD	59071 COMMUNICATION EQUIP. WRONG WAY DETECTOR CABLE	300.000 LF	_____	_____	_____	_____
2990	ATTD	60125 BRIDGE TEMPORARY SHORING	LUMP SUM	LUMP SUM	_____	_____	_____
3000	404	60409 CONC. CLASS A4 MOD. LOW SHRINKAGE	1,979.800 CY	_____	_____	_____	_____
3010	404	60490 BRIDGE DECK GROOVING	6,605.000 SY	_____	_____	_____	_____
3020	404	60495 COVER DEPTH SURVEY	6,605.000 SY	_____	_____	_____	_____
3030	405	61214 PREST.CONC.BEAM,BULB-T 37" DEPTH +60'-70'	20.000 EA	_____	_____	_____	_____
3040	405	61223 PREST.CONC.BEAM,BULB-T 45" DEPTH +70-80'	80.000 EA	_____	_____	_____	_____
3050	406	61712 CORROSION RESISTANT REINF. STEEL CL. II	353,310.000 LB	_____	_____	_____	_____
3060	410	62030 RAILING,KANSAS CORRAL 27" W/CURB	137.000 LF	_____	_____	_____	_____
3070	410	62031 RAILING,KANSAS CORRAL 27" W/OUT CURB	3,169.000 LF	_____	_____	_____	_____
3080	512	62115 TRAF. BARR. SER. CONC. SINGLE FACE PARAPET MB- 10A	111.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000097715B01

Oversight/State Project No.: 00172-114-220, C501, B619

Order No.: B34

Federal Project No.: STP-5A03(987), STP-5A03(986)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS - BASE

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
3090	423	62403 TOOTH EXPANSION JOINT ASSEMBLY 2-1/4"	81.000 LF	_____	_____	_____	_____
3100	420	62414 ADHESIVE BASED JOINT SEALER CLASS I, 3"	34.000 LF	_____	_____	_____	_____
3110	ATTD	62534 BRIDGE SUPERSTRUCTURE ELASTIC INCLUSION (14" EPS)	30.000 SY	_____	_____	_____	_____
3120	401	64011 STRUCTURE EXCAVATION	1,083.000 CY	_____	_____	_____	_____
3130	401	64015 SELECT BACKFILL ABUTMENT ZONE	867.000 TON	_____	_____	_____	_____
3140	401	64032 GEOCOMPOSITE WALL DRAIN	23.000 SY	_____	_____	_____	_____
3150	402	64040 SHEET PILES STEEL	7,915.000 SF	_____	_____	_____	_____
3160	403	64082 TREATED TIMBER PILES 12"	5,500.000 LF	_____	_____	_____	_____
3170	403	64512 PRESTR. CONC STAINLESS STEEL STRAND PILES 12"	1,890.000 LF	_____	_____	_____	_____
3180	403	64524 PRESTR. CONC STAINLESS STEEL STRAND PILES 24"	8,946.000 LF	_____	_____	_____	_____
3190	403	64612 PRESTR. CONC CFRP STRAND PILES 12"	1,890.000 LF	_____	_____	_____	_____
3200	403	64624 PRESTR. CONC CFRP STRAND PILES 24"	8,946.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000097715B01

Oversight/State Project No.: 00172-114-220, C501, B619

Order No.: B34

Federal Project No.: STP-5A03(987), STP-5A03(986)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS - BASE

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
3210	403	64751 DRIVING TEST FOR TIMBER PILE	165.000 LF	_____	_____	_____	_____
3220	403	64875 PILE DRIVING TEST FOR 12" PSC STAINLESS STEEL OR CFRP STRAND PILE	177.000 LF	_____	_____	_____	_____
3230	403	64875 PILE DRIVING TEST FOR 24" PSC STAINLESS STEEL OR CFRP STRAND PILE	659.000 LF	_____	_____	_____	_____
3240	404	65013 CONCRETE CLASS A3	637.500 CY	_____	_____	_____	_____
3250	406	65211 CORROSION RESISTANT REINF. STEEL CL. I	94,850.000 LB	_____	_____	_____	_____
3260	504	65810 RAILING MODIFIED HANDRAIL HR-1 TYPE II	222.000 LF	_____	_____	_____	_____
3270	414	66127 DRY RIPRAP CL.I 26"	358.000 TON	_____	_____	_____	_____
3280	ATTD	66924 BRIDGE SUBSTRUCTURE PRECAST CONCRETE CAPS - EMBANKMENT STABILIZATION	113.000 EA	_____	_____	_____	_____
3290	ATTD	66925 BRIDGE SUBSTRUCTURE LIGHTWEIGHT AGGREGATE BACKFILL - CARYS CHAPEL	1,138.000 TON	_____	_____	_____	_____
3300	ATTD	66925 BRIDGE SUBSTRUCTURE LIGHTWEIGHT AGGREGATE BACKFILL - EMBANKMENT STABILIZATION	737.000 TON	_____	_____	_____	_____

Proposal ID: C0000097715B01

Oversight/State Project No.: 00172-114-220, C501, B619

Order No.: B34

Federal Project No.: STP-5A03(987), STP-5A03(986)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS - BASE

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
3310	ATTD	67260 BRIDGE CONDUIT SYSTEM TELEPHONE CONDUIT SYSTEM	LUMP SUM	LUMP SUM		_____.	_____.
3320	ATTD	67904 BRIDGE INCIDENTALS TEMPORARY WORK BRIDGE	LUMP SUM	LUMP SUM		_____.	_____.
3330	430	67910 NBIS ACCESS, UNDER BRIDGE (B619)	5.000 DAY		_____.	_____.	_____.
3340	404	68043 CONC. CLASS A4 MOD.LOW SHRINKAGE	130.000 CY		_____.	_____.	_____.
3350	316	68265 CONC. CLASS A-4 BRIDGE APPR. SLAB	42.900 CY		_____.	_____.	_____.
3360	316	68270 REINF. STEEL BRIDGE APPR. SLAB	5,964.000 LB		_____.	_____.	_____.
3370	413	68900 REM. PORT. OF EX. STR. NO. 1901	LUMP SUM	LUMP SUM		_____.	_____.
3380	403	69426 DYNAMIC PILE TEST	12.000 EA		_____.	_____.	_____.
Section: 0001				Total:		_____.	_____.

Proposal ID: C0000097715B01

Oversight/State Project No.: 00172-114-220, C501, B619

Order No.: B34

Federal Project No.: STP-5A03(987), STP-5A03(986)

Contractor: _____

SECTION: 0002

BID ADDITIVE #1

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
3390	315	10610 ASPHALT CONCRETE TY. IM-19.0A	88.000 TON	_____	_____	_____	_____
3400	515	10625 FLEXIBLE PAVE. TIE-IN PLANING 0" - 2"	11,901.000 SY	_____	_____	_____	_____
3410	ATTD	11070 SAW-CUT ASPH CONC FULL DEPTH	1,000.000 LF	_____	_____	_____	_____
3420	315	16378 THIN HOT MIX ASPHALT CONCRETE	506.000 TON	_____	_____	_____	_____
3430	512	24282 FLAGGER SERVICE	140.000 HR	_____	_____	_____	_____
3440	704	54032 TYPE B CLASS I PVMT LINE MRKG 4"	12,400.000 LF	_____	_____	_____	_____
3450	704	54042 TYPE B CLASS I PAVE. LINE MARKING 24"	100.000 LF	_____	_____	_____	_____
Section: 0002				Total:		_____	
				Total Bid:		_____	