

Schedule of Items

Proposal ID: CM522PMG118744 Oversight/State Project No.: PM5G-001-731,P401

Order No.: 567

Federal Project No.: PM05(462)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	310	10417 TACK COAT	44,951.000 GAL	_____	_____	_____	_____
0020	ATTD	10497 PAVEMENT CRACK SEAL TY C	2,800.000 LB	_____	_____	_____	_____
0030	315	10700 RUMBLE STRIP CYLINDRICAL ASPHALT	53,676.000 LF	_____	_____	_____	_____
0040	ATTD	16242 AGGR. BASE MATL. TY. I OR II NO. 21A OR 21B	357.190 TON	_____	_____	_____	_____
0050	315	16355 ASPHALT CONC. TY. SM- 12.5D	41,688.840 TON	_____	_____	_____	_____
0060	ATTD	16394 ASPH. CONC. PATCH TY. IM- 19.0D	60.000 TON	_____	_____	_____	_____
0070	515	16522 FLEXIBLE PAVEMENT PLANING 0" - 2"	451,862.390 SY	_____	_____	_____	_____
0080	ATTD	24265 MAINTENANCE OF TRAFFIC PLANT MIX LUMP SUM	LUMP SUM	LUMP SUM	_____	_____	_____
0090	512	24282 FLAGGER SERVICE	665.000 HR	_____	_____	_____	_____
0100	700	51615 14/1 ENCLOSED COND. CABLE	4,180.000 LF	_____	_____	_____	_____
0110	703	51912 LOOP SAW CUT 3/8"	1,000.000 LF	_____	_____	_____	_____
0120	703	51913 LOOP SAWCUT 5/8"	4,180.000 LF	_____	_____	_____	_____
0130	704	54020 TYPE A PVMT LINE MRKG 4"	49,983.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: CM522PMG118744 Oversight/State Project No.: PM5G-001-731,P401

Order No.: 567

Federal Project No.: PM05(462)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0140	704	54032 TYPE B CLASS I PVMT LINE MRKG 4"	203,384.000 LF	_____	_____	_____	_____
0150	704	54034 TYPE B CLASS I PVMT LINE MRKG 6"	144,814.000 LF	_____	_____	_____	_____
0160	704	54040 TYPE B CLASS I PVMT LINE MRKG 12"	860.000 LF	_____	_____	_____	_____
0170	704	54042 TYPE B CLASS I PAVE. LINE MARKING 24"	1,182.000 LF	_____	_____	_____	_____
0180	ATTD	54100 PAVEMENT MARKING RAISED RUMBLE STRIPS	192.000 LF	_____	_____	_____	_____
0190	512	54105 ERADICATE EXIST. LINEAR PVMT MARKING	15,725.000 LF	_____	_____	_____	_____
0200	512	54106 ERADICATE EXIST. NONLINEAR PVMT MRKG	160.000 SF	_____	_____	_____	_____
0210	ATTD	54219 INLAID PAVEMENT MARKER ASPHALT	1,338.000 EA	_____	_____	_____	_____
0220	704	54404 PVMT MESSAGE MARK. R/R CROSSING	1.000 EA	_____	_____	_____	_____
0230	512	54428 TEMP. PVMT MRKG, TY. A, 4"	44,309.000 LF	_____	_____	_____	_____
0240	512	54430 TEMP. PVMT MRKG, TY. A, 6"	15,580.000 LF	_____	_____	_____	_____
0250	512	54436 TEMP. PVMT MRKG, TY. A, 12"	1,740.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: CM522PMG118744 Oversight/State Project No.: PM5G-001-731,P401
 Order No.: 567 Federal Project No.: PM05(462)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0260	704	54574 PVMT SYMB MRKG SGL TURN ARROW TY B, CL I	137.000 EA	_____	_____	_____	_____
0270	704	54577 PVMT SYMB MRKG DBL TURN ARROW THRU/LT OR RT TY B, CL I	2.000 EA	_____	_____	_____	_____
Section: 0001				Total:	_____	_____	_____

SECTION: 0002 ALTERNATE BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0280	ATTD	16243 SHOULDER MAINTENANCE MATERIAL	1.000 TON	_____	_____	_____	_____
Section: 0002				Total:	_____	_____	_____
				Total Bid:	_____	_____	_____