

Schedule of Items

Proposal ID: CM422PM2119810 Oversight/State Project No.: PM42-964-F22, P401

Order No.: G18

Federal Project No.: PM04(498)

Contractor: \_\_\_\_\_

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	310	10417 TACK COAT	31,034.000 GAL	_____	_____	_____	_____
0020	315	10700 RUMBLE STRIP CYLINDRICAL ASPHALT	57,446.800 LF	_____	_____	_____	_____
0030	ATTD	15305 PATCH CEMENT CONC. PAVE., TYPE IV-A	1,066.000 SY	_____	_____	_____	_____
0040	ATTD	15309 PAVEMENT PARTIAL DEPTH PCC PATCHING (MAT. TYPE IM 19.0D UP TO 4 "DEEP)	280.000 SY	_____	_____	_____	_____
0050	315	16350 ASPHALT CONC. TY. SM-12.5A	4,348.770 TON	_____	_____	_____	_____
0060	315	16360 ASPHALT CONC. TY. SM-12.5E	4,219.890 TON	_____	_____	_____	_____
0070	315	16371 ASPHALT CONC. TY. IM-19.0E	6,832.470 TON	_____	_____	_____	_____
0080	315	16378 THIN HOT MIX ASPHALT CONCRETE	1,564.310 TON	_____	_____	_____	_____
0090	ATTD	16394 ASPH. CONC. PATCH TY. IM-19.0D	351.710 TON	_____	_____	_____	_____
0100	317, 315	16403 STONE MATRIX ASPHALT SMA-12.5 64E-22	12,140.400 TON	_____	_____	_____	_____
0110	317, 315	16405 STONE MATRIX ASPHALT SMA-19.0 64E-22	4,669.630 TON	_____	_____	_____	_____
0120	ATTD	16515 FLEXIBLE PAVE. PLANING OVER 4" DEEP	23,613.330 SY	_____	_____	_____	_____

Schedule of Items

Proposal ID: CM422PM2119810      Oversight/State Project No.: PM42-964-F22, P401  
 Order No.: G18      Federal Project No.: PM04(498)

Contractor: \_\_\_\_\_

SECTION: 0001      REGULAR BID ITEMS

Cat Alt Set ID:      Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0130	515	16516 FLEXIBLE PAVE. TIE-IN PLANING 0" - 2"	651.200 SY	_____	_____	_____	_____
0140	515	16522 FLEXIBLE PAVEMENT PLANING 0" - 2"	95,502.630 SY	_____	_____	_____	_____
0150	515	16523 FLEXIBLE PAVEMENT PLANING ABOVE 2" - 4"	69,144.530 SY	_____	_____	_____	_____
0160	512	24265 MAINTENANCE OF TRAFFIC PLANT MIX	LUMP SUM	LUMP SUM		_____	_____
0170	704	54042 TYPE B CLASS I PAVE. LINE MARKING 24"	21.000 LF	_____	_____	_____	_____
0180	704	54076 TYPE B CLASS VI PVMT LINE MRKG 6"	112,003.800 LF	_____	_____	_____	_____
0190	704	54077 TYPE B CLASS VI PVMT LINE MRKG 8"	1,401.000 LF	_____	_____	_____	_____
0200	704	54078 TYPE B CLASS VI PVMT LINE MRKG 12"	4,380.000 LF	_____	_____	_____	_____
0210	512	54105 ERADICATE EXIST. LINEAR PVMT MARKING	22,141.000 LF	_____	_____	_____	_____
0220	ATTD	54219 INLAID PAVEMENT MARKER ASPHALT	847.000 EA	_____	_____	_____	_____
0230	704	54402 PAVE. MESSAGE MARKING "STOP AHEAD"	1.000 EA	_____	_____	_____	_____
0240	704	54402 PAVE. MESSAGE MARKING YIELD MESSAGE	1.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: CM422PM2119810    Oversight/State Project No.: PM42-964-F22, P401  
 Order No.: G18    Federal Project No.: PM04(498)

Contractor: \_\_\_\_\_

SECTION: 0001    REGULAR BID ITEMS

Cat Alt Set ID:    Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0250	512	54428 TEMP. PVMT MRKG, TY. A, 4"	88,884.000 LF	_____	_____	_____	_____
0260	512	54430 TEMP. PVMT MRKG, TY. A, 6"	1,341.000 LF	_____	_____	_____	_____
0270	512	54432 TEMP. PVMT MRKG, TY. A, 8"	4,031.000 LF	_____	_____	_____	_____
0280	512	54436 TEMP. PVMT MRKG, TY. A, 12"	21.000 LF	_____	_____	_____	_____
0290	704	54593 PVMT SYMB MRKG WRONG-WAY ARROW TY B, CL I	1.000 EA	_____	_____	_____	_____
<b>Section: 0001</b>				<b>Total:</b>	_____	_____	_____
				<b>Total Bid:</b>	_____	_____	_____