

Schedule of Items

Proposal ID: C0000110914C01

Oversight/State Project No.: 0001-088-709,C501,B617,D609-10

Order No.: F97

Federal Project No.: NHPP-5111(402); HSIP-5111(401)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	513	00100 MOBILIZATION	LUMP SUM	LUMP SUM			
0020	517	00101 CONSTRUCTION SURVEYING CONSTRUCTION	LUMP SUM	LUMP SUM			
0030	301	00110 CLEARING AND GRUBBING	LUMP SUM	LUMP SUM			
0040	ATTD	00118 EXCAVATION REGULAR EXCAVATION	23,163.000 CY				
0050	305	00140 BORROW EXCAVATION	85.000 CY				
0060	303	00211 MINOR STRUCTURE EXCAV. PIPE CULVERT	963.000 CY				
0070	305	00355 GEOTEXTILE SUBGRADE STABILIZATION	45.000 SY				
0080	ATTD	00507 BEDDING MATL. AGGR. NO. 57	1,157.000 TON				
0090	302	00522 CONCRETE CLASS A4 BOX CULVERT	536.500 CY				
0100	302 504	00525 CONCRETE CLASS A3 MISC.	17.000 CY				
0110	501	00585 UNDERDRAIN UD-2	569.000 LF				
0120	501	00588 UNDERDRAIN UD-4	3,797.000 LF				
0130	501	00595 OUTLET PIPE	169.000 LF				

Schedule of Items

Proposal ID: C0000110914C01 Oversight/State Project No.: 0001-088-709,C501,B617,D609-10
 Order No.: F97 Federal Project No.: NHPP-5111(402); HSIP-5111(401)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0140	302	00596 ENDWALL EW-12	2.000 EA	_____	_____	_____	_____
0150	302	01126 STORM SEWER PIPE 12"	14.000 LF	_____	_____	_____	_____
0160	302	01156 STORM SEWER PIPE 15"	1,672.000 LF	_____	_____	_____	_____
0170	302	01186 STORM SEWER PIPE 18"	232.000 LF	_____	_____	_____	_____
0180	302	01244 24" RADIAL PIPE	53.000 LF	_____	_____	_____	_____
0190	302	01246 STORM SEWER PIPE 24"	850.000 LF	_____	_____	_____	_____
0200	302	01364 36" RADIAL PIPE	147.000 LF	_____	_____	_____	_____
0210	302	01366 STORM SEWER PIPE 36"	516.000 LF	_____	_____	_____	_____
0220	302	01426 STORM SEWER PIPE 42"	193.000 LF	_____	_____	_____	_____
0230	302	01486 STORM SEWER PIPE 48"	102.000 LF	_____	_____	_____	_____
0240	302	06180 18" END SECTION ES-1 OR 2	1.000 EA	_____	_____	_____	_____
0250	302	06240 24" END SECTION ES-1 OR 2	1.000 EA	_____	_____	_____	_____
0260	302	06360 36" END SECTION ES-1 OR 2	2.000 EA	_____	_____	_____	_____
0270	302	06745 DROP INLET DI-2A	1.000 EA	_____	_____	_____	_____
0280	302	06749 DROP INLET DI-2B,L=8'	1.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000110914C01 Oversight/State Project No.: 0001-088-709,C501,B617,D609-10
 Order No.: F97 Federal Project No.: NHPP-5111(402); HSIP-5111(401)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0290	302	06750 DROP INLET DI-2B,L=10'	1.000 EA	_____	_____	_____	_____
0300	302	06818 DROP INLET DI-3B,L=6'	2.000 EA	_____	_____	_____	_____
0310	302	06820 DROP INLET DI-3B,L=10'	12.000 EA	_____	_____	_____	_____
0320	302	06821 DROP INLET DI-3B,L=12'	5.000 EA	_____	_____	_____	_____
0330	302	06823 DROP INLET DI-3B,L=16'	2.000 EA	_____	_____	_____	_____
0340	302	06824 DROP INLET DI-3B,L=18'	2.000 EA	_____	_____	_____	_____
0350	302	06825 DROP INLET DI-3B,L=20'	1.000 EA	_____	_____	_____	_____
0360	302	06829 DROP INLET DI-3BB,L=10'	1.000 EA	_____	_____	_____	_____
0370	302	06830 DROP INLET DI-3BB,L=12'	2.000 EA	_____	_____	_____	_____
0380	302	06836 DROP INLET DI-3C,L=8'	1.000 EA	_____	_____	_____	_____
0390	302	06838 DROP INLET DI-3C,L=12'	1.000 EA	_____	_____	_____	_____
0400	302	06844 DROP INLET DI-3CC,L=8'	1.000 EA	_____	_____	_____	_____
0410	302	07114 DROP INLET DI-4B,L=10'	1.000 EA	_____	_____	_____	_____
0420	302	07116 DROP INLET DI-4B,L=12'	2.000 EA	_____	_____	_____	_____
0430	302	07130 DROP INLET DI-4BB,L=10'	1.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000110914C01 Oversight/State Project No.: 0001-088-709,C501,B617,D609-10
 Order No.: F97 Federal Project No.: NHPP-5111(402); HSIP-5111(401)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0440	302	07210 DROP INLET DI-4C,L=12'	2.000 EA	_____	_____	_____	_____
0450	302	07220 DROP INLET DI-4CC,L=8'	1.000 EA	_____	_____	_____	_____
0460	302	07222 DROP INLET DI-4CC,L=10'	1.000 EA	_____	_____	_____	_____
0470	302	07304 DROP INLET DI-4D	2.000 EA	_____	_____	_____	_____
0480	302	07506 DROP INLET DI-5	1.000 EA	_____	_____	_____	_____
0490	302	07508 DROP INLET DI-7	1.000 EA	_____	_____	_____	_____
0500	302	09056 MANHOLE MH-1 OR 2	13.000 LF	_____	_____	_____	_____
0510	302	09057 FRAME & COVER MH-1	6.000 EA	_____	_____	_____	_____
0520	414	09148 EROSION CONTROL STONE CLASS A1 EC-1	3.900 TON	_____	_____	_____	_____
0530	414	09150 EROSION CONTROL STONE CLASS I, EC-1	155.000 TON	_____	_____	_____	_____
0540	502	09185 PAVED DITCH PG-2A	219.000 SY	_____	_____	_____	_____
0550	306	10027 MANIPULATION FOR LIME TREATMENT (SLOPES < or = 2:1)	8,412.600 SY	_____	_____	_____	_____
0560	306	10032 LIME FOR SLOPES (12 TONS / ACRE)	20.860 TON	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000110914C01 Oversight/State Project No.: 0001-088-709,C501,B617,D609-10
 Order No.: F97 Federal Project No.: NHPP-5111(402); HSIP-5111(401)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0570	308	10128 AGGR. BASE MATL. TY. I NO. 21B	10,056.000 TON	_____	_____	_____	_____
0580	315	10608 ASPHALT CONCRETE TY. SM-12.5D	3,750.000 TON	_____	_____	_____	_____
0590	315	10611 ASPHALT CONCRETE TY. IM-19.0D	828.000 TON	_____	_____	_____	_____
0600	515	10628 FLEXIBLE PAVEMENT PLANING 0" - 2"	25,791.000 SY	_____	_____	_____	_____
0610	315	10642 ASPHALT CONCRETE TY. BM-25.0A	2,935.000 TON	_____	_____	_____	_____
0620	316	11040 CONCRETE ENTRANCE PAVE. 7"	70.000 SY	_____	_____	_____	_____
0630	315	11070 SAW-CUT ASPH CONC 12" DEPTH	6,235.000 LF	_____	_____	_____	_____
0640	502	12020 STD. CURB CG-2	480.000 LF	_____	_____	_____	_____
0650	502	12022 RADIAL CURB CG-2	146.000 LF	_____	_____	_____	_____
0660	502	12030 STD. CURB CG-3	103.000 LF	_____	_____	_____	_____
0670	502	12600 STD. COMB. CURB & GUTTER CG-6	3,233.000 LF	_____	_____	_____	_____
0680	502	12610 RADIAL COMB. CURB & GUTTER CG-6	823.000 LF	_____	_____	_____	_____

Proposal ID: C0000110914C01

Oversight/State Project No.: 0001-088-709,C501,B617,D609-10

Order No.: F97

Federal Project No.: NHPP-5111(402); HSIP-5111(401)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0690	502	12720 COMB. CURB & GUTTER MODIFIED CG-6	65.000 LF	_____	_____	_____	_____
0700	502	12940 ENTRANCE GUTTER CG-9D	59.000 SY	_____	_____	_____	_____
0710	504	13108 CG-12 DETECTABLE WARNING SURFACE	27.000 SY	_____	_____	_____	_____
0720	504	13220 HYDRAULIC CEMENT CONC. SIDEWALK 4"	1,345.000 SY	_____	_____	_____	_____
0730	505	13268 REMOVE EXISTING GUARDRAIL TERMINAL	4.000 EA	_____	_____	_____	_____
0740	505	13280 GUARDRAIL GR-MGS1	351.000 LF	_____	_____	_____	_____
0750	505	13282 GUARDRAIL GR-MGS1, 9' POST	158.000 LF	_____	_____	_____	_____
0760	505	13283 RADIAL GUARDRAIL GR- MGS1	38.000 LF	_____	_____	_____	_____
0770	505	13286 GUARDRAIL TERMINAL GR- MGS2	3.000 EA	_____	_____	_____	_____
0780	505	13287 GUARDRAIL END ANCHORAGE GR-MGS3	2.000 EA	_____	_____	_____	_____
0790	505	13288 GUARDRAIL HEIGHT TRANSITION GR-MGS4	3.000 EA	_____	_____	_____	_____
0800	505	13315 GUARDRAIL TERMINAL GR-11	1.000 EA	_____	_____	_____	_____

Proposal ID: C0000110914C01 Oversight/State Project No.: 0001-088-709,C501,B617,D609-10
 Order No.: F97 Federal Project No.: NHPP-5111(402); HSIP-5111(401)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0810	505	13355 GUARDRAIL GR-10	36.000 LF	_____	_____	_____	_____
0820	505	13384 FIXED OBJECT ATTACH. GR-FOA-1 TY. II	2.000 EA	_____	_____	_____	_____
0830	505	13393 FIXED OBJECT ATTACH. GR-FOA-2 TY. II	1.000 EA	_____	_____	_____	_____
0840	505	13394 FIXED OBJECT ATTACH. GR-FOA-5	3.000 EA	_____	_____	_____	_____
0850	502	13460 MEDIAN BARRIER MB-7D	45.000 LF	_____	_____	_____	_____
0860	512	13495 TRAF. BARR. SER. CONC. SINGLE FACE PAR.MB-10A	120.000 LF	_____	_____	_____	_____
0870	512	13496 TRAF. BARR. SER. CONC. DOUBLE FACE PAR.MB-11A	100.000 LF	_____	_____	_____	_____
0880	506	13565 RETAINING WALL EXCAVATION	2,502.000 CY	_____	_____	_____	_____
0890	512	13604 IMPACT ATTEN. SER. TY. 1 TL-3, >=40 MPH	2.000 EA	_____	_____	_____	_____
0900	505	13607 IMPACT ATTEN. STD. IA-1, TL-3>=40 MPH DES.SP.	2.000 EA	_____	_____	_____	_____
0910	ATTD	14260 CRUSHER RUN AGGREGATE NO. 25 OR 26	35.000 TON	_____	_____	_____	_____
0920	ATTD	14424 CURB CONCRETE WHEEL STOPS	32.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000110914C01 Oversight/State Project No.: 0001-088-709,C501,B617,D609-10
 Order No.: F97 Federal Project No.: NHPP-5111(402); HSIP-5111(401)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0930	ATTD	14502 REINFORCING STEEL	120,709.910 LB	_____	_____	_____	_____
0940	502	21020 MEDIAN STRIP MS-1	579.000 SY	_____	_____	_____	_____
0950	502	21110 MEDIAN STRIP MS-1A	383.000 SY	_____	_____	_____	_____
0960	502	21215 MEDIAN STRIP MS-2	133.000 LF	_____	_____	_____	_____
0970	507	22501 FENCE FE-W1	198.000 LF	_____	_____	_____	_____
0980	507	22541 LINE BRACE UNIT FE-W1,FE-W2	4.000 EA	_____	_____	_____	_____
0990	507	22581 CORNER BRACE UNIT FE-W1,FE-W2	3.000 EA	_____	_____	_____	_____
1000	507	22910 GATE FE-G L=16'	1.000 EA	_____	_____	_____	_____
1010	511	24100 ALLAYING DUST	400.000 HR	_____	_____	_____	_____
1020	512	24150 TYPE 3 BARRICADE 4'	2.000 EA	_____	_____	_____	_____
1030	512	24152 TYPE 3 BARRICADE 8'	1.000 EA	_____	_____	_____	_____
1040	512	24160 TEMPORARY (CONSTRUCTION) SIGN	1,050.000 SF	_____	_____	_____	_____
1050	512	24272 TRUCK MOUNTED ATTENUATOR	2,640.000 HR	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000110914C01 Oversight/State Project No.: 0001-088-709,C501,B617,D609-10
 Order No.: F97 Federal Project No.: NHPP-5111(402); HSIP-5111(401)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1060	512	24278 GROUP 2 CHANNELIZING DEVICES	36,985.000 DAY	_____	_____	_____	_____
1070	512	24279 PORTABLE CHANGEABLE MESSAGE SIGN	6,912.000 HR	_____	_____	_____	_____
1080	512	24281 ELECTRONIC ARROW BOARD	2,320.000 HR	_____	_____	_____	_____
1090	512	24333 TEMPORARY TRAFFIC CONTROL SIGNAL .	LUMP SUM	LUMP SUM	_____	_____	_____
1100	508	24410 DEMOLITION OF PAVEMENT COMBINATION	727.000 SY	_____	_____	_____	_____
1110	508	24420 DEMOLITION OF PAVEMENT RIGID	65.000 SY	_____	_____	_____	_____
1120	508	24430 DEMOLITION OF PAVEMENT FLEXIBLE	2,559.000 SY	_____	_____	_____	_____
1130	505	24600 REMOVE EXISTING GUARDRAIL	1,603.000 LF	_____	_____	_____	_____
1140	510	24825 MODIFY EXIST. CONTROLLER CABINET	3.000 EA	_____	_____	_____	_____
1150	510	24825 MODIFY EXIST. JUNCTION BOX	7.000 EA	_____	_____	_____	_____
1160	504	25003 HANDRAIL HR-1 TYPE II	22.000 LF	_____	_____	_____	_____
1170	514	25505 FIELD OFFICE TY.I	20.000 MO	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000110914C01
Order No.: F97

Oversight/State Project No.: 0001-088-709,C501,B617,D609-10
Federal Project No.: NHPP-5111(402); HSIP-5111(401)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1180	ATTD	25565 PROGRESS SCHEDULE BASELINE	LUMP SUM	LUMP SUM			
1190	ATTD	25567 PROGRESS SCHEDULE UPDATES	20.000 EA				
1200	414	26127 DRY RIPRAP CL.I 26"	843.000 TON				
1210	602	27022 TOPSOIL CLASS B 2"	0.792 ACRE				
1220	602	27024 TOPSOIL FOR SLOPES (6" DEPTH)	1.738 ACRE				
1230	603	27100 PERMANENT SEED	474.000 LB				
1240	603	27101 TEMPORARY SEED	126.000 LB				
1250	603	27103 OVERSEEDING	380.000 LB				
1260	603	27110 HYDRAULIC EROSION CONTROL PRODUCT TYPE 1	2,057.000 SY				
1270	603	27112 HYDRAULIC EROSION CONTROL PRODUCT TYPE 3	19,348.000 SY				
1280	603	27120 SEDIMENT RETENTION ROLL 18" MIN	11.810 LF				
1290	603	27230 FERTILIZER NITROGEN - N	218.000 LB				
1300	603	27231 FERTILIZER PHOSPHOROUS - P	284.000 LB				

Schedule of Items

Proposal ID: C0000110914C01 Oversight/State Project No.: 0001-088-709,C501,B617,D609-10
 Order No.: F97 Federal Project No.: NHPP-5111(402); HSIP-5111(401)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1310	603	27232 FERTILIZER POTASSIUM - K	142.000 LB	_____	_____	_____	_____
1320	603	27250 LIME	10.120 TON	_____	_____	_____	_____
1330	606	27326 ROLLED EROSION CTRL PRODUCT EC-3 TYPE 2	258.000 SY	_____	_____	_____	_____
1340	606	27327 ROLLED EROSION CTRL PRODUCT EC-3 TYPE 3	1,177.000 SY	_____	_____	_____	_____
1350	303	27345 TEMPORARY DIVERSION DIKE	593.000 LF	_____	_____	_____	_____
1360	414	27401 EROSION CONTROL RIPRAP	139.000 TON	_____	_____	_____	_____
1370	303	27410 CHECK DAM, ROCK TY. I	6.000 EA	_____	_____	_____	_____
1380	303	27415 CHECK DAM ROCK TY. II	41.000 EA	_____	_____	_____	_____
1390	303	27430 SILTATION CONTROL EXCAVATION	1,112.000 CY	_____	_____	_____	_____
1400	303	27451 INLET PROTECTION TYPE A	7.000 EA	_____	_____	_____	_____
1410	303	27461 INLET PROTECTION TYPE B	59.000 EA	_____	_____	_____	_____
1420	303	27500 GEOTEXTILE FABRIC	162.000 SY	_____	_____	_____	_____
1430	303	27504 TEMP. SILT FENCE TYPE B	903.000 LF	_____	_____	_____	_____
1440	303	27505 TEMP. SILT FENCE TYPE A	2,383.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000110914C01

Oversight/State Project No.: 0001-088-709,C501,B617,D609-10

Order No.: F97

Federal Project No.: NHPP-5111(402); HSIP-5111(401)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1450	401	27510 COFFERDAM	8.000 EA	_____	_____	_____	_____
1460	302	27570 TEMP. SEDIMENT RISER PIPE 36"	5.500 LF	_____	_____	_____	_____
1470	303	27580 TEMP. SEDIMENT BASIN EXCAVATION	221.000 CY	_____	_____	_____	_____
1480	520	40003 1" WATER SERVICE LINE	58.000 LF	_____	_____	_____	_____
1490	520	41968 1" WATER METER BOX & YOKE	1.000 EA	_____	_____	_____	_____
1500	ATTD	42000 SEWER PIPE 8" DI SANITARY SEWER	28.000 LF	_____	_____	_____	_____
1510	ATTD	42000 SEWER PIPE 8" SANITARY DROP CONNECTION	10.000 LF	_____	_____	_____	_____
1520	520	42755 SANITARY SEWER MANHOLE	22.000 LF	_____	_____	_____	_____
1530	520	42764 MANHOLE FRAME & COVER F&C-1	1.000 EA	_____	_____	_____	_____
1540	510	42765 ADJUST EXIST FRAME & COVER	1.000 EA	_____	_____	_____	_____
1550	509	45640 FLOWABLE BACKFILL UTILITY	612.000 CY	_____	_____	_____	_____
1560	702	50037 FLEXIBLE POST DELINEATOR, GROUND MOUNT	34.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000110914C01

Oversight/State Project No.: 0001-088-709,C501,B617,D609-10

Order No.: F97

Federal Project No.: NHPP-5111(402); HSIP-5111(401)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1570	701	50108 SIGN PANEL	978.840 SF	_____	_____	_____	_____
1580	700	50300 REMOVE EXISTING 1 POST SIGN STRUCTURE	15.000 EA	_____	_____	_____	_____
1590	700	50320 REMOVE EXISTING 1 POST SIGN PANEL	4.000 EA	_____	_____	_____	_____
1600	700	50326 REMOVE EXISTING OVERHEAD SIGNAL SIGN PANEL	4.000 EA	_____	_____	_____	_____
1610	700	50340 RELOCATE EXISTING 1 POST GROUND MOUNTED SIGN PANEL	2.000 EA	_____	_____	_____	_____
1620	700	50342 RELOCATE EXISTING 2 POST GROUND MOUNTED SIGN PANEL	1.000 EA	_____	_____	_____	_____
1630	700	50430 SIGN POST STP-1, 2", 14 GAUGE	422.000 LF	_____	_____	_____	_____
1640	700	50434 SIGN POST STP-1, 2 1/2", 10 GAUGE	176.750 LF	_____	_____	_____	_____
1650	700	50436 SIGN POST STP-1, 2 1/2", 12 GAUGE	239.500 LF	_____	_____	_____	_____
1660	700	50485 CONCRETE SIGN FOUNDATION STP-1, TYPE A	59.000 EA	_____	_____	_____	_____
1670	700	50486 CONCRETE SIGN FOUNDATION STP-1, TYPE B	13.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000110914C01 Oversight/State Project No.: 0001-088-709,C501,B617,D609-10
 Order No.: F97 Federal Project No.: NHPP-5111(402); HSIP-5111(401)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1680	700	50900 TRAFFIC SIGN STP-2, 4"	58.500 LF	_____	_____	_____	_____
1690	700	50902 TRAFFIC SIGN STP - 2 FOUNDATION 2'-6" X 6'-6"	3.000 EA	_____	_____	_____	_____
1700	703	51185 TRAFFIC SIGNAL HEAD SECTION 12" HVS BACKPLATE	51.000 EA	_____	_____	_____	_____
1710	700	51210 PEDESTAL POLE PF-2 10'	2.000 EA	_____	_____	_____	_____
1720	700	51238 CONCRETE FOUNDATION SIGNAL POLE PF-8	48.000 CY	_____	_____	_____	_____
1730	700	51240 CONCRETE FOUNDATION PF- 2	2.000 EA	_____	_____	_____	_____
1740	700	51478 SIGNAL MAST ARM POLE MP- 3, TYPE C	1.000 EA	_____	_____	_____	_____
1750	700	51479 SIGNAL MAST ARM POLE MP- 3, TYPE D	1.000 EA	_____	_____	_____	_____
1760	700	51480 SIGNAL MAST ARM POLE MP- 3, TYPE E1	1.000 EA	_____	_____	_____	_____
1770	700	51487 MAST ARM 49'	2.000 EA	_____	_____	_____	_____
1780	700	51488 MAST ARM 60'	1.000 EA	_____	_____	_____	_____
1790	700	51491 MAST ARM 75' CASE 1 LOADING	1.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000110914C01 Oversight/State Project No.: 0001-088-709,C501,B617,D609-10
 Order No.: F97 Federal Project No.: NHPP-5111(402); HSIP-5111(401)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1800	703	51507 VIDEO DETECTION CAMERA	2.000 EA	_____	_____	_____	_____
1810	703	51508 VIDEO DETECTION CABLE	1,235.000 LF	_____	_____	_____	_____
1820	703	51540 LOOP DETECTOR AMPLIFIER	9.000 EA	_____	_____	_____	_____
1830	700	51598 8/3 CONDUCTOR CABLE	1,700.000 LF	_____	_____	_____	_____
1840	700	51602 14/4 CONDUCTOR CABLE	6,910.000 LF	_____	_____	_____	_____
1850	700	51607 14/7 CONDUCTOR CABLE	1,015.000 LF	_____	_____	_____	_____
1860	700	51615 14/1 ENCLOSED COND. CABLE	7,070.000 LF	_____	_____	_____	_____
1870	700	51700 14/2 CONDUCTOR CABLE SHIELDED	3,600.000 LF	_____	_____	_____	_____
1880	703	51830 HANGER ASSEMBLY SM-3, ONE WAY	16.000 EA	_____	_____	_____	_____
1890	703	51834 HANGER ASSEMBLY SMB-2, ONE WAY	2.000 EA	_____	_____	_____	_____
1900	703	51912 LOOP SAW CUT 3/8"	1,940.000 LF	_____	_____	_____	_____
1910	703	51913 LOOP SAWCUT 5/8"	490.000 LF	_____	_____	_____	_____
1920	703	51933 REMOVE EXISTING POLE	3.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000110914C01

Oversight/State Project No.: 0001-088-709,C501,B617,D609-10

Order No.: F97

Federal Project No.: NHPP-5111(402); HSIP-5111(401)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1930	703	51934 REMOVE EXISTING FOUNDATION	3.000 EA	_____	_____	_____	_____
1940	703	51935 REMOVE EXISTING SIGNAL HEAD	1.000 EA	_____	_____	_____	_____
1950	700	52001 TRAFFIC SIGNALIZATION ANTENNA CABLE	100.000 LF	_____	_____	_____	_____
1960	700	52002 TRAFFIC SIGNALIZATION ACCESSIBLE PEDESTRIAN PUSHBUTTON (APS-APA)	2.000 EA	_____	_____	_____	_____
1970	700	52002 TRAFFIC SIGNALIZATION ANTENNA RELOCATION	1.000 EA	_____	_____	_____	_____
1980	703	52404 PEDESTRIAN SIGNAL HEAD SP-9	2.000 EA	_____	_____	_____	_____
1990	704	54032 TYPE B CLASS I PVMT LINE MRKG 4"	12,900.000 LF	_____	_____	_____	_____
2000	704	54034 TYPE B CLASS I PVMT LINE MRKG 6"	5,080.000 LF	_____	_____	_____	_____
2010	704	54037 TYPE B CLASS I PVMT LINE MRKG 8"	1,115.000 LF	_____	_____	_____	_____
2020	704	54048 TYPE B CLASS II PAVE. LINE MARKING 24"	359.000 LF	_____	_____	_____	_____
2030	512	54105 ERADICATE EXIST. LINEAR PVMT MARKING	1,339.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000110914C01

Oversight/State Project No.: 0001-088-709,C501,B617,D609-10

Order No.: F97

Federal Project No.: NHPP-5111(402); HSIP-5111(401)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
2040	ATTD	54219 INLAID PAVEMENT MARKER ASPHALT	178.000 EA	_____	_____	_____	_____
2050	704	54393 PVMT MSG. MARK. "ONLY" TY B, CL II, 6'	6.000 EA	_____	_____	_____	_____
2060	512	54544 TYPE D, CLASS III TEMP. PVMT MRKG 8"	1,339.000 LF	_____	_____	_____	_____
2070	704	54575 PVMT SYMB MRKG SGL TURN ARROW TY B, CL II	46.000 EA	_____	_____	_____	_____
2080	704	54578 PVMT SYMB MRKG DBL TURN ARROW THRU/LT OR RT TY B, CL II	5.000 EA	_____	_____	_____	_____
2090	700	55080 8 CONDUCTOR CABLE	1,170.000 LF	_____	_____	_____	_____
2100	700	55179 LUMINAIRE ARM 18'	2.000 EA	_____	_____	_____	_____
2110	ATTD	55505 LUMINAIRE CONVENTIONAL 140 WATTS LED	3.000 EA	_____	_____	_____	_____
2120	700	55587 JUNCTION BOX JB-S2	14.000 EA	_____	_____	_____	_____
2130	700	56021 1" PVC CONDUIT	195.000 LF	_____	_____	_____	_____
2140	700	56050 BORED CONDUIT 2"	215.000 LF	_____	_____	_____	_____
2150	700	56051 BORED CONDUIT 3"	2,015.000 LF	_____	_____	_____	_____
2160	700	56053 2" PVC CONDUIT	1,635.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000110914C01

Oversight/State Project No.: 0001-088-709,C501,B617,D609-10

Order No.: F97

Federal Project No.: NHPP-5111(402); HSIP-5111(401)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
2170	700	56054 3" PVC CONDUIT	480.000 LF	_____	_____	_____	_____
2180	700	56200 TRENCH EXCAVATION ECI-1	1,950.000 LF	_____	_____	_____	_____
2190	705	59000 LIGHTING REMOVE EXISTING LUMINAIRE	1.000 EA	_____	_____	_____	_____
2200	705	59000 LIGHTING ROTATE EXISTING LUMINAIRE ARM	1.000 EA	_____	_____	_____	_____
2210	405	61247 PREST.CONC.BEAM,BULB-T 61" DEPTH +110'-120'	2.000 EA	_____	_____	_____	_____
2220	406	61711 CORROSION RESISTANT REINF. STEEL CL. I	27,340.000 LB	_____	_____	_____	_____
2230	410	62034 RAILING, CPSR 2 RAIL	122.000 LF	_____	_____	_____	_____
2240	410	62034 RAILING, CPSR 2 RAIL	576.000 LF	_____	_____	_____	_____
2250	420	62412 ADHESIVE BASED JOINT SEALER CLASS I, 2"	100.000 LF	_____	_____	_____	_____
2260	420	62417 ADHESIVE BASED JOINT SEALER CLASS I, 3.5"	97.000 LF	_____	_____	_____	_____
2270	401	64032 GEOCOMPOSITE WALL DRAIN	499.000 SY	_____	_____	_____	_____
2280	404	65013 CONCRETE CLASS A3	733.400 CY	_____	_____	_____	_____
2290	410	65840 RAILING, CPSR 2 RAIL	69.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000110914C01

Oversight/State Project No.: 0001-088-709,C501,B617,D609-10

Order No.: F97

Federal Project No.: NHPP-5111(402); HSIP-5111(401)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
2300	401	66120 COFFERDAM	2.000 EA	_____	_____	_____	_____
2310	512	67110 TRAFFIC BARRIER SERVICE CONCRETE	1,300.000 LF	_____	_____	_____	_____
2320	430	67910 NBIS ACCESS, UNDER BRIDGE B617	1.000 DAY	_____	_____	_____	_____
2330	404	68043 CONC. CLASS A4 MOD.LOW SHRINKAGE	82.600 CY	_____	_____	_____	_____
2340	404	68085 COVER DEPTH SURVEY	208.000 SY	_____	_____	_____	_____
2350	404	68090 BRIDGE DECK GROOVING	108.000 SY	_____	_____	_____	_____
2360	406	68091 CORROSION RESISTANT REINF. STEEL CL. I	14,100.000 LB	_____	_____	_____	_____
2370	316	68265 CONC. CLASS A-4 BRIDGE APPR. SLAB	23.500 CY	_____	_____	_____	_____
2380	316	68270 REINF. STEEL BRIDGE APPR. SLAB	3,990.000 LB	_____	_____	_____	_____
2390	413	68900 REM. PORT. OF EX. STR. (VA STR. NO. 6012)	LUMP SUM	LUMP SUM	_____	_____	_____
2400	401	69008 GEOCOMPOSITE WALL DRAIN	106.000 SY	_____	_____	_____	_____
2410	401	69010 PIPE UNDERDRAIN 6"	70.000 LF	_____	_____	_____	_____
2420	401	69011 STRUCTURE EXCAVATION	354.000 CY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000110914C01 Oversight/State Project No.: 0001-088-709,C501,B617,D609-10
 Order No.: F97 Federal Project No.: NHPP-5111(402); HSIP-5111(401)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
2430	401	69014 SELECT BACKFILL ABUTMENT ZONE	1,023.000 TON	_____	_____	_____	_____
2440	412	69030 CONCRETE CLASS A3	178.000 CY	_____	_____	_____	_____
2450	406	69091 CORROSION RESISTANT REINF. STEEL CL. I	8,850.000 LB	_____	_____	_____	_____
2460	406	69100 REINF. STEEL	8,540.000 LB	_____	_____	_____	_____
2470	403	69112 STEEL PILE 12"	1,728.000 LF	_____	_____	_____	_____
2480	403	69113 DRIVING TEST FOR 12" STEEL PILE	130.000 LF	_____	_____	_____	_____
2490	403	69222 PILE POINT FOR 12" STEEL PILE	31.000 EA	_____	_____	_____	_____
2500	403	69426 DYNAMIC PILE TEST	2.000 EA	_____	_____	_____	_____
2510	414	69639 DRY RIPRAP CL. II 38"	600.000 TON	_____	_____	_____	_____
Section: 0001				Total:	_____	_____	_____
				Total Bid:	_____	_____	_____