

Schedule of Items

Proposal ID: C0000118348B60

Oversight/State Project No.: 0029-029-504, C501, B660

Order No.: G52

Federal Project No.: NHPP-5B01(233)

Contractor: _____

SECTION: 0001 REGULAR ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	513	00100 MOBILIZATION	LUMP SUM	LUMP SUM			
0020	517	00101 CONSTRUCTION SURVEYING CONSTRUCTION	LUMP SUM	LUMP SUM			
0030	301	00111 CLEARING AND GRUBBING	0.900 ACRE				
0040	303	00120 REGULAR EXCAVATION	819.000 CY				
0050	305	00140 BORROW EXCAVATION	578.000 CY				
0060	ATTD	00180 UTILITY TEST PIT UNPAVED	10.000 EA				
0070	ATTD	00181 UTILITY TEST PIT ASPHALT CONCRETE	5.000 EA				
0080	302 504	00525 CONCRETE CLASS A3 MISC.	1.530 CY				
0090	302 406	00540 REINF. STEEL	161.000 LB				
0100	302	00574 ENDWALL GRATE & FRAME EW-11A	1.000 EA				
0110	501	00588 UNDERDRAIN UD-4	1,501.000 LF				
0120	501	00591 CROSSDRAIN CD-2	83.000 LF				
0130	302	01156 STORM SEWER PIPE 15"	682.000 LF				
0140	302	01186 STORM SEWER PIPE 18"	125.000 LF				

Schedule of Items

Proposal ID: C0000118348B60

Oversight/State Project No.: 0029-029-504, C501, B660

Order No.: G52

Federal Project No.: NHPP-5B01(233)

Contractor: _____

SECTION: 0001 REGULAR ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0150	302	06151 15" END SECTION ES-1	2.000 EA	_____	_____	_____	_____
0160	302	06181 18" END SECTION ES-1	1.000 EA	_____	_____	_____	_____
0170	302	06818 DROP INLET DI-3B,L=6'	2.000 EA	_____	_____	_____	_____
0180	302	06851 DROP INLET DI-3D	2.000 EA	_____	_____	_____	_____
0190	302	07506 DROP INLET DI-5	5.000 EA	_____	_____	_____	_____
0200	302	09055 MANHOLE MH-2	17.900 LF	_____	_____	_____	_____
0210	302	09057 FRAME & COVER MH-1	2.000 EA	_____	_____	_____	_____
0220	502	09245 PAVED DITCH PG-6B	300.000 SY	_____	_____	_____	_____
0230	308	10128 AGGR. BASE MATL. TY. I NO. 21B	1,439.000 TON	_____	_____	_____	_____
0240	315	10610 ASPHALT CONCRETE TY. IM-19.0A	47.000 TON	_____	_____	_____	_____
0250	515	10628 FLEXIBLE PAVEMENT PLANING 0" - 2"	3,767.000 SY	_____	_____	_____	_____
0260	315	10635 ASPHALT CONC.TY. SM-9.5A	30.000 TON	_____	_____	_____	_____
0270	315	10636 ASPHALT CONC.TY. SM-9.5D	636.000 TON	_____	_____	_____	_____
0280	315	10642 ASPHALT CONCRETE TY. BM-25.0A	775.000 TON	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000118348B60

Oversight/State Project No.: 0029-029-504, C501, B660

Order No.: G52

Federal Project No.: NHPP-5B01(233)

Contractor: _____

SECTION: 0001

REGULAR ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0290	315	11070 SAW-CUT ASPH CONC FULL DEPTH	2,478.000 LF	_____	_____	_____	_____
0300	502	12030 STD. CURB CG-3	162.000 LF	_____	_____	_____	_____
0310	502	12700 STD. COMB. CURB & GUTTER CG-7	361.000 LF	_____	_____	_____	_____
0320	502	12720 COMB. CURB & GUTTER CG-7	15.000 LF	_____	_____	_____	_____
0330	505	13280 GUARDRAIL GR-MGS1	341.000 LF	_____	_____	_____	_____
0340	505	13286 GUARDRAIL TERMINAL GR- MGS2	2.000 EA	_____	_____	_____	_____
0350	505	13287 GUARDRAIL END ANCHORAGE GR-MGS3	1.000 EA	_____	_____	_____	_____
0360	505	13394 FIXED OBJECT ATTACH. GR- FOA-5	3.000 EA	_____	_____	_____	_____
0370	512	13496 TRAF. BARR. SER. CONC. DOUBLE FACE PAR.MB-11A	3,297.000 LF	_____	_____	_____	_____
0380	512	13710 IMPACT ATTENUATOR SERVICE TYPE I, TL-3 LOW MAINTENANCE	8.000 EA	_____	_____	_____	_____
0390	512	24152 TYPE 3 BARRICADE 8'	3.000 EA	_____	_____	_____	_____
0400	512	24160 TEMPORARY (CONSTRUCTION) SIGN	867.000 SF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000118348B60

Oversight/State Project No.: 0029-029-504, C501, B660

Order No.: G52

Federal Project No.: NHPP-5B01(233)

Contractor: _____

SECTION: 0001

REGULAR ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0410	512	24272 TRUCK MOUNTED ATTENUATOR	2,016.000 HR	_____	_____	_____	_____
0420	512	24278 GROUP 2 CHANNELIZING DEVICES	5,222.000 DAY	_____	_____	_____	_____
0430	512	24279 PORTABLE CHANGEABLE MESSAGE SIGN	816.000 HR	_____	_____	_____	_____
0440	512	24281 ELECTRONIC ARROW BOARD	168.000 HR	_____	_____	_____	_____
0450	508	24410 DEMOLITION OF PAVEMENT COMBINATION	535.000 SY	_____	_____	_____	_____
0460	510	24825 MODIFY EXIST. DROP INLET	1.000 EA	_____	_____	_____	_____
0470	504	25002 HANDRAIL HR-1 TYPE I	300.000 LF	_____	_____	_____	_____
0480	414	26118 DRY RIPRAP CL.I 18"	2.110 SY	_____	_____	_____	_____
0490	414	26238 DRY RIPRAP CL.II 38"	5.320 SY	_____	_____	_____	_____
0500	602	27013 TOPSOIL CLASS A	191.000 CY	_____	_____	_____	_____
0510	603	27101 TEMPORARY SEED	36.000 LB	_____	_____	_____	_____
0520	603	27102 REGULAR SEED	134.000 LB	_____	_____	_____	_____
0530	603	27103 OVERSEEDING	107.000 LB	_____	_____	_____	_____

Proposal ID: C0000118348B60

Oversight/State Project No.: 0029-029-504, C501, B660

Order No.: G52

Federal Project No.: NHPP-5B01(233)

Contractor: _____

SECTION: 0001 REGULAR ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0540	603	27110 HYDRAULIC EROSION CONTROL PRODUCT TYPE 1	4,296.000 SY	_____	_____	_____	_____
0550	603	27230 FERTILIZER NITROGEN - N	68.000 LB	_____	_____	_____	_____
0560	603	27231 FERTILIZER PHOSPHOROUS - P	93.000 LB	_____	_____	_____	_____
0570	603	27232 FERTILIZER POTASSIUM - K	47.000 LB	_____	_____	_____	_____
0580	603	27250 LIME	3.200 TON	_____	_____	_____	_____
0590	606	27318 ROLLED EROSION CTRL PRODUCT EC-2 TYPE 1	106.000 SY	_____	_____	_____	_____
0600	303	27410 CHECK DAM, ROCK TY. I	2.000 EA	_____	_____	_____	_____
0610	303	27422 DEWATERING BASIN EC-8	1.000 EA	_____	_____	_____	_____
0620	303	27451 INLET PROTECTION TYPE A	6.000 EA	_____	_____	_____	_____
0630	303	27461 INLET PROTECTION TYPE B	5.000 EA	_____	_____	_____	_____
0640	303	27500 GEOTEXTILE FABRIC	7.430 SY	_____	_____	_____	_____
0650	303	27505 TEMP. SILT FENCE TYPE A	6,640.000 LF	_____	_____	_____	_____
0660	702	50030 BARRIER DELINEATOR	8.000 EA	_____	_____	_____	_____
0670	700	50300 REMOVE EXISTING 1 POST SIGN STRUCTURE	3.000 EA	_____	_____	_____	_____

Proposal ID: C0000118348B60

Oversight/State Project No.: 0029-029-504, C501, B660

Order No.: G52

Federal Project No.: NHPP-5B01(233)

Contractor: _____

SECTION: 0001 REGULAR ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0680	700	50340 RELOCATE EXISTING 1 POST GROUND MOUNTED SIGN PANEL	3.000 EA	_____	_____	_____	_____
0690	700	50430 SIGN POST STP-1, 2", 14 GAUGE	40.000 LF	_____	_____	_____	_____
0700	700	50485 CONCRETE SIGN FOUNDATION STP-1, TYPE A	3.000 EA	_____	_____	_____	_____
0710	704	54032 TYPE B CLASS I PVMT LINE MRKG 4"	2,110.000 LF	_____	_____	_____	_____
0720	704	54075 TYPE B CLASS VI PVMT LINE MRKG 4"	240.000 LF	_____	_____	_____	_____
0730	512	54105 ERADICATE EXIST. LINEAR PVMT MARKING	2,520.000 LF	_____	_____	_____	_____
0740	512	54106 ERADICATE EXIST. NONLINEAR PVMT MRKG	105.000 SF	_____	_____	_____	_____
0750	704	54402 PAVE. MESSAGE MARKING ELONGATED ARROW SINGLE	2.000 EA	_____	_____	_____	_____
0760	512	54542 TYPE D, CLASS III TEMP. PVMT MRKG 4"	640.000 LF	_____	_____	_____	_____
0770	512	54544 TYPE D, CLASS III TEMP. PVMT MRKG 8"	14,928.000 LF	_____	_____	_____	_____
0780	ATTD	60125 BRIDGE TEMPORARY SUPPORT	LUMP SUM	LUMP SUM	_____	_____	_____

Proposal ID: C0000118348B60

Oversight/State Project No.: 0029-029-504, C501, B660

Order No.: G52

Federal Project No.: NHPP-5B01(233)

Contractor: _____

SECTION: 0001 REGULAR ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0790	407	61812 STR.STEEL PLATE GIRDER ASTM A709 GRADE 50W	LUMP SUM	LUMP SUM			
0800	410	62034 RAILING, CPSR 2 RAIL	216.000 LF				
0810	512	62115 TRAF. BARR. SER. CONC. SINGLE FACE PARAPET MB-10A	480.000 LF				
0820	ATTD	62535 BRIDGE SUPERSTRUCTURE REINFORCING STEEL THREAD COUPLER BAR SIZE #4 (PARAPET)	300.000 EA				
0830	404	68044 CONC. CLASS A4 MOD.LIGHTWEIGHT LOW SHRINKAGE	83.000 CY				
0840	404	68085 COVER DEPTH SURVEY	310.000 SY				
0850	404	68090 BRIDGE DECK GROOVING	310.000 SY				
0860	406	68092 CORROSION RESISTANT REINF. STEEL CL. II	23,300.000 LB				
0870	412	68172 CRACK REPAIR TYPE B	45.000 LF				
0880	412	68218 REINFORCING STEEL SPLICER #5 BAR	620.000 EA				
0890	413	68900 REM. PORT. OF EX. STR. 1048	LUMP SUM	LUMP SUM			
0900	412	69815 RECONSTRUCT BRIDGE SEAT TYPE A	18.000 EA				

Schedule of Items

Proposal ID: C0000118348B60

Oversight/State Project No.: 0029-029-504, C501, B660

Order No.: G52

Federal Project No.: NHPP-5B01(233)

Contractor: _____

Section: 0001

Total: _____

Total Bid: _____