

Schedule of Items

Proposal ID: C0000111048C01 Oversight/State Project No.: U000-132-350, C501
 Order No.: G14 Federal Project No.: STP-5132 (172)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	513	00100 MOBILIZATION	LUMP SUM	LUMP SUM			
0020	517	00101 CONSTRUCTION SURVEYING CONSTRUCTION	LUMP SUM	LUMP SUM			
0030	301	00110 CLEARING AND GRUBBING	LUMP SUM	LUMP SUM			
0040	303	00120 REGULAR EXCAVATION	109,022.000 CY				
0050	305	00140 BORROW EXCAVATION	8,457.000 CY				
0060	303	00151 EMBANKMENT FOR STORMWATER MANAGEMENT PONDS	3,664.000 CY				
0070	ATTD	00154 GEOTEXTILE HIGH STRENGTH REINFORCEMENT FABRIC	26,194.000 SY				
0080	303	00211 MINOR STRUCTURE EXCAV. PIPE CULVERT	415.000 CY				
0090	ATT	00306 SELECT MATERIAL OGB	9,263.000 TON				
0100	305	00355 GEOTEXTILE SUBGRADE STABILIZATION	32,454.000 SY				
0110	ATTD	00507 BEDDING MATL. AGGR. NO. 57	616.300 TON				
0120	302 504	00525 CONCRETE CLASS A3 MISC.	60.100 CY				

Schedule of Items

Proposal ID: C0000111048C01

Oversight/State Project No.: U000-132-350, C501

Order No.: G14

Federal Project No.: STP-5132 (172)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0130	302 406	00540 REINF. STEEL	1,732.000 LB	_____	_____	_____	_____
0140	501	00585 UNDERDRAIN UD-2	430.000 LF	_____	_____	_____	_____
0150	501	00587 UNDERDRAIN UD-3	3,989.000 LF	_____	_____	_____	_____
0160	501	00588 UNDERDRAIN UD-4	9,748.000 LF	_____	_____	_____	_____
0170	501	00591 CROSSDRAIN CD-2	84.000 LF	_____	_____	_____	_____
0180	501	00595 OUTLET PIPE	295.000 LF	_____	_____	_____	_____
0190	302	01154 15" RADIAL PIPE	1,015.000 LF	_____	_____	_____	_____
0200	302	01156 STORM SEWER PIPE 15"	3,265.000 LF	_____	_____	_____	_____
0210	302	01182 18" CONC. PIPE	341.000 LF	_____	_____	_____	_____
0220	302	01186 STORM SEWER PIPE 18"	478.000 LF	_____	_____	_____	_____
0230	302	01240 24" PIPE	74.000 LF	_____	_____	_____	_____
0240	302	01242 24" CONC. PIPE	64.000 LF	_____	_____	_____	_____
0250	302	01246 STORM SEWER PIPE 24"	553.000 LF	_____	_____	_____	_____
0260	302	01602 60" CONC. PIPE	209.000 LF	_____	_____	_____	_____
0270	302	01606 STORM SEWER PIPE 60"	206.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000111048C01

Oversight/State Project No.: U000-132-350, C501

Order No.: G14

Federal Project No.: STP-5132 (172)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0280	302	06181 18" END SECTION ES-1	1.000 EA	_____	_____	_____	_____
0290	302	06240 24" END SECTION ES-1 OR 2	6.000 EA	_____	_____	_____	_____
0300	302	06241 24" END SECTION ES-1	1.000 EA	_____	_____	_____	_____
0310	302	06740 DROP INLET DI-1	2.000 EA	_____	_____	_____	_____
0320	302	06816 DROP INLET DI-3AA	1.000 EA	_____	_____	_____	_____
0330	302	06818 DROP INLET DI-3B,L=6'	16.000 EA	_____	_____	_____	_____
0340	302	06819 DROP INLET DI-3B,L=8'	12.000 EA	_____	_____	_____	_____
0350	302	06820 DROP INLET DI-3B,L=10'	8.000 EA	_____	_____	_____	_____
0360	302	06821 DROP INLET DI-3B,L=12'	5.000 EA	_____	_____	_____	_____
0370	302	06822 DROP INLET DI-3B,L=14'	1.000 EA	_____	_____	_____	_____
0380	302	06827 DROP INLET DI-3BB,L=6'	2.000 EA	_____	_____	_____	_____
0390	302	06828 DROP INLET DI-3BB,L=8'	2.000 EA	_____	_____	_____	_____
0400	302	06829 DROP INLET DI-3BB,L=10'	2.000 EA	_____	_____	_____	_____
0410	302	06831 DROP INLET DI-3BB,L=14'	1.000 EA	_____	_____	_____	_____
0420	302	06835 DROP INLET DI-3C,L=6'	4.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000111048C01 Oversight/State Project No.: U000-132-350, C501
 Order No.: G14 Federal Project No.: STP-5132 (172)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0430	302	06838 DROP INLET DI-3C,L=12'	1.000 EA	_____	_____	_____	_____
0440	302	06841 DROP INLET DI-3C,L=18'	1.000 EA	_____	_____	_____	_____
0450	302	07508 DROP INLET DI-7	1.000 EA	_____	_____	_____	_____
0460	302	07510 DROP INLET DI-7A	1.000 EA	_____	_____	_____	_____
0470	302	09056 MANHOLE MH-1 OR 2	3.300 LF	_____	_____	_____	_____
0480	302	09057 FRAME & COVER MH-1	2.000 EA	_____	_____	_____	_____
0490	414	09150 EROSION CONTROL STONE CLASS I, EC-1	134.000 TON	_____	_____	_____	_____
0500	414	09152 EROSION CONTROL STONE CLASS II, EC-1	162.100 TON	_____	_____	_____	_____
0510	610	09155 GABIONS	41.100 CY	_____	_____	_____	_____
0520	303	09250 SLOPE DRAIN	6.000 EA	_____	_____	_____	_____
0530	309	10245 AGGR. BASE MATL. TY. I NO. 21B	8,416.000 TON	_____	_____	_____	_____
0540	515	10628 FLEXIBLE PAVEMENT PLANING 0" - 2"	40.000 SY	_____	_____	_____	_____
0550	315	10635 ASPHALT CONC.TY. SM-9.5A	2,704.000 TON	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000111048C01 Oversight/State Project No.: U000-132-350, C501
 Order No.: G14 Federal Project No.: STP-5132 (172)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0560	315	10642 ASPHALT CONCRETE TY. BM-25.0A	6,391.000 TON	_____	_____	_____	_____
0570	ATTD, 316	10985 HYDRAULIC CEM. CONC. CONT. REINF. PAVE., 8"	726.000 SY	_____	_____	_____	_____
0580	ATTD	11070 SAW-CUT ASPH CONC FULL DEPTH	72.000 LF	_____	_____	_____	_____
0590	502	12020 STD. CURB CG-2	2,328.000 LF	_____	_____	_____	_____
0600	502	12022 RADIAL CURB CG-2	262.000 LF	_____	_____	_____	_____
0610	ATTD	12025 CURB MODIFIED CG-3	327.000 LF	_____	_____	_____	_____
0620	502	12030 STD. CURB CG-3	316.000 LF	_____	_____	_____	_____
0630	502	12600 STD. COMB. CURB & GUTTER CG-6	7,787.000 LF	_____	_____	_____	_____
0640	502	12610 RADIAL COMB. CURB & GUTTER CG-6	1,803.000 LF	_____	_____	_____	_____
0650	502	12940 ENTRANCE GUTTER CG-9D	39.000 SY	_____	_____	_____	_____
0660	504	13108 CG-12 DETECTABLE WARNING SURFACE	73.000 SY	_____	_____	_____	_____
0670	504	13220 HYDRAULIC CEMENT CONC. SIDEWALK 4"	1,876.000 SY	_____	_____	_____	_____
0680	504	13232 GEOTEXTILE DRAINAGE FABRIC	1,720.000 SY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000111048C01

Oversight/State Project No.: U000-132-350, C501

Order No.: G14

Federal Project No.: STP-5132 (172)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0690	505	13280 GUARDRAIL GR-MGS1	1,078.000 LF	_____	_____	_____	_____
0700	505	13286 GUARDRAIL TERMINAL GR- MGS2	2.000 EA	_____	_____	_____	_____
0710	505	13287 GUARDRAIL END ANCHORAGE GR-MGS3	2.000 EA	_____	_____	_____	_____
0720	ATTD	14260 CRUSHER RUN AGGREGATE NO. 25 OR 26	792.400 TON	_____	_____	_____	_____
0730	ATTD	14280 COARSE AGGREGATE NO.8	139.000 TON	_____	_____	_____	_____
0740	502	21110 MEDIAN STRIP MS-1A	250.000 SY	_____	_____	_____	_____
0750	502	21215 MEDIAN STRIP MS-2	169.000 LF	_____	_____	_____	_____
0760	507	22643 FENCE FE-CL	1,403.000 LF	_____	_____	_____	_____
0770	507	23570 HIGH VISIBILITY FENCE, 4'	538.000 LF	_____	_____	_____	_____
0780	511	24100 ALLAYING DUST	100.000 HR	_____	_____	_____	_____
0790	512	24150 TYPE 3 BARRICADE 4'	4.000 EA	_____	_____	_____	_____
0800	512	24152 TYPE 3 BARRICADE 8'	14.000 EA	_____	_____	_____	_____
0810	512	24160 TEMPORARY (CONSTRUCTION) SIGN	144.000 SF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000111048C01 Oversight/State Project No.: U000-132-350, C501
 Order No.: G14 Federal Project No.: STP-5132 (172)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0820	512	24278 GROUP 2 CHANNELIZING DEVICES	400.000 DAY	_____	_____	_____	_____
0830	512	24288 WARNING LIGHT TY. B	2,200.000 DAY	_____	_____	_____	_____
0840	508	24400 OBSCURING ROADWAY	2.800 UNIT	_____	_____	_____	_____
0850	508	24430 DEMOLITION OF PAVEMENT FLEXIBLE	1,935.000 SY	_____	_____	_____	_____
0860	302	24832 ADJUST EXIST. MANHOLE STORM SEWER MANHOLES	2.000 EA	_____	_____	_____	_____
0870	514	25506 FIELD OFFICE TY.II	9.000 MO	_____	_____	_____	_____
0880	ATTD	25565 PROGRESS SCHEDULE BASELINE	LUMP SUM	LUMP SUM	_____	_____	_____
0890	ATTD	25567 PROGRESS SCHEDULE UPDATES	23.000 EA	_____	_____	_____	_____
0900	414	26127 DRY RIPRAP CL.I 26"	159.100 TON	_____	_____	_____	_____
0910	602	27024 TOPSOIL CLASS B 3"	5.110 ACRE	_____	_____	_____	_____
0920	603	27101 TEMPORARY SEED	511.000 LB	_____	_____	_____	_____
0930	603	27102 REGULAR SEED	1,405.000 LB	_____	_____	_____	_____
0940	603	27103 OVERSEEDING	1,124.000 LB	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000111048C01

Oversight/State Project No.: U000-132-350, C501

Order No.: G14

Federal Project No.: STP-5132 (172)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0950	603	27112 HYDRAULIC EROSION CONTROL PRODUCT TYPE 3	55,638.000 SY	_____	_____	_____	_____
0960	603	27120 SEDIMENT RETENTION ROLL 18" MIN	762.000 LF	_____	_____	_____	_____
0970	603	27230 FERTILIZER NITROGEN - N	511.000 LB	_____	_____	_____	_____
0980	603	27231 FERTILIZER PHOSPHOROUS - P	358.000 LB	_____	_____	_____	_____
0990	603	27232 FERTILIZER POTASSIUM - K	358.000 LB	_____	_____	_____	_____
1000	603	27250 LIME	28.100 TON	_____	_____	_____	_____
1010	604	27300 SOD	514.000 SY	_____	_____	_____	_____
1020	606	27318 ROLLED EROSION CTRL PRODUCT EC-2 TYPE 1	17,265.000 SY	_____	_____	_____	_____
1030	606	27320 ROLLED EROSION CTRL PRODUCT EC-2 TYPE 3	79.000 SY	_____	_____	_____	_____
1040	606	27325 ROLLED EROSION CTRL PRODUCT EC-3 TYPE 1	769.000 SY	_____	_____	_____	_____
1050	302	27336 TEMP. DIVERSION CHANNEL LINING CL. A	422.000 SY	_____	_____	_____	_____
1060	302	27340 TEMP. DIVERSION CHANNEL EXCAVATION	105.000 CY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000111048C01 Oversight/State Project No.: U000-132-350, C501
 Order No.: G14 Federal Project No.: STP-5132 (172)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1070	303	27345 TEMPORARY DIVERSION DIKE	2,156.000 LF	_____	_____	_____	_____
1080	303	27415 CHECK DAM ROCK TY. II	46.000 EA	_____	_____	_____	_____
1090	303	27422 DEWATERING BASIN EC-8	2.000 EA	_____	_____	_____	_____
1100	303	27430 SILTATION CONTROL EXCAVATION	2,829.000 CY	_____	_____	_____	_____
1110	303	27451 INLET PROTECTION TYPE A	4.000 EA	_____	_____	_____	_____
1120	303	27461 INLET PROTECTION TYPE B	62.000 EA	_____	_____	_____	_____
1130	303	27504 TEMP. SILT FENCE TYPE B	3,686.000 LF	_____	_____	_____	_____
1140	303	27505 TEMP. SILT FENCE TYPE A	4,212.000 LF	_____	_____	_____	_____
1150	245	27543 STORM WATER MANAGEMENT LOW PERMEABILITY LINER	625.000 SY	_____	_____	_____	_____
1160	305	27544 STORM WATER MGT. BIORETENTION SOIL MIXTURE	417.000 CY	_____	_____	_____	_____
1170	303	27545 STORM WATER MANAGEMENT BASIN EXCAVATION	10,911.000 CY	_____	_____	_____	_____
1180	302	27550 STORM WATER MANAGEMENT DRAINAGE STR. SWM-1	20.200 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000111048C01 Oversight/State Project No.: U000-132-350, C501
 Order No.: G14 Federal Project No.: STP-5132 (172)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1190	305	27553 PERMANENT SWM FACILITY AS-BUILT DOCUMENTATION .	LUMP SUM	LUMP SUM			
1200	520	40061 6" DI WATER MAIN	4.000 LF				
1210	520	40101 10" DI WATER MAIN	132.000 LF				
1220	520	41006 6" GATE VALVE & BOX	1.000 EA				
1230	520	41010 10" GATE VALVE & BOX	2.000 EA				
1240	510	41104 ADJUST EXIST. VALVE BOX	1.000 EA				
1250	520	41820 FIRE HYDRANT	1.000 EA				
1260	509	45640 FLOWABLE BACKFILL UTILITY	12.400 CY				
1270	701	50108 SIGN PANEL	434.000 SF				
1280	700	50300 REMOVE EXISTING 1 POST SIGN STRUCTURE	2.000 EA				
1290	700	50430 SIGN POST STP-1, 2", 14 GAUGE	614.000 LF				
1300	700	50436 SIGN POST STP-1, 2 1/2", 12 GAUGE	26.000 LF				
1310	700	50485 CONCRETE SIGN FOUNDATION STP-1, TYPE A	19.000 EA				

Schedule of Items

Proposal ID: C0000111048C01 Oversight/State Project No.: U000-132-350, C501
 Order No.: G14 Federal Project No.: STP-5132 (172)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1320	700	50488 CONCRETE SIGN FOUNDATION STP-1, TYPE D	39.000 EA	_____	_____	_____	_____
1330	700	50489 CONCRETE SIGN FOUNDATION STP-1, TYPE E	2.000 EA	_____	_____	_____	_____
1340	704	54032 TYPE B CLASS I PVMT LINE MRKG 4"	14,064.000 LF	_____	_____	_____	_____
1350	704	54034 TYPE B CLASS I PVMT LINE MRKG 6"	822.000 LF	_____	_____	_____	_____
1360	704	54040 TYPE B CLASS I PVMT LINE MRKG 12"	40.000 LF	_____	_____	_____	_____
1370	704	54048 TYPE B CLASS II PAVE. LINE MARKING 24"	1,098.000 LF	_____	_____	_____	_____
1380	704	54257 PVMT MESSAGE, 6', CHARACTER, TY. B, CL. II	7.000 EA	_____	_____	_____	_____
1390	704	54575 PVMT SYMB MRKG SGL TURN ARROW TY B, CL II	15.000 EA	_____	_____	_____	_____
1400	704	54594 PVMT SYMB MRKG WRONG-WAY ARROW TY B, CL II	1.000 EA	_____	_____	_____	_____
1410	704	54626 PVMT SYMB MRKG YIELD (2' X 3') TY B, CL II	20.000 EA	_____	_____	_____	_____
1420	704	54634 PVMT MRKG (INT'L ACCESSIBILITY SYMB) TY B CL II	9.000 EA	_____	_____	_____	_____

Section: 0001

Total: _____

Total Bid: _____.