

Schedule of Items

Proposal ID: C0000116157C01 Oversight/State Project No.: 0081-086-830, C501
 Order No.: H06 Federal Project No.: NHPP-081-1(403)

Contractor: _____

SECTION: 0001 REGULAR ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	513	00100 MOBILIZATION	LUMP SUM	LUMP SUM			
0020	517	00101 CONSTRUCTION SURVEYING CONSTRUCTION	LUMP SUM	LUMP SUM			
0030	301	00110 CLEARING AND GRUBBING	LUMP SUM	LUMP SUM			
0040	303	00120 REGULAR EXCAVATION	27,626.000 CY				
0050	302 504	00525 CONCRETE CLASS A3 MISC.	45.800 CY				
0060	509	00529 FLOWABLE BACKFILL	11.000 CY				
0070	501	00588 UNDERDRAIN UD-4	3,500.000 LF				
0080	501	00595 OUTLET PIPE	309.000 LF				
0090	302	00596 ENDWALL EW-12	10.000 EA				
0100	302	01152 15" CONC. PIPE	5.000 LF				
0110	302	01182 18" CONC. PIPE	7.000 LF				
0120	302	01242 24" CONC. PIPE	953.000 LF				
0130	302	01302 30" CONC. PIPE	1,127.000 LF				
0140	302	01362 36" CONC. PIPE	40.000 LF				

Schedule of Items

Proposal ID: C0000116157C01 Oversight/State Project No.: 0081-086-830, C501
 Order No.: H06 Federal Project No.: NHPP-081-1(403)

Contractor: _____

SECTION: 0001 REGULAR ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0150	ATTD	02090 PIPE CLEANING	644.000 LF	_____	_____	_____	_____
0160	245	02110 DRAINAGE LOW PERMEABILITY LINER, GEOTEXTILE	1,655.000 SY	_____	_____	_____	_____
0170	302	06241 24" END SECTION ES-1	1.000 EA	_____	_____	_____	_____
0180	302	06301 30" END SECTION ES-1	2.000 EA	_____	_____	_____	_____
0190	302	06750 DROP INLET DI-2B,L=10'	6.000 EA	_____	_____	_____	_____
0200	302	08932 DROP INLET DI-12B,L=10'	1.000 EA	_____	_____	_____	_____
0210	302	08934 DROP INLET DI-12B,L=12'	1.000 EA	_____	_____	_____	_____
0220	302	09056 MANHOLE MH-1 OR 2	65.700 LF	_____	_____	_____	_____
0230	302	09057 FRAME & COVER MH-1	10.000 EA	_____	_____	_____	_____
0240	414	09150 EROSION CONTROL STONE CLASS I, EC-1	215.000 TON	_____	_____	_____	_____
0250	502	09185 PAVED DITCH PG-2A	96.000 SY	_____	_____	_____	_____
0260	502	09215 PAVED DITCH PG-5	100.000 SY	_____	_____	_____	_____
0270	303	09250 SLOPE DRAIN	18.000 EA	_____	_____	_____	_____
0280	308	10065 AGGR. MATL. NO. 1	29,795.000 TON	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000116157C01 Oversight/State Project No.: 0081-086-830, C501
 Order No.: H06 Federal Project No.: NHPP-081-1(403)

Contractor: _____

SECTION: 0001 REGULAR ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0290	308	10100 AGGR. MATL. NO. 21B	11,203.000 TON	_____	_____	_____	_____
0300	315	10609 ASPHALT CONCRETE TY. SM-12.5E	4,160.000 TON	_____	_____	_____	_____
0310	315	10612 ASPHALT CONCRETE TY. IM-19.0E	1,685.000 TON	_____	_____	_____	_____
0320	515	10628 FLEXIBLE PAVEMENT PLANING 0" - 2"	22,412.000 SY	_____	_____	_____	_____
0330	515	10629 FLEXIBLE PAVEMENT PLANING ABOVE 2" - 4"	233.000 SY	_____	_____	_____	_____
0340	315	10642 ASPHALT CONCRETE TY. BM-25.0A	8,284.000 TON	_____	_____	_____	_____
0350	310	11070 SAW-CUT ASPH CONC SAW-CUT ASPH CONC (13" DEPTH)	6,557.000 LF	_____	_____	_____	_____
0360	502	12322 ASPHALT CONC. CURB TY. MC-3B	2,662.000 LF	_____	_____	_____	_____
0370	315	12505 ASPHALT CONCRETE, CURB BACKUP MATERIAL	196.000 TON	_____	_____	_____	_____
0380	505	13280 GUARDRAIL GR-MGS1	4,112.500 LF	_____	_____	_____	_____
0390	505	13282 GUARDRAIL GR-MGS1, 9' POST	1,175.000 LF	_____	_____	_____	_____
0400	505	13286 GUARDRAIL TERMINAL GR-MGS2	3.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000116157C01 Oversight/State Project No.: 0081-086-830, C501
 Order No.: H06 Federal Project No.: NHPP-081-1(403)

Contractor: _____

SECTION: 0001 REGULAR ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0410	505	13287 GUARDRAIL END ANCHORAGE GR-MGS3	2.000 EA	_____	_____	_____	_____
0420	505	13315 GUARDRAIL TERMINAL GR-11	1.000 EA	_____	_____	_____	_____
0430	505	13345 ALTERNATE BREAKAWAY CABLE TERMINAL GR-9	1.000 EA	_____	_____	_____	_____
0440	505	13349 GUARDRAIL TERMINAL SITE PREPARATION	2.000 EA	_____	_____	_____	_____
0450	505	13421 MEDIAN BARRIER MB-3	2,635.000 LF	_____	_____	_____	_____
0460	505	13480 CABLE BARRICADE CR-1	1.000 EA	_____	_____	_____	_____
0470	512	13496 TRAF. BARR. SER. CONC. DOUBLE FACE PAR.MB-11A	5,960.000 LF	_____	_____	_____	_____
0480	512	13604 IMPACT ATTEN. SER. TY. 1 TL-3, >=40 MPH	1.000 EA	_____	_____	_____	_____
0490	310	16249 NONTRACKING TACK COAT	241.000 GAL	_____	_____	_____	_____
0500	315	16300 RUMBLE STRIP, ASPHALT	12,975.000 LF	_____	_____	_____	_____
0510	511	24100 ALLAYING DUST	300.000 HR	_____	_____	_____	_____
0520	512	24160 TEMPORARY (CONSTRUCTION) SIGN	814.000 SF	_____	_____	_____	_____
0530	512	24272 TRUCK MOUNTED ATTENUATOR	407.000 HR	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000116157C01 Oversight/State Project No.: 0081-086-830, C501
 Order No.: H06 Federal Project No.: NHPP-081-1(403)

Contractor: _____

SECTION: 0001 REGULAR ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0540	512	24278 GROUP 2 CHANNELIZING DEVICES	9,850.000 DAY	_____	_____	_____	_____
0550	512	24279 PORTABLE CHANGEABLE MESSAGE SIGN	1,000.000 HR	_____	_____	_____	_____
0560	512	24281 ELECTRONIC ARROW BOARD	407.000 HR	_____	_____	_____	_____
0570	512	24288 WARNING LIGHT TY. B	740.000 DAY	_____	_____	_____	_____
0580	508	24430 DEMOLITION OF PAVEMENT FLEXIBLE	6,760.000 SY	_____	_____	_____	_____
0590	505	24600 REMOVE EXISTING GUARDRAIL	3,800.000 LF	_____	_____	_____	_____
0600	514	25505 FIELD OFFICE TY.I	18.000 MO	_____	_____	_____	_____
0610	ATTD	25565 PROGRESS SCHEDULE BASELINE	LUMP SUM	LUMP SUM	_____	_____	_____
0620	ATTD	25567 PROGRESS SCHEDULE UPDATES	17.000 EA	_____	_____	_____	_____
0630	414	26127 DRY RIPRAP CL.I 26"	463.000 TON	_____	_____	_____	_____
0640	602	27023 TOPSOIL CLASS B	2,575.000 CY	_____	_____	_____	_____
0650	603	27101 TEMPORARY SEED	40.000 LB	_____	_____	_____	_____
0660	603	27102 REGULAR SEED	956.000 LB	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000116157C01 Oversight/State Project No.: 0081-086-830, C501
 Order No.: H06 Federal Project No.: NHPP-081-1(403)

Contractor: _____

SECTION: 0001 REGULAR ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0670	603	27103 OVERSEEDING	745.000 LB	_____	_____	_____	_____
0680	603	27104 LEGUME SEED	33.000 LB	_____	_____	_____	_____
0690	603	27105 LEGUME OVERSEEDING	27.000 LB	_____	_____	_____	_____
0700	603	27110 HYDRAULIC EROSION CONTROL PRODUCT TYPE 1	15,549.000 SY	_____	_____	_____	_____
0710	603	27112 HYDRAULIC EROSION CONTROL PRODUCT TYPE 3	2,571.000 SY	_____	_____	_____	_____
0720	603	27113 HYDRAULIC EROSION CONTROL PRODUCT TYPE 4	9,801.000 SY	_____	_____	_____	_____
0730	603	27230 FERTILIZER NITROGEN - N	351.000 LB	_____	_____	_____	_____
0740	603	27231 FERTILIZER PHOSPHOROUS - P	225.000 LB	_____	_____	_____	_____
0750	603	27232 FERTILIZER POTASSIUM - K	225.000 LB	_____	_____	_____	_____
0760	603	27250 LIME	16.700 TON	_____	_____	_____	_____
0770	606	27318 ROLLED EROSION CTRL PRODUCT EC-2 TYPE 1	2,558.000 SY	_____	_____	_____	_____
0780	303	27345 TEMPORARY DIVERSION DIKE	3,890.000 LF	_____	_____	_____	_____
0790	303	27410 CHECK DAM, ROCK TY. I	6.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000116157C01 Oversight/State Project No.: 0081-086-830, C501
 Order No.: H06 Federal Project No.: NHPP-081-1(403)

Contractor: _____

SECTION: 0001 REGULAR ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0800	303	27415 CHECK DAM ROCK TY. II	115.000 EA	_____	_____	_____	_____
0810	303	27418 CHECK DAM SEDIMENT RETENTION ROLL 20"	62.000 EA	_____	_____	_____	_____
0820	303	27430 SILTATION CONTROL EXCAVATION	2,832.000 CY	_____	_____	_____	_____
0830	303	27451 INLET PROTECTION TYPE A	10.000 EA	_____	_____	_____	_____
0840	303	27461 INLET PROTECTION TYPE B	6.000 EA	_____	_____	_____	_____
0850	303	27504 TEMP. SILT FENCE TYPE B	3,290.000 LF	_____	_____	_____	_____
0860	303	27505 TEMP. SILT FENCE TYPE A	10,680.000 LF	_____	_____	_____	_____
0870	303	27545 STORM WATER MANAGEMENT BASIN EXCAVATION	5,057.000 CY	_____	_____	_____	_____
0880	302	27550 STORM WATER MANAGEMENT DRAINAGE STR. SWM-1	8.250 LF	_____	_____	_____	_____
0890	303	27553 PERMANENT SWM FACILITY AS-BUILT DOCUMENTATION PERMANENT SWM FACILITY AS-BUILT DOCUMENTATION	LUMP SUM	LUMP SUM	_____	_____	_____
0900	302	27574 TEMP. SEDIMENT RISER PIPE 48"	10.500 LF	_____	_____	_____	_____
0910	303	27580 TEMP. SEDIMENT BASIN EXCAVATION	3,315.000 CY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000116157C01 Oversight/State Project No.: 0081-086-830, C501
 Order No.: H06 Federal Project No.: NHPP-081-1(403)

Contractor: _____

SECTION: 0001 REGULAR ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0920	701	50108 SIGN PANEL	244.000 SF	_____	_____	_____	_____
0930	700	50300 REMOVE EXISTING 1 POST SIGN STRUCTURE	12.000 EA	_____	_____	_____	_____
0940	700	50430 SIGN POST STP-1, 2", 14 GAUGE	71.000 LF	_____	_____	_____	_____
0950	700	50432 SIGN POST STP-1, 2 3/16", 10 GAUGE	30.000 LF	_____	_____	_____	_____
0960	700	50434 SIGN POST STP-1, 2 1/2", 10 GAUGE	82.000 LF	_____	_____	_____	_____
0970	700	50436 SIGN POST STP-1, 2 1/2", 12 GAUGE	62.000 LF	_____	_____	_____	_____
0980	700	50485 CONCRETE SIGN FOUNDATION STP-1, TYPE A	15.000 EA	_____	_____	_____	_____
0990	700	50486 CONCRETE SIGN FOUNDATION STP-1, TYPE B	7.000 EA	_____	_____	_____	_____
1000	ATTD	50864 REMOVE-DISPOSE SIGN STRUCT. TY. VI A	1.000 EA	_____	_____	_____	_____
1010	704	54076 TYPE B CLASS VI PVMT LINE MRKG 6"	18,870.000 LF	_____	_____	_____	_____
1020	512	54105 ERADICATE EXIST. LINEAR PVMT MARKING	20,000.000 LF	_____	_____	_____	_____
1030	510	54210 REMOVE EXIST. RAISED PAVEMENT MARKER	76.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000116157C01 Oversight/State Project No.: 0081-086-830, C501
 Order No.: H06 Federal Project No.: NHPP-081-1(403)

Contractor: _____

SECTION: 0001 REGULAR ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1040	ATTD	54219 INLAID PAVEMENT MARKER ASPHALT	131.000 EA	_____	_____	_____	_____
1050	512	54543 TYPE D, CLASS III TEMP. PVMT MRKG 6"	17,400.000 LF	_____	_____	_____	_____
1060	512	54544 TYPE D, CLASS III TEMP. PVMT MRKG 8"	2,300.000 LF	_____	_____	_____	_____
1070	704	54590 PVMT SYMB MRKG LANE REDUCTION ARROW TY B, CL II	2.000 EA	_____	_____	_____	_____
Section: 0001				Total:		_____	_____
				Total Bid:		_____	_____