

Schedule of Items

Proposal ID: C00011779D85B Oversight/State Project No.: 0702-002-928, D685

Order No.: G96

Federal Project No.: NONE

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	513	00100 MOBILIZATION	LUMP SUM	LUMP SUM			
0020	517	00101 CONSTRUCTION SURVEYING CONSTRUCTION	LUMP SUM	LUMP SUM			
0030	301	00110 CLEARING AND GRUBBING	LUMP SUM	LUMP SUM			
0040	303	00120 REGULAR EXCAVATION	153.000 CY				
0050	305	00140 BORROW EXCAVATION	718.000 CY				
0060	303	00212 MINOR STRUCTURE EXCAV. BOX CULVERT	1,120.000 CY				
0070	302 205	00506 BEDDING MATL. AGGR. NO. NO.57	25.000 TON				
0080	302	01150 15" PIPE	61.000 LF				
0090	414	09148 EROSION CONTROL STONE CLASS A1 EC-1	3.000 TON				
0100	308	10128 AGGR. BASE MATL. TY. I NO. 21B	340.000 TON				
0110	315	10610 ASPHALT CONCRETE TY. IM-19.0A	97.000 TON				
0120	515	10628 FLEXIBLE PAVEMENT PLANING 0" - 2"	825.000 SY				
0130	315	10635 ASPHALT CONC.TY. SM-9.5A	132.000 TON				

Schedule of Items

Proposal ID: C000111779D85B Oversight/State Project No.: 0702-002-928, D685

Order No.: G96

Federal Project No.: NONE

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0140	315	11070 SAW-CUT ASPH CONC SAW CUT	605.000 LF	_____	_____	_____	_____
0150	512	13495 TRAF. BARR. SER. CONC. SINGLE FACE PAR.MB-10A	170.000 LF	_____	_____	_____	_____
0160	512	13496 TRAF. BARR. SER. CONC. DOUBLE FACE PAR.MB-11A	170.000 LF	_____	_____	_____	_____
0170	505	13603 IMPACT ATTEN. TY. 1 TL-3, LOW MAINTENANCE	4.000 EA	_____	_____	_____	_____
0180	507	22643 FENCE FE-CL	50.000 LF	_____	_____	_____	_____
0190	507	22653 LINE BRACE UNIT FE-CL	1.000 EA	_____	_____	_____	_____
0200	507	22663 CORNER BRACE UNIT FE-CL	1.000 EA	_____	_____	_____	_____
0210	511	24100 ALLAYING DUST	100.000 HR	_____	_____	_____	_____
0220	512	24152 TYPE 3 BARRICADE 8'	4.000 EA	_____	_____	_____	_____
0230	512	24160 TEMPORARY (CONSTRUCTION) SIGN	310.000 SF	_____	_____	_____	_____
0240	ATTD	24262 PORTABLE TEMPORARY RUMBLE STRIP ARRAY	8.000 DAY	_____	_____	_____	_____
0250	512	24278 GROUP 2 CHANNELIZING DEVICES	3,650.000 DAY	_____	_____	_____	_____
0260	512	24279 PORTABLE CHANGEABLE MESSAGE SIGN	672.000 HR	_____	_____	_____	_____

Schedule of Items

Proposal ID: C000111779D85B Oversight/State Project No.: 0702-002-928, D685

Order No.: G96

Federal Project No.: NONE

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0270	512	24282 FLAGGER SERVICE	100.000 HR	_____	_____	_____	_____
0280	508	24430 DEMOLITION OF PAVEMENT FLEXIBLE	241.000 SY	_____	_____	_____	_____
0290	510	24602 REMOVE EXIST. FENCE REMOVE EXIST FENCE	50.000 LF	_____	_____	_____	_____
0300	603	27102 REGULAR SEED	45.000 LB	_____	_____	_____	_____
0310	603	27103 OVERSEEDING	37.000 LB	_____	_____	_____	_____
0320	603	27104 LEGUME SEED	6.000 LB	_____	_____	_____	_____
0330	603	27105 LEGUME OVERSEEDING	5.000 LB	_____	_____	_____	_____
0340	603	27111 HYDRAULIC EROSION CONTROL PRODUCT TYPE 2	2,000.000 SY	_____	_____	_____	_____
0350	603	27112 HYDRAULIC EROSION CONTROL PRODUCT TYPE 3	250.000 SY	_____	_____	_____	_____
0360	603	27230 FERTILIZER NITROGEN - N	24.000 LB	_____	_____	_____	_____
0370	603	27231 FERTILIZER PHOSPHOROUS - P	29.000 LB	_____	_____	_____	_____
0380	603	27232 FERTILIZER POTASSIUM - K	15.000 LB	_____	_____	_____	_____
0390	603	27250 LIME	1.100 TON	_____	_____	_____	_____

Schedule of Items

Proposal ID: C000111779D85B Oversight/State Project No.: 0702-002-928, D685

Order No.: G96

Federal Project No.: NONE

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0400	606	27321 ROLLED EROSION CTRL PRODUCT EC-2 TYPE 4	90.000 SY	_____	_____	_____	_____
0410	606	27325 ROLLED EROSION CTRL PRODUCT EC-3 TYPE 1	80.000 SY	_____	_____	_____	_____
0420	303	27415 CHECK DAM ROCK TY. II	11.000 EA	_____	_____	_____	_____
0430	303	27422 DEWATERING BASIN EC-8	2.000 EA	_____	_____	_____	_____
0440	303	27430 SILTATION CONTROL EXCAVATION	134.000 CY	_____	_____	_____	_____
0450	303	27505 TEMP. SILT FENCE TYPE A	718.000 LF	_____	_____	_____	_____
0460	520	45562 16" STEEL ENCASE. PIPE	50.000 LF	_____	_____	_____	_____
0470	701	50108 SIGN PANEL	19.000 SF	_____	_____	_____	_____
0480	700	50340 RELOCATE EXISTING 1 POST GROUND MOUNTED SIGN PANEL	2.000 EA	_____	_____	_____	_____
0490	700	50430 SIGN POST STP-1, 2", 14 GAUGE	60.000 LF	_____	_____	_____	_____
0500	700	50485 CONCRETE SIGN FOUNDATION STP-1, TYPE A	5.000 EA	_____	_____	_____	_____
0510	512	51955 TEMPORARY TRAFFIC CONTROL SIGNAL TRAFFIC SIGNALZATION	LUMP SUM	LUMP SUM	_____	_____	_____

Schedule of Items

Proposal ID: C000111779D85B Oversight/State Project No.: 0702-002-928, D685

Order No.: G96

Federal Project No.: NONE

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0520	704	54043 TYPE B CLASS II PAVE. LINE MARKING 4"	1,700.000 LF	_____	_____	_____	_____
0530	704	54048 TYPE B CLASS II PAVE. LINE MARKING 24"	30.000 LF	_____	_____	_____	_____
0540	512	54105 ERADICATE EXIST. LINEAR PVMT MARKING	500.000 LF	_____	_____	_____	_____
0550	512	54542 TYPE D, CLASS III TEMP. PVMT MRKG 4"	1,000.000 LF	_____	_____	_____	_____
0560	512	54544 TYPE D, CLASS III TEMP. PVMT MRKG 8"	400.000 LF	_____	_____	_____	_____
0570	512	54548 TYPE D, CLASS III TEMP. PVMT MRKG 24"	96.000 LF	_____	_____	_____	_____
0580	ATTD	60125 BRIDGE SEGEMENTAL PRECAST REINF. CONC. BOX CULVERT 15'X15'	LUMP SUM	LUMP SUM		_____	_____
0590	401	64032 GEOCOMPOSITE WALL DRAIN	176.000 SY	_____	_____	_____	_____
0600	401	64036 PIPE UNDERDRAIN 6"	160.000 LF	_____	_____	_____	_____
0610	404	65013 CONCRETE CLASS A3	204.100 CY	_____	_____	_____	_____
0620	406	65200 REINF. STEEL	7,578.000 LB	_____	_____	_____	_____
0630	406	65211 CORROSION RESISTANT REINF. STEEL CL. I	8,204.000 LB	_____	_____	_____	_____

Schedule of Items

Proposal ID: C000111779D85B Oversight/State Project No.: 0702-002-928, D685

Order No.: G96

Federal Project No.: NONE

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0640	401	66120 COFFERDAM	6.000 EA	_____	_____	_____	_____
0650	414	66127 DRY RIPRAP CL.I 26"	400.000 TON	_____	_____	_____	_____
0660	ATTD	67904 BRIDGE INCIDENTALS TEMPORARY SHORING	LUMP SUM	LUMP SUM		_____	_____
0670	410	68047 CONCRETE PARAPET 42"	43.500 LF	_____	_____	_____	_____
0680	431	68675 EPOXY OVERLAY	34.200 SY	_____	_____	_____	_____
0690	413	68900 REM. PORT. OF EX. STR. DISMANTLE AND REMOVE PORTION OF EXIST. STR.NO. 6401	LUMP SUM	LUMP SUM		_____	_____
Section: 0001				Total:		_____	_____
				Total Bid:		_____	_____