

Schedule of Items

Proposal ID: C000000121076B

Oversight/State Project No.: 9999-964-748

Order No.: H49

Federal Project No.: BFP-964-4(162)

Contractor: \_\_\_\_\_

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	ATTD	00098 MOBILIZATION ON-CALL TASK ORDER GREATER THAN \$200,000 (RICHMOND DISTRICTWIDE)	5.000 EA	_____	_____	_____	_____
0020	512	24160 TEMPORARY (CONSTRUCTION) SIGN	2,808.000 SF	_____	_____	_____	_____
0030	ATTD	24262 PORTABLE TEMPORARY RUMBLE STRIP ARRAY	44.000 DAY	_____	_____	_____	_____
0040	512	24272 TRUCK MOUNTED ATTENUATOR	2,944.000 HR	_____	_____	_____	_____
0050	512	24278 GROUP 2 CHANNELIZING DEVICES	26,423.000 DAY	_____	_____	_____	_____
0060	512	24281 ELECTRONIC ARROW BOARD	4,480.000 HR	_____	_____	_____	_____
0070	512	24282 FLAGGER SERVICE	1,408.000 HR	_____	_____	_____	_____
0080	ATTD	67908 BRIDGE INCIDENTALS INSPECT STRUCTURES (VARIOUS)	3.000 EA	_____	_____	_____	_____
0090	430	67910 NBIS ACCESS, UNDER BRIDGE VA STR. NO VARIOUS STRUCTURES	15.000 DAY	_____	_____	_____	_____
0100	404	68090 BRIDGE DECK GROOVING	6,268.000 SY	_____	_____	_____	_____
0110	412	68166 REPLACE ANCHOR BOLT	23.000 EA	_____	_____	_____	_____
0120	412	68172 CRACK REPAIR TYPE B	791.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000000121076B

Oversight/State Project No.: 9999-964-748

Order No.: H49

Federal Project No.: BFP-964-4(162)

Contractor: \_\_\_\_\_

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0130	412	68180 EMBEDDED GALVANIC ANODES	1,025.000 EA	_____	_____	_____	_____
0140	426	68192 REPLACE BEARING	144.000 EA	_____	_____	_____	_____
0150	426	68193 RESET EXIST. ROCKER EXPANSION BEARING	18.000 EA	_____	_____	_____	_____
0160	425	68258 REMOVE ASPHALT CONCRETE OVERLAY	3,928.000 SY	_____	_____	_____	_____
0170	316	68265 CONC. CLASS A-4 BRIDGE APPR. SLAB	48.000 CY	_____	_____	_____	_____
0180	316	68270 REINF. STEEL BRIDGE APPR. SLAB	7,200.000 LB	_____	_____	_____	_____
0190	412	68312 H.E.S. PATCHING TYPE A	26.000 SY	_____	_____	_____	_____
0200	425	68313 TYPE A MILLING 1/2"	1,643.000 SY	_____	_____	_____	_____
0210	425	68314 TYPE A MILLING 1"	2,340.000 SY	_____	_____	_____	_____
0220	412	68322 H.E.S. PATCHING TYPE B	24.000 SY	_____	_____	_____	_____
0230	412	68339 DECK SLAB CLOSURE	491.000 SY	_____	_____	_____	_____
0240	411	68455 PRE.& SPOT COAT EX. STR. VARIOUS STRUCTURES	1,556.000 SF	_____	_____	_____	_____
0250	420	68542 ADHESIVE BASED JOINT SEALER CLASS III, 4"	1,010.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000000121076B

Oversight/State Project No.: 9999-964-748

Order No.: H49

Federal Project No.: BFP-964-4(162)

Contractor: \_\_\_\_\_

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0260	412	68571 RECONSTR. EXPAN. JOINT LMC-VE (TYPE C)	244.000 LF	_____	_____	_____	_____
0270	412	68579 RECONSTRUCT BACK WALL, HES	766.000 LF	_____	_____	_____	_____
0280	412	68590 JACKING AND BLOCKING BEAM	144.000 EA	_____	_____	_____	_____
0290	412	68600 CONCRETE SUPERSTRUCT. SURFACE REPAIR	115.000 SY	_____	_____	_____	_____
0300	425	68616 PLACE VERY EARLY STRENGTH LATEX MODIFIED CONCRETE OVERLAY	6,268.000 SY	_____	_____	_____	_____
0310	ATTD	68621 FURNISH VERY EARLY STRENGTH LATEX MOD. CONC. 1-1/2" - 2"	98.000 CY	_____	_____	_____	_____
0320	ATTD	68621 FURNISH VERY EARLY STRENGTH LATEX MOD. CONC. 3" - 4-1/2"	424.000 CY	_____	_____	_____	_____
0330	425	68642 TYPE A HYDRO-DEMOLITION 1/2"	6,268.000 SY	_____	_____	_____	_____
0340	ATTD	68904 SUPERSTR. WID./REPAIR CLEAN BEARING ASSEMBLY	40.000 EA	_____	_____	_____	_____
0350	ATTD	68907 SUPERSTR. WID./REPAIR STRUCTURAL STEEL REPAIR	19,696.000 LB	_____	_____	_____	_____
0360	412	69815 RECONSTRUCT BRIDGE SEAT TYPE A	144.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000000121076B

Oversight/State Project No.: 9999-964-748

Order No.: H49

Federal Project No.: BFP-964-4(162)

Contractor: \_\_\_\_\_

SECTION: 0001                      REGULAR BID ITEMS

Cat Alt Set ID:                      Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0370	416	69835 WATERPROOFING - EPOXY RESIN TYPE EP-3B/EP-3T	210.000 SY	_____	_____	_____	_____
<b>Section: 0001</b>				<b>Total:</b>		_____	_____
				<b>Total Bid:</b>		_____	_____