

Schedule of Items

Proposal ID: C0000098823B01

Oversight/State Project No.: 0601-047-622,B608,M501

Order No.: H57

Federal Project No.: STP-5B03(035)

Contractor: \_\_\_\_\_

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	513	00100 MOBILIZATION	LUMP SUM	LUMP SUM			
0020	517	00101 CONSTRUCTION SURVEYING CONSTRUCTION	LUMP SUM	LUMP SUM			
0030	301	00110 CLEARING AND GRUBBING	LUMP SUM	LUMP SUM			
0040	303	00120 REGULAR EXCAVATION	1,102.000 CY				
0050	305	00140 BORROW EXCAVATION	842.000 CY				
0060	305	00154 GEOTEXTILE GEOTEXTILE GEOGRID	665.000 SY				
0070	303	00155 GEOTEXTILE EMBANKMENT STABILIZATION	4.000 SY				
0080	305	00280 SELECT MATL. TY. II MIN. CBR-20	821.000 CY				
0090	305	00355 GEOTEXTILE SUBGRADE STABILIZATION	665.000 SY				
0100	308	10128 AGGR. BASE MATL. TY. I NO. 21B	169.000 TON				
0110	310	10417 TACK COAT	10.000 GAL				
0120	515	10628 FLEXIBLE PAVEMENT PLANING 0" - 2"	226.000 SY				
0130	315	10635 ASPHALT CONC.TY. SM-9.5A	50.000 TON				

Schedule of Items

Proposal ID: C0000098823B01

Oversight/State Project No.: 0601-047-622,B608,M501

Order No.: H57

Federal Project No.: STP-5B03(035)

Contractor: \_\_\_\_\_

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0140	315	11070 SAW-CUT ASPH CONC SAWCUT AC	40.000 LF	_____	_____	_____	_____
0150	505	13280 GUARDRAIL GR-MGS1	100.000 LF	_____	_____	_____	_____
0160	505	13286 GUARDRAIL TERMINAL GR- MGS2	4.000 EA	_____	_____	_____	_____
0170	505	13349 GUARDRAIL TERMINAL SITE PREPARATION	4.000 EA	_____	_____	_____	_____
0180	512	13611 IMPACT ATTENUATOR SERVICE TYPE I	4.000 EA	_____	_____	_____	_____
0190	ATTD	14260 CRUSHER RUN AGGREGATE NO. 25 OR 26	150.000 TON	_____	_____	_____	_____
0200	ATTD	14280 COARSE AGGREGATE NO.8	225.000 TON	_____	_____	_____	_____
0210	ATTD	16241 AGGR. MATL NO. 2 STONE	1,575.000 TON	_____	_____	_____	_____
0220	507	23570 HIGH VISIBILITY FENCE, 4'	800.000 LF	_____	_____	_____	_____
0230	511	24100 ALLAYING DUST	360.000 HR	_____	_____	_____	_____
0240	512	24150 TYPE 3 BARRICADE 4'	2.000 EA	_____	_____	_____	_____
0250	512	24160 TEMPORARY (CONSTRUCTION) SIGN	360.000 SF	_____	_____	_____	_____
0260	512	24278 GROUP 2 CHANNELIZING DEVICES	18,250.000 DAY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000098823B01

Oversight/State Project No.: 0601-047-622,B608,M501

Order No.: H57

Federal Project No.: STP-5B03(035)

Contractor: \_\_\_\_\_

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0270	512	24279 PORTABLE CHANGEABLE MESSAGE SIGN	2,016.000 HR	_____	_____	_____	_____
0280	512	24282 FLAGGER SERVICE	180.000 HR	_____	_____	_____	_____
0290	508	24410 DEMOLITION OF PAVEMENT COMBINATION	226.000 SY	_____	_____	_____	_____
0300	ATTD	25565 BASELINE PROGRESS SCHEDULE	LUMP SUM	LUMP SUM	_____	_____	_____
0310	ATTD	25567 PROGRESS SCHEDULE UPDATES	29.000 EA	_____	_____	_____	_____
0320	602	27012 TOPSOIL CLASS A 2"	0.210 ACRE	_____	_____	_____	_____
0330	603	27101 TEMPORARY SEED	63.000 LB	_____	_____	_____	_____
0340	603	27102 REGULAR SEED	98.000 LB	_____	_____	_____	_____
0350	603	27103 OVERSEEDING	77.000 LB	_____	_____	_____	_____
0360	603	27111 HYDRAULIC EROSION CONTROL PRODUCT TYPE 2	430.000 SY	_____	_____	_____	_____
0370	603	27112 HYDRAULIC EROSION CONTROL PRODUCT TYPE 3	6,440.000 SY	_____	_____	_____	_____
0380	603	27120 SEDIMENT RETENTION ROLL 18" MIN	154.000 LF	_____	_____	_____	_____
0390	603	27230 FERTILIZER NITROGEN - N	63.000 LB	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000098823B01

Oversight/State Project No.: 0601-047-622,B608,M501

Order No.: H57

Federal Project No.: STP-5B03(035)

Contractor: \_\_\_\_\_

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0400	603	27231 FERTILIZER PHOSPHOROUS - P	84.000 LB	_____	_____	_____	_____
0410	603	27232 FERTILIZER POTASSIUM - K	42.000 LB	_____	_____	_____	_____
0420	603	27250 LIME	0.900 TON	_____	_____	_____	_____
0430	303	27284 EROSION CONTROL MULCH	2,800.000 SY	_____	_____	_____	_____
0440	606	27318 ROLLED EROSION CTRL PRODUCT EC-2 TYPE 1	95.000 SY	_____	_____	_____	_____
0450	606	27319 ROLLED EROSION CTRL PRODUCT EC-2 TYPE 2	366.000 SY	_____	_____	_____	_____
0460	606	27325 ROLLED EROSION CTRL PRODUCT EC-3 TYPE 1	50.000 SY	_____	_____	_____	_____
0470	303	27419 CHECK DAM ROCK TYPE I TEMPORARY	2.000 EA	_____	_____	_____	_____
0480	303	27430 SILTATION CONTROL EXCAVATION	371.000 CY	_____	_____	_____	_____
0490	303	27504 TEMP. SILT FENCE TYPE B	611.000 LF	_____	_____	_____	_____
0500	303	27525 TURBIDITY CURTAIN, PERVIOUS	335.000 LF	_____	_____	_____	_____
0510	512	54542 TYPE D, CLASS III TEMP. PVMT MRKG 4"	75.000 LF	_____	_____	_____	_____

## Schedule of Items

Proposal ID: C0000098823B01

Oversight/State Project No.: 0601-047-622,B608,M501

Order No.: H57

Federal Project No.: STP-5B03(035)

Contractor: \_\_\_\_\_

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0520	512	54544 TYPE D, CLASS III TEMP. PVMT MRKG 8"	1,234.000 LF	_____	_____	_____	_____
0530	512	54548 TYPE D, CLASS III TEMP. PVMT MRKG 24"	20.000 LF	_____	_____	_____	_____
0540	ATTD	60125 BRIDGE TEMPORARY BRIDGE	LUMP SUM	LUMP SUM	_____	_____	_____
0550	404	60404 CONCRETE CLASS A4	19.600 CY	_____	_____	_____	_____
0560	404	60490 BRIDGE DECK GROOVING	118.000 SY	_____	_____	_____	_____
0570	410	62021 RAILING BMGS-2	144.000 LF	_____	_____	_____	_____
0580	405	61181 PREST. CONC. SLAB 4' X 18" X(+30' - 35')	8.000 EA	_____	_____	_____	_____
0590	406	61711 CORROSION RESISTANT REINF. STEEL CL. I	1,881.000 LB	_____	_____	_____	_____
0600	401	64011 STRUCTURE EXCAVATION	226.000 CY	_____	_____	_____	_____
0610	401	64015 SELECT BACKFILL ABUTMENT ZONE	626.000 TON	_____	_____	_____	_____
0620	401	64032 GEOCOMPOSITE WALL DRAIN	18.000 SY	_____	_____	_____	_____
0630	401	64036 PIPE UNDERDRAIN 6"	56.000 LF	_____	_____	_____	_____
0640	403	64101 DYNAMIC PILE TEST	3.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000098823B01

Oversight/State Project No.: 0601-047-622,B608,M501

Order No.: H57

Federal Project No.: STP-5B03(035)

Contractor: \_\_\_\_\_

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0670	403	64808 DRIVING TEST FOR 12" PRESTR. CONC. PILE	191.000 LF	_____	_____	_____	_____
0680	403	64828 DRIVING TEST FOR 18" PRESTR. CONC. PILE	87.000 LF	_____	_____	_____	_____
0690	404	65013 CONCRETE CLASS A3	59.400 CY	_____	_____	_____	_____
0700	406	65200 REINF. STEEL	3,226.000 LB	_____	_____	_____	_____
0710	406	65211 CORROSION RESISTANT REINF. STEEL CL. I	1,859.000 LB	_____	_____	_____	_____
0720	401	66120 COFFERDAM	3.000 EA	_____	_____	_____	_____
0730	414	66127 DRY RIPRAP CL.I 26"	139.000 TON	_____	_____	_____	_____
0740	512	67110 TRAFFIC BARRIER SERVICE CONCRETE	482.000 LF	_____	_____	_____	_____
0750	413	67900 DISM.& REM. EX. STR. REMOVE EXIST. BRIDGE No. 6001	LUMP SUM	LUMP SUM	_____	_____	_____
0760	425	68621 FURNISH VERY EARLY STRENGTH LATEX MOD. CONC. Very High Performance Concrete VHPC for box beams closure	2.000 CY	_____	_____	_____	_____
0770	ATTD	70005 DEMOLITION WITH ACM INCLUDE CLEARING OF PARCEL NO 3; NON FRIABLE ASBESTOS	LUMP SUM	LUMP SUM	_____	_____	_____

Schedule of Items

Proposal ID: C0000098823B01  
Order No.: H57

Oversight/State Project No.: 0601-047-622,B608,M501  
Federal Project No.: STP-5B03(035)

Contractor: \_\_\_\_\_

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0780	ATTD	70114 CAT I NF ACM	2,632.000 SF	_____	_____	_____	_____

Section: 0001 Total: \_\_\_\_\_

SECTION: 0002 ALTERNATE 1

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0650	403	64512 PRESTR. CONC STAINLESS STEEL STRAND PILES 12"	1,153.000 LF	_____	_____	_____	_____
0790	403	64612 PRESTR. CONC CFRP STRAND PILES 12"	1,153.000 LF	_____	_____	_____	_____

Section: 0002 Total: \_\_\_\_\_

SECTION: 0003 ALTERNATE 2

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0660	403	64518 PRESTR. CONC STAINLESS STEEL STRAND PILES 18"	229.000 LF	_____	_____	_____	_____
0800	403	64618 PRESTR. CONC CFRP STRAND PILES 18"	229.000 LF	_____	_____	_____	_____

Section: 0003 Total: \_\_\_\_\_

Total Bid: \_\_\_\_\_