

Schedule of Items

Proposal ID: C0000120718M01

Oversight/State Project No.: 0637-079-610,B614,M501

Order No.: H76

Federal Project No.: STP-PM04(523)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	513	00100 MOBILIZATION	LUMP SUM	LUMP SUM			
0020	517	00101 CONSTRUCTION SURVEYING CONSTRUCTION	LUMP SUM	LUMP SUM			
0030	301	00111 CLEARING AND GRUBBING	0.200 ACRE				
0040	303	00120 REGULAR EXCAVATION	342.000 CY				
0050	305	00140 BORROW EXCAVATION	316.000 CY				
0060	308	10128 AGGR. BASE MATL. TY. I NO. 21B	215.000 TON				
0070	515	10628 FLEXIBLE PAVEMENT PLANING 0" - 2"	66.000 SY				
0080	315	11070 SAW-CUT ASPH CONC FULL DEPTH	41.000 LF				
0090	502	12030 STD. CURB CG-3	109.000 LF				
0100	505	13280 GUARDRAIL GR-MGS1	37.500 LF				
0110	505	13286 GUARDRAIL TERMINAL GR- MGS2	1.000 EA				
0120	505	13288 GUARDRAIL HEIGHT TRANSITION GR-MGS4	3.000 EA				
0130	505	13394 FIXED OBJECT ATTACH. GR- FOA-5	4.000 EA				

Schedule of Items

Proposal ID: C0000120718M01

Oversight/State Project No.: 0637-079-610,B614,M501

Order No.: H76

Federal Project No.: STP-PM04(523)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0140	512	13496 TRAF. BARR. SER. CONC. DOUBLE FACE PAR.MB-11A	48.000 LF	_____	_____	_____	_____
0150	315	16350 ASPHALT CONC. TY. SM-12.5A	44.000 TON	_____	_____	_____	_____
0160	315	16365 ASPHALT CONC. TY. IM-19.0A	36.000 TON	_____	_____	_____	_____
0170	512	24152 TYPE 3 BARRICADE 8'	4.000 EA	_____	_____	_____	_____
0180	508	24430 DEMOLITION OF PAVEMENT FLEXIBLE	349.000 SY	_____	_____	_____	_____
0190	505	24600 REMOVE EXISTING GUARDRAIL	367.000 LF	_____	_____	_____	_____
0200	ATTD	25565 BASELINE PROGRESS SCHEDULE	LUMP SUM	LUMP SUM		_____	_____
0210	ATTD	25567 PROGRESS SCHEDULE UPDATES	16.000 EA	_____	_____	_____	_____
0220	414	26117 DRY RIPRAP CL. AI	29.000 TON	_____	_____	_____	_____
0230	602	27012 TOPSOIL CLASS A 2"	0.220 ACRE	_____	_____	_____	_____
0240	603	27101 TEMPORARY SEED	22.000 LB	_____	_____	_____	_____
0250	603	27102 REGULAR SEED	34.000 LB	_____	_____	_____	_____
0260	603	27103 OVERSEEDING	27.000 LB	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000120718M01

Oversight/State Project No.: 0637-079-610,B614,M501

Order No.: H76

Federal Project No.: STP-PM04(523)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0270	603	27110 HYDRAULIC EROSION CONTROL PRODUCT TYPE 1	430.000 SY	_____	_____	_____	_____
0280	603	27112 HYDRAULIC EROSION CONTROL PRODUCT TYPE 3	1,960.000 SY	_____	_____	_____	_____
0290	603	27230 FERTILIZER NITROGEN - N	34.000 LB	_____	_____	_____	_____
0300	603	27231 FERTILIZER PHOSPHOROUS - P	15.000 LB	_____	_____	_____	_____
0310	603	27232 FERTILIZER POTASSIUM - K	15.000 LB	_____	_____	_____	_____
0320	603	27250 LIME	1.210 TON	_____	_____	_____	_____
0330	606	27321 ROLLED EROSION CTRL PRODUCT EC-2 TYPE 4	42.000 SY	_____	_____	_____	_____
0340	303	27415 CHECK DAM ROCK TY. II	2.000 EA	_____	_____	_____	_____
0350	303	27422 DEWATERING BASIN EC-8	2.000 EA	_____	_____	_____	_____
0360	303	27430 SILTATION CONTROL EXCAVATION	79.000 CY	_____	_____	_____	_____
0370	303	27505 TEMP. SILT FENCE TYPE A	463.000 LF	_____	_____	_____	_____
0380	303	27526 TURBIDITY CURTAIN, IMPERVIOUS	104.000 LF	_____	_____	_____	_____
0390	ATTD	28501 WETLAND NON-TIDAL WETLAND TEMPORARY RESTORATION	LUMP SUM	LUMP SUM	_____	_____	_____

Schedule of Items

Proposal ID: C0000120718M01

Oversight/State Project No.: 0637-079-610,B614,M501

Order No.: H76

Federal Project No.: STP-PM04(523)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0400	701	50108 SIGN PANEL	9.000 SF	_____	_____	_____	_____
0410	700	50430 SIGN POST STP-1, 2", 14 GAUGE	24.000 LF	_____	_____	_____	_____
0420	700	50485 CONCRETE SIGN FOUNDATION STP-1, TYPE A	2.000 EA	_____	_____	_____	_____
0430	404	60409 CONC. CLASS A4 MOD. LOW SHRINKAGE	93.900 CY	_____	_____	_____	_____
0440	404	60490 BRIDGE DECK GROOVING	343.000 SY	_____	_____	_____	_____
0450	404	60495 COVER DEPTH SURVEY	343.000 SY	_____	_____	_____	_____
0460	ATTD,404	61020 VIRGINIA ADJACENT MEMBER CONNECTION BLOCK-OUTS	172.000 CF	_____	_____	_____	_____
0470	405	61150 PREST. CONC. SLAB 3' X 21" X(+50' - 55')	4.000 EA	_____	_____	_____	_____
0480	405	61200 PREST. CONCRETE BEAM PREST. CONC. SLAB 4' X 21" (+50'-55')	12.000 EA	_____	_____	_____	_____
0490	406	61711 CORROSION RESISTANT REINF. STEEL CL. I	11,210.000 LB	_____	_____	_____	_____
0500	410	62034 RAILING, CPSR 2 RAIL	220.000 LF	_____	_____	_____	_____
0510	401	64011 STRUCTURE EXCAVATION	1,440.000 CY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000120718M01 Oversight/State Project No.: 0637-079-610,B614,M501
 Order No.: H76 Federal Project No.: STP-PM04(523)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0520	401	64015 SELECT BACKFILL ABUTMENT ZONE	1,560.000 TON	_____	_____	_____	_____
0530	401	64032 GEOCOMPOSITE WALL DRAIN	84.000 SY	_____	_____	_____	_____
0540	403	64101 DYNAMIC PILE TEST	4.000 EA	_____	_____	_____	_____
0550	403	64414 PRESTR. CONC. CARBON STEEL STRAND PILES 14"	1,634.000 LF	_____	_____	_____	_____
0560	403	64424 PRESTR. CONC. CARBON STEEL STRAND PILES 24"	183.000 LF	_____	_____	_____	_____
0570	403	64818 DRIVING TEST FOR 14" PRESTR. CONC. PILE	106.000 LF	_____	_____	_____	_____
0580	403	64868 DRIVING TEST FOR 24" PRESTR. CONC. PILE	142.000 LF	_____	_____	_____	_____
0590	404	65013 CONCRETE CLASS A3	160.300 CY	_____	_____	_____	_____
0600	406	65200 REINF. STEEL	9,720.000 LB	_____	_____	_____	_____
0610	406	65211 CORROSION RESISTANT REINF. STEEL CL. I	6,410.000 LB	_____	_____	_____	_____
0620	401	66120 COFFERDAM	2.000 EA	_____	_____	_____	_____
0630	414	66239 DRY RIPRAP CL.II 38"	810.000 TON	_____	_____	_____	_____
0640	413	67900 DISM.& REM. EX. STR. STR NO 6013	LUMP SUM	LUMP SUM	_____	_____	_____

Schedule of Items

Proposal ID: C0000120718M01

Oversight/State Project No.: 0637-079-610,B614,M501

Order No.: H76

Federal Project No.: STP-PM04(523)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0650	430	67910 NBIS ACCESS, UNDER BRIDGE B614	1.000 DAY	_____	_____	_____	_____
Section: 0001				Total:		_____	_____
				Total Bid:		_____	_____