

Schedule of Items

Proposal ID: C000102937C501B Oversight/State Project No.: 0001-016-594, B619, C501
 Order No.: G72 Federal Project No.: NHPP-016-6(089)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	513	00100 MOBILIZATION	LUMP SUM	LUMP SUM			
0020	517	00101 CONSTRUCTION SURVEYING CONSTRUCTION	LUMP SUM	LUMP SUM			
0030	301	00110 CLEARING AND GRUBBING	LUMP SUM	LUMP SUM			
0040	303	00125 GRADING	LUMP SUM	LUMP SUM			
0050	303	00128 EXTRA EXCAVATION	132.000 CY				
0060	302	01122 12" CONC. PIPE	25.000 LF				
0070	308	10128 AGGR. BASE MATL. TY. I NO. 21B	1,437.000 TON				
0080	315	10608 ASPHALT CONCRETE TY. SM- 12.5D	528.000 TON				
0090	315	10610 ASPHALT CONCRETE TY. IM- 19.0A	210.000 TON				
0100	515	10633 RIGID PAVEMENT PLANING 0" - 2"	156.000 SY				
0110	315	10642 ASPHALT CONCRETE TY. BM- 25.0A	219.000 TON				
0120	315	10700 RUMBLE STRIP CYLINDRICAL ASPHALT	1,800.000 LF				
0130	315	11070 SAW-CUT ASPH CONC (FULL DEPTH)	1,774.000 LF				

Schedule of Items

Proposal ID: C000102937C501B Oversight/State Project No.: 0001-016-594, B619, C501
 Order No.: G72 Federal Project No.: NHPP-016-6(089)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0140	315	11071 SAW-CUT HYD.CEM.CON.PAV (FULL DEPTH)	80.000 LF	_____	_____	_____	_____
0150	502	12700 STD. COMB. CURB & GUTTER CG-7	40.000 LF	_____	_____	_____	_____
0160	503	13212 R/W MONUMENT RM-2	9.000 EA	_____	_____	_____	_____
0170	505	13280 GUARDRAIL GR-MGS1	100.000 LF	_____	_____	_____	_____
0180	505	13286 GUARDRAIL TERMINAL GR- MGS2	4.000 EA	_____	_____	_____	_____
0190	505	13288 GUARDRAIL HEIGHT TRANSITION GR-MGS4	4.000 EA	_____	_____	_____	_____
0200	505	13372 SP. DES. GR.BR.ATTACH BR- GR (BGR21)	4.000 EA	_____	_____	_____	_____
0210	ATTD	13373 HAND DIG GUARDRAIL POST HOLE (PUNCH-OUTS)	112.000 EA	_____	_____	_____	_____
0220	502	13460 MEDIAN BARRIER MB-7D	1,100.000 LF	_____	_____	_____	_____
0230	512	13496 TRAF. BARR. SER. CONC. DOUBLE FACE PAR.MB-11A	120.000 LF	_____	_____	_____	_____
0240	512	13605 IMPACT ATTEN. SER. TY. 1 TL- 2, <40 MPH	4.000 EA	_____	_____	_____	_____
0250	515	16522 FLEXIBLE PAVEMENT PLANING 0" - 2"	11,647.000 SY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C000102937C501B Oversight/State Project No.: 0001-016-594, B619, C501
 Order No.: G72 Federal Project No.: NHPP-016-6(089)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0260	511	24100 ALLAYING DUST	100.000 HR	_____	_____	_____	_____
0270	512	24160 TEMPORARY (CONSTRUCTION) SIGN	536.000 SF	_____	_____	_____	_____
0280	ATTD	24262 PORTABLE TEMPORARY RUMBLE STRIP ARRAY	1,030.000 DAY	_____	_____	_____	_____
0290	512	24272 TRUCK MOUNTED ATTENUATOR	740.000 HR	_____	_____	_____	_____
0300	512	24278 GROUP 2 CHANNELIZING DEVICES	25,739.000 DAY	_____	_____	_____	_____
0310	512	24279 PORTABLE CHANGEABLE MESSAGE SIGN	22,728.000 HR	_____	_____	_____	_____
0320	512	24281 ELECTRONIC ARROW BOARD	7,688.000 HR	_____	_____	_____	_____
0330	508	24420 DEMOLITION OF PAVEMENT RIGID	107.000 SY	_____	_____	_____	_____
0340	508	24430 DEMOLITION OF PAVEMENT FLEXIBLE	881.000 SY	_____	_____	_____	_____
0350	514	25507 FIELD OFFICE TY.III	13.000 MO	_____	_____	_____	_____
0360	414	26127 DRY RIPRAP CL.I 26"	15.000 TON	_____	_____	_____	_____
0370	603	27101 TEMPORARY SEED	44.000 LB	_____	_____	_____	_____
0380	603	27102 REGULAR SEED	83.000 LB	_____	_____	_____	_____

Schedule of Items

Proposal ID: C000102937C501B Oversight/State Project No.: 0001-016-594, B619, C501
 Order No.: G72 Federal Project No.: NHPP-016-6(089)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0390	603	27103 OVERSEEDING	66.000 LB	_____	_____	_____	_____
0400	603	27111 HYDRAULIC EROSION CONTROL PRODUCT TYPE 2	847.000 SY	_____	_____	_____	_____
0410	603	27112 HYDRAULIC EROSION CONTROL PRODUCT TYPE 3	3,945.000 SY	_____	_____	_____	_____
0420	603	27230 FERTILIZER NITROGEN - N	44.000 LB	_____	_____	_____	_____
0430	603	27231 FERTILIZER PHOSPHOROUS - P	31.000 LB	_____	_____	_____	_____
0440	603	27232 FERTILIZER POTASSIUM - K	31.000 LB	_____	_____	_____	_____
0450	603	27250 LIME	2.420 TON	_____	_____	_____	_____
0460	606	27318 ROLLED EROSION CTRL PRODUCT EC-2 TYPE 1	142.000 SY	_____	_____	_____	_____
0470	606	27320 ROLLED EROSION CTRL PRODUCT EC-2 TYPE 3	305.000 SY	_____	_____	_____	_____
0480	606	27325 ROLLED EROSION CTRL PRODUCT EC-3 TYPE 1	97.000 SY	_____	_____	_____	_____
0490	303	27415 CHECK DAM ROCK TY. II	6.000 EA	_____	_____	_____	_____
0500	303	27422 DEWATERING BASIN EC-8	2.000 EA	_____	_____	_____	_____
0510	303	27430 SILTATION CONTROL EXCAVATION	131.000 CY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C000102937C501B Oversight/State Project No.: 0001-016-594, B619, C501
 Order No.: G72 Federal Project No.: NHPP-016-6(089)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0520	303	27505 TEMP. SILT FENCE TYPE A	723.000 LF	_____	_____	_____	_____
0530	701	50108 SIGN PANEL	6.000 SF	_____	_____	_____	_____
0540	700	50430 SIGN POST STP-1, 2", 14 GAUGE	24.000 LF	_____	_____	_____	_____
0550	700	50485 CONCRETE SIGN FOUNDATION STP-1, TYPE A	2.000 EA	_____	_____	_____	_____
0560	704	54032 TYPE B CLASS I PVMT LINE MRKG 4"	9,363.000 LF	_____	_____	_____	_____
0570	704	54040 TYPE B CLASS I PVMT LINE MRKG 12"	190.000 LF	_____	_____	_____	_____
0580	704	54042 TYPE B CLASS I PAVE. LINE MARKING 24"	29.000 LF	_____	_____	_____	_____
0590	512	54105 ERADICATE EXIST. LINEAR PVMT MARKING	20,915.000 LF	_____	_____	_____	_____
0600	ATTD	54219 INLAID PAVEMENT MARKER ASPHALT	145.000 EA	_____	_____	_____	_____
0610	512	54240 TEMP. PAVE. MARKER 1 WAY	169.000 EA	_____	_____	_____	_____
0620	512	54242 TEMP. PAVE. MARKER 2 WAY	61.000 EA	_____	_____	_____	_____
0630	512	54428 TEMP. PVMT MRKG, TY. A, 4"	16,601.000 LF	_____	_____	_____	_____
0640	512	54430 TEMP. PVMT MRKG, TY. A, 6"	2,134.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C000102937C501B Oversight/State Project No.: 0001-016-594, B619, C501
 Order No.: G72 Federal Project No.: NHPP-016-6(089)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0650	512	54432 TEMP. PVMT MRKG, TY. A, 8"	2,230.000 LF	_____	_____	_____	_____
0660	404	60490 BRIDGE DECK GROOVING	391.000 SY	_____	_____	_____	_____
0670	430	67910 NBIS ACCESS, UNDER BRIDGE NS NBIS ACCESS, UNDER BRIDGE	3.000 DAY	_____	_____	_____	_____
0680	412	68172 CRACK REPAIR TYPE B	170.000 LF	_____	_____	_____	_____
0690	412	68180 EMBEDDED GALVANIC ANODES	1,100.000 EA	_____	_____	_____	_____
0700	412	68191 FIBER REINFORCED POLYMER WRAPS	2,450.000 SF	_____	_____	_____	_____
0710	428	68197 CONCRETE SURFACE PENETRANT SEALER	150.000 SY	_____	_____	_____	_____
0720	425	68258 REMOVE ASPHALT CONCRETE OVERLAY	391.000 SY	_____	_____	_____	_____
0730	425	68317 TYPE A MILLING (1.5")	391.000 SY	_____	_____	_____	_____
0740	412	68320 PATCHING TYPE B	120.000 SY	_____	_____	_____	_____
0750	412	68330 PATCHING TYPE C	45.000 SY	_____	_____	_____	_____
0760	429	68403 BRIDGE DECK WATERPROOFING MEMBRANE TYPE III	24.000 SY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C000102937C501B Oversight/State Project No.: 0001-016-594, B619, C501
 Order No.: G72 Federal Project No.: NHPP-016-6(089)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0770	412	68572 RECONSTRUCT EXPANSION JOINT	66.000 LF	_____	_____	_____	_____
0780	412	68580 BEAM END REPAIR	4.000 EA	_____	_____	_____	_____
0790	412	68600 CONCRETE SUPERSTRUCT. SURFACE REPAIR	25.000 SY	_____	_____	_____	_____
0800	425	68607 PLACE LATEX MODIFIED CONCRETE OVERLAY	391.000 SY	_____	_____	_____	_____
0810	425	68618 FURNISH LATEX MODIFIED CONC. VERY EARLY STRENGTH (3")	33.000 CY	_____	_____	_____	_____
0820	401	69011 STRUCTURE EXCAVATION	64.000 CY	_____	_____	_____	_____
0830	412	69500 CONCRETE SUBSTRUCT. SURFACE REPAIR	27.000 SY	_____	_____	_____	_____
Section: 0001				Total:		_____	
				Total Bid:		_____	