

Schedule of Items

Proposal ID: C0000113031B67 Oversight/State Project No.: 0743-087-681,B667

Order No.: H74

Federal Project No.: BROS-087-5(048)

Contractor: _____

SECTION: 0001 REGULAR ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	513	00100 MOBILIZATION	LUMP SUM	LUMP SUM			
0020	517	00101 CONSTRUCTION SURVEYING CONSTRUCTION	LUMP SUM	LUMP SUM			
0030	301	00110 CLEARING AND GRUBBING	LUMP SUM	LUMP SUM			
0040	303	00120 REGULAR EXCAVATION	323.000 CY				
0050	305	00140 BORROW EXCAVATION	579.000 CY				
0060	315	10607 ASPHALT CONCRETE TY. SM-12.5A	72.000 TON				
0070	315	10642 ASPHALT CONCRETE TY. BM-25.0A	156.000 TON				
0080	505	13280 GUARDRAIL GR-MGS1	37.500 LF				
0090	505	13286 GUARDRAIL TERMINAL GR-MGS2	4.000 EA				
0100	505	13349 GUARDRAIL TERMINAL SITE PREPARATION	4.000 EA				
0110	315	16340 ASPHALT CONC. TY. SM-9.5D	19.000 TON				
0120	315	16370 ASPHALT CONC. TY. IM-19.0D	13.000 TON				
0130	512	24150 TYPE 3 BARRICADE 4'	4.000 EA				

Schedule of Items

Proposal ID: C0000113031B67 Oversight/State Project No.: 0743-087-681,B667

Order No.: H74

Federal Project No.: BROS-087-5(048)

Contractor: _____

SECTION: 0001 REGULAR ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0140	512	24152 TYPE 3 BARRICADE 8'	4.000 EA	_____	_____	_____	_____
0150	512	24160 TEMPORARY (CONSTRUCTION) SIGN	711.500 SF	_____	_____	_____	_____
0160	512	24290 TRAFFIC BARRIER SERVICE CONC. MB-7D PC	40.000 LF	_____	_____	_____	_____
0170	508	24430 DEMOLITION OF PAVEMENT FLEXIBLE	393.000 SY	_____	_____	_____	_____
0180	505	24600 REMOVE EXISTING GUARDRAIL	264.000 LF	_____	_____	_____	_____
0190	514	25507 FIELD OFFICE TY.III	10.000 MO	_____	_____	_____	_____
0200	602	27012 TOPSOIL CLASS A 2"	0.260 ACRE	_____	_____	_____	_____
0210	603	27101 TEMPORARY SEED	26.000 LB	_____	_____	_____	_____
0220	603	27102 REGULAR SEED	45.000 LB	_____	_____	_____	_____
0230	603	27103 OVERSEEDING	36.000 LB	_____	_____	_____	_____
0240	603	27111 HYDRAULIC EROSION CONTROL PRODUCT TYPE 2	968.000 SY	_____	_____	_____	_____
0250	603	27112 HYDRAULIC EROSION CONTROL PRODUCT TYPE 3	1,936.000 SY	_____	_____	_____	_____
0260	603	27230 FERTILIZER NITROGEN - N	26.000 LB	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000113031B67 Oversight/State Project No.: 0743-087-681,B667

Order No.: H74

Federal Project No.: BROS-087-5(048)

Contractor: _____

SECTION: 0001 REGULAR ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0270	603	27231 FERTILIZER PHOSPHOROUS - P	18.000 LB	_____	_____	_____	_____
0280	603	27232 FERTILIZER POTASSIUM - K	18.000 LB	_____	_____	_____	_____
0290	603	27250 LIME	1.430 TON	_____	_____	_____	_____
0300	303	27422 DEWATERING BASIN EC-8	2.000 EA	_____	_____	_____	_____
0310	303	27430 SILTATION CONTROL EXCAVATION	65.000 CY	_____	_____	_____	_____
0320	303	27504 TEMP. SILT FENCE TYPE B	356.000 LF	_____	_____	_____	_____
0330	303	27526 TURBIDITY CURTAIN, IMPERVIOUS	183.000 LF	_____	_____	_____	_____
0340	701	50108 SIGN PANEL	23.000 SF	_____	_____	_____	_____
0350	700	50300 REMOVE EXISTING 1 POST SIGN STRUCTURE	20.000 EA	_____	_____	_____	_____
0360	700	50436 SIGN POST STP-1, 2 1/2", 12 GAUGE	26.000 LF	_____	_____	_____	_____
0370	700	50489 CONCRETE SIGN FOUNDATION STP-1, TYPE E	2.000 EA	_____	_____	_____	_____
0380	410	60519 RAILING, 31" MGS	150.000 LF	_____	_____	_____	_____
0390	ATTD	61010 SHEAR KEYS	23.600 CF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000113031B67 Oversight/State Project No.: 0743-087-681,B667

Order No.: H74

Federal Project No.: BROS-087-5(048)

Contractor: _____

SECTION: 0001 REGULAR ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0400	ATTD,404	61020 VIRGINIA ADJACENT MEMBER CONNECTION BLOCK-OUTS	85.500 CF	_____	_____	_____	_____
0410	ATTD	62534 BRIDGE SUPERSTRUCTURE ELASTIC INCLUSION 10"	12.000 SY	_____	_____	_____	_____
0420	401	64011 STRUCTURE EXCAVATION	222.000 CY	_____	_____	_____	_____
0430	401	64015 SELECT BACKFILL ABUTMENT ZONE	287.000 TON	_____	_____	_____	_____
0440	401	64032 GEOCOMPOSITE WALL DRAIN	36.000 SY	_____	_____	_____	_____
0450	401	64036 PIPE UNDERDRAIN 6"	82.000 LF	_____	_____	_____	_____
0460	403	64101 DYNAMIC PILE TEST	1.000 EA	_____	_____	_____	_____
0470	403	64414 PRESTR. CONC. CARBON STEEL STRAND PILES 14"	760.000 LF	_____	_____	_____	_____
0480	404	65013 CONCRETE CLASS A3	21.000 CY	_____	_____	_____	_____
0490	406	65211 CORROSION RESISTANT REINF. STEEL CL. I	3,094.000 LB	_____	_____	_____	_____
0500	401	66120 COFFERDAM	2.000 EA	_____	_____	_____	_____
0510	414	66127 DRY RIPRAP CL.I 26"	282.000 TON	_____	_____	_____	_____
0520	417	66810 DAMP-PROOFING	6.000 SY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000113031B67 Oversight/State Project No.: 0743-087-681,B667

Order No.: H74

Federal Project No.: BROS-087-5(048)

Contractor: _____

SECTION: 0001 REGULAR ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0530	413	67900 DISM.& REM. EX. STR. DISM. & REM. EXIST. STR. NO. 6085, TY. B	LUMP SUM	LUMP SUM			
0540	405	68132 PRESTRESSED CONCRETE BOX BEAM 3' X 2'-3" X(+65' - 70')	5.000 EA				
0550	405	68132 PRESTRESSED CONCRETE BOX BEAM 4' X 2'-3" X(+65' - 70')	2.000 EA				
0560	413	68476 ENV.& WORK. PROTECTION ENV. & WORKER PROTECTION STR. # 6085, TYPE B	LUMP SUM	LUMP SUM			
0570	411	68490 DISPOSAL OF MATERIAL DISPOSAL OF MATERIAL, STR. NO. 6085, TYPE B	LUMP SUM	LUMP SUM			
Section: 0001				Total:			
				Total Bid:			