

Schedule of Items

Proposal ID: CM823LMA121437 Oversight/State Project No.: LM8A-968-F23,N501

Order No.: 801

Federal Project No.: PM08(465)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	ATTD	10497 PAVEMENT CRACK SEAL - TYPE A	79,080.000 LB	_____	_____	_____	_____
0020	ATTD	10505 PAVEMENT FLEXIBLE MICROSURFACING - TYPE B	396.000 TON	_____	_____	_____	_____
0030	ATTD	10505 PAVEMENT FLEXIBLE MICROSURFACING - TYPE C	5,966.420 TON	_____	_____	_____	_____
0040	ATTD	15309 PAVEMENT LIQUID ASPHALT COATING (PAVEMENT MARKER GROOVE)	310.000 SY	_____	_____	_____	_____
0050	ATTD	16144 LATEX MOD. EMULSION TREAT. TYPE B	307.300 TON	_____	_____	_____	_____
0060	ATTD	16145 LATEX MOD. EMULSION TREAT. TYPE C	813.670 TON	_____	_____	_____	_____
0070	ATTD	24262 PORTABLE TEMPORARY RUMBLE STRIP ARRAY	54.000 DAY	_____	_____	_____	_____
0080	ATTD	24265 MAINTENANCE OF TRAFFIC MOT FOR UPC 121437	LUMP SUM	LUMP SUM	_____	_____	_____
0090	ATTD	24265 MAINTENANCE OF TRAFFIC MOT FOR UPC 121438	LUMP SUM	LUMP SUM	_____	_____	_____
0100	ATTD	24265 MAINTENANCE OF TRAFFIC MOT FOR UPC 121439	LUMP SUM	LUMP SUM	_____	_____	_____
0110	512	24282 FLAGGER SERVICE	2,735.000 HR	_____	_____	_____	_____
0120	704	54020 TYPE A PVMT LINE MRKG 4"	221,100.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: CM823LMA121437 Oversight/State Project No.: LM8A-968-F23,N501

Order No.: 801

Federal Project No.: PM08(465)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0130	704	54022 TYPE A PVMT LINE MRKG 6"	265,720.000 LF	_____	_____	_____	_____
0140	704	54043 TYPE B CLASS II PAVE. LINE MARKING 4"	800.000 LF	_____	_____	_____	_____
0150	704	54045 TYPE B CLASS II PAVE. LINE MARKING 8"	200.000 LF	_____	_____	_____	_____
0160	704	54048 TYPE B CLASS II PAVE. LINE MARKING 24"	2,525.000 LF	_____	_____	_____	_____
0170	512	54106 ERADICATE EXIST. NONLINEAR PVMT MRKG	5,420.000 SF	_____	_____	_____	_____
0180	ATTD	54219 INLAID PAVEMENT MARKER ASPHALT	800.000 EA	_____	_____	_____	_____
0190	512	54428 TEMP. PVMT MRKG, TY. A, 4"	221,100.000 LF	_____	_____	_____	_____
0200	512	54430 TEMP. PVMT MRKG, TY. A, 6"	266,640.000 LF	_____	_____	_____	_____
0210	512	54436 TEMP. PVMT MRKG, TY. A, 12"	1,125.000 LF	_____	_____	_____	_____
0220	512	54457 TEMP. PVMT SYMBOL MRKG SINGLE TURN ARROW TY. A	120.000 EA	_____	_____	_____	_____
0230	704	54575 PVMT SYMB MRKG SGL TURN ARROW TY B, CL II	135.000 EA	_____	_____	_____	_____
Section: 0001				Total:		_____	
				Total Bid:		_____	