

Schedule of Items

Proposal ID: C0000111306C01

Oversight/State Project No.: 6131-165-659

Order No.: H78

Federal Project No.: STP-5165(004)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS ROADWAY

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	513	00100 MOBILIZATION	LUMP SUM	LUMP SUM			
0020	301	00110 CLEARING AND GRUBBING	LUMP SUM	LUMP SUM			
0030	303	00120 REGULAR EXCAVATION	2,405.000 CY				
0040	305	00140 BORROW EXCAVATION	3,622.000 CY				
0050	ATTD	00504 BEDDING MATL. FINE AGGR. OR AGGR. NO. 8	81.000 TON				
0060	ATTD	00506 BEDDING MATL. AGGR. NO. (GRADE A SAND)	65.000 TON				
0070	302 504	00525 CONCRETE CLASS A3 MISC.	13.200 CY				
0080	ATTD	00598 UNDERDRAIN MEDIA PIPE DRAINS (4")	120.000 LF				
0090	302	01150 15" PIPE	50.000 LF				
0100	302	01156 STORM SEWER PIPE 15"	2,793.000 LF				
0110	302	01186 STORM SEWER PIPE 18"	318.000 LF				
0120	302	01246 STORM SEWER PIPE 24"	1,077.000 LF				
0130	302	01302 30" CONC. PIPE	41.000 LF				
0140	302	06817 DROP INLET DI-3B,L=4'	7.000 EA				

Schedule of Items

Proposal ID: C0000111306C01

Oversight/State Project No.: 6131-165-659

Order No.: H78

Federal Project No.: STP-5165(004)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS ROADWAY

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0150	302	06818 DROP INLET DI-3B,L=6'	11.000 EA	_____	_____	_____	_____
0160	302	06819 DROP INLET DI-3B,L=8'	1.000 EA	_____	_____	_____	_____
0170	302	06820 DROP INLET DI-3B,L=10'	1.000 EA	_____	_____	_____	_____
0180	302	06835 DROP INLET DI-3C,L=6'	2.000 EA	_____	_____	_____	_____
0190	302	06837 DROP INLET DI-3C,L=10'	1.000 EA	_____	_____	_____	_____
0200	302	07508 DROP INLET DI-7	1.000 EA	_____	_____	_____	_____
0210	302	09056 MANHOLE MH-1 OR 2	27.800 LF	_____	_____	_____	_____
0220	302	09057 FRAME & COVER MH-1	5.000 EA	_____	_____	_____	_____
0230	414	09150 EROSION CONTROL STONE CLASS I, EC-1	36.000 TON	_____	_____	_____	_____
0240	610	09155 GABIONS	40.000 CY	_____	_____	_____	_____
0250	308	10128 AGGR. BASE MATL. TY. I NO. 21B	3,026.000 TON	_____	_____	_____	_____
0260	315	10611 ASPHALT CONCRETE TY. IM- 19.0D	2,251.000 TON	_____	_____	_____	_____
0270	515	10628 FLEXIBLE PAVEMENT PLANING 0" - 2"	1,036.000 SY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000111306C01

Oversight/State Project No.: 6131-165-659

Order No.: H78

Federal Project No.: STP-5165(004)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS ROADWAY

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0280	515	10629 FLEXIBLE PAVEMENT PLANING ABOVE 2" - 4"	8,269.000 SY	_____	_____	_____	_____
0290	315	10636 ASPHALT CONC.TY. SM-9.5D	2,017.000 TON	_____	_____	_____	_____
0300	315	10642 ASPHALT CONCRETE TY. BM- 25.0A	871.000 TON	_____	_____	_____	_____
0310	316.04	11070 SAW-CUT ASPH CONC FULL DEPTH	8,332.000 LF	_____	_____	_____	_____
0320	502	12020 STD. CURB CG-2	713.000 LF	_____	_____	_____	_____
0330	502	12022 RADIAL CURB CG-2	149.000 LF	_____	_____	_____	_____
0340	502	12600 STD. COMB. CURB & GUTTER CG-6	2,948.000 LF	_____	_____	_____	_____
0350	502	12610 RADIAL COMB. CURB & GUTTER CG-6	1,383.000 LF	_____	_____	_____	_____
0360	502	12940 ENTRANCE GUTTER CG-9D	225.000 SY	_____	_____	_____	_____
0370	504	13108 CG-12 DETECTABLE WARNING SURFACE	41.000 SY	_____	_____	_____	_____
0380	503	13212 R/W MONUMENT RM-2	18.000 EA	_____	_____	_____	_____
0390	504	13220 HYDRAULIC CEMENT CONC. SIDEWALK 4"	450.000 SY	_____	_____	_____	_____
0400	504	13232 GEOTEXTILE DRAINAGE FABRIC	40.000 SY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000111306C01

Oversight/State Project No.: 6131-165-659

Order No.: H78

Federal Project No.: STP-5165(004)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS ROADWAY

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0410	ATTD	14260 CRUSHER RUN AGGREGATE NO. 25 OR 26	118.000 TON	_____	_____	_____	_____
0420	502	21020 MEDIAN STRIP MS-1	158.000 SY	_____	_____	_____	_____
0430	502	21021 MEDIAN STRIP MS-2	2,578.000 SY	_____	_____	_____	_____
0440	511	24100 ALLAYING DUST	300.000 HR	_____	_____	_____	_____
0450	512	24160 TEMPORARY (CONSTRUCTION) SIGN	434.000 SF	_____	_____	_____	_____
0460	512	24278 GROUP 2 CHANNELIZING DEVICES	19,290.000 DAY	_____	_____	_____	_____
0470	512	24279 PORTABLE CHANGEABLE MESSAGE SIGN	2,016.000 HR	_____	_____	_____	_____
0480	512	24282 FLAGGER SERVICE	912.000 HR	_____	_____	_____	_____
0490	508	24430 DEMOLITION OF PAVEMENT FLEXIBLE	4,650.000 SY	_____	_____	_____	_____
0500	510	24832 ADJUST EXIST. MANHOLE UTILITIES	6.000 EA	_____	_____	_____	_____
0510	514	25505 FIELD OFFICE TY.I	13.000 MO	_____	_____	_____	_____
0520	602	27024 TOPSOIL (CLASS A 3" DEPTH)	1.750 ACRE	_____	_____	_____	_____
0530	603	27101 TEMPORARY SEED	175.000 LB	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000111306C01

Oversight/State Project No.: 6131-165-659

Order No.: H78

Federal Project No.: STP-5165(004)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS ROADWAY

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0540	603	27102 REGULAR SEED	104.000 LB	_____	_____	_____	_____
0550	603	27103 OVERSEEDING	83.000 LB	_____	_____	_____	_____
0560	603	27113 HYDRAULIC EROSION CONTROL PRODUCT TYPE 4	13,795.000 SY	_____	_____	_____	_____
0570	603	27230 FERTILIZER NITROGEN - N	100.000 LB	_____	_____	_____	_____
0580	603	27231 FERTILIZER PHOSPHOROUS - P	148.000 LB	_____	_____	_____	_____
0590	603	27232 FERTILIZER POTASSIUM - K	74.000 LB	_____	_____	_____	_____
0600	603	27250 LIME	4.820 TON	_____	_____	_____	_____
0610	606	27319 ROLLED EROSION CTRL PRODUCT EC-2 TYPE 2	62.000 SY	_____	_____	_____	_____
0620	606	27325 ROLLED EROSION CTRL PRODUCT EC-3 TYPE 1	272.000 SY	_____	_____	_____	_____
0630	606	27327 ROLLED EROSION CTRL PRODUCT EC-3 TYPE 3	108.000 SY	_____	_____	_____	_____
0640	303	27415 CHECK DAM ROCK TY. II	14.000 EA	_____	_____	_____	_____
0650	303	27430 SILTATION CONTROL EXCAVATION	1,094.000 CY	_____	_____	_____	_____
0660	303	27451 INLET PROTECTION TYPE A	1.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000111306C01

Oversight/State Project No.: 6131-165-659

Order No.: H78

Federal Project No.: STP-5165(004)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS ROADWAY

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0670	303	27461 INLET PROTECTION TYPE B	25.000 EA	_____	_____	_____	_____
0680	303	27504 TEMP. SILT FENCE TYPE B	367.000 LF	_____	_____	_____	_____
0690	303	27505 TEMP. SILT FENCE TYPE A	2,840.000 LF	_____	_____	_____	_____
0700	303	27545 STORM WATER MANAGEMENT BASIN EXCAVATION	565.000 CY	_____	_____	_____	_____
0710	302	27550 STORM WATER MANAGEMENT DRAINAGE STR. SWM-1	8.200 LF	_____	_____	_____	_____
0720	ATTD	27553 PERMANENT SWM FACILITY AS-BUILT DOCUMENTATION .	LUMP SUM	LUMP SUM	_____	_____	_____
0730	303	27580 TEMP. SEDIMENT BASIN EXCAVATION	209.000 CY	_____	_____	_____	_____
0740	605	28805 BED PREPARATION	276.000 UNIT	_____	_____	_____	_____
0750	605	28810 MULCHING	135.000 CY	_____	_____	_____	_____
0760	605	38900 PLANT OR TREE PER./GROUND COVER - ACHILLEA M. 'SALMON BEAUTY' / YARROW - SIZE 1 GAL.	174.000 EA	_____	_____	_____	_____
0770	605	38900 PLANT OR TREE PER./GROUND COVER - ASCLEPIAS T. / BUTTERFLY MILKWEED - SIZE 1 GAL.	175.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000111306C01

Oversight/State Project No.: 6131-165-659

Order No.: H78

Federal Project No.: STP-5165(004)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS ROADWAY

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0780	605	38900 PLANT OR TREE PER./GROUND COVER - ECHINACEA P. CONEFLOWER - SIZE 1 GAL.	196.000 EA	_____	_____	_____	_____
0790	605	38900 PLANT OR TREE PER./GROUND COVER - HEUCHERA V. / HAIRY ALUM ROOT - SIZE 1 GAL.	1,869.000 EA	_____	_____	_____	_____
0800	605	38900 PLANT OR TREE PER./GROUND COVER - HYLOTELEPHIUM 'H. / STONECROP- SIZE 1 GAL.	1,360.000 EA	_____	_____	_____	_____
0810	605	38900 PLANT OR TREE PER./GROUND COVER - JUNIPER HOR. 'BAR HARBOR'- SIZE 1 GAL.	1,469.000 EA	_____	_____	_____	_____
0820	605	38900 PLANT OR TREE PER./GROUND COVER - LEUCANTHEMUM X SUP. 'BECKY' / SHASTA DAISY - SIZE 1 GAL.	174.000 EA	_____	_____	_____	_____
0830	605	38900 PLANT OR TREE PER./GROUND COVER - LIASTRIS SPICATA / B. STAR - SIZE 1 GAL.	483.000 EA	_____	_____	_____	_____
0840	605	38900 PLANT OR TREE PER./GROUND COVER - RUDBECKIA F. / B-EYED SUSAN - SIZE 1 GAL.	241.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000111306C01

Oversight/State Project No.: 6131-165-659

Order No.: H78

Federal Project No.: STP-5165(004)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS ROADWAY

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0850	605	38900 PLANT OR TREE PER./GROUND COVER - SYMPHYOTRICHUM O. 'OCT. SKIES' / AROMATIC ASTER - SIZE 1 GAL.	1,482.000 EA	_____	_____	_____	_____
0860	ATTD	38951 LANDSCAPE FILTERING FACILITY (SWM-10)	120.000 SY	_____	_____	_____	_____
0870	605	39001 TREE CARPINUS CAROLINIANA / AMERICAN HORNBEAM - SIZE 2" CAL.	5.000 EA	_____	_____	_____	_____
0880	605	39001 TREE CERCIS CANADENSIS / EASTERN REDBUD - SIZE 2" CAL.	6.000 EA	_____	_____	_____	_____
0890	605	39001 TREE CORNUS FLORIDA / FLOWERING DOGWOOD - SIZE 2" CAL.	4.000 EA	_____	_____	_____	_____
0900	605	39001 TREE QUERCUS COCCINEA / SCARLET OAK - SIZE 3" CAL.	9.000 EA	_____	_____	_____	_____
0910	605	39001 TREE QUERCUS RUBRA / RED OAK - SIZE 3" CAL.	10.000 EA	_____	_____	_____	_____
0920	605	39002 SHRUB CLETHRA ALNIFOLIA 'RUBY SPICE' / SWEET PEPPERBUSH - SIZE 24" HT.	56.000 EA	_____	_____	_____	_____
0930	605	39002 SHRUB CORNUS SERICEA 'FARROW' / ARTIC FIRE RED TWIG DOGWOOD - SIZE 36-48" HT.	39.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000111306C01

Oversight/State Project No.: 6131-165-659

Order No.: H78

Federal Project No.: STP-5165(004)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS ROADWAY

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0940	605	39002 SHRUB ITEA VIRGINICA / VIRGINIA SWEETSPIRE - SIZE 24-36" HT.	38.000 EA	_____	_____	_____	_____
0950	605	39003 HERB PENNISETUM ALOPECUROIDES 'HAMELN' / FOUNTAIN GRASS - SIZE 1 GAL.	505.000 EA	_____	_____	_____	_____
0960	605	39003 HERB SCHIZACHYRIUM SCOPARIUM 'THE BLUES' / THE BLUES LITTLE BLUESTEM - SIZE 1 GAL.	145.000 EA	_____	_____	_____	_____
0970	520	40003 1" WATER SERVICE LINE	100.000 LF	_____	_____	_____	_____
0980	520	40061 6" DI WATER MAIN	15.000 LF	_____	_____	_____	_____
0990	520	40081 8" DI WATER MAIN	315.000 LF	_____	_____	_____	_____
1000	520	40121 12" DI WATER MAIN	909.000 LF	_____	_____	_____	_____
1010	520	41006 6" GATE VALVE & BOX	1.000 EA	_____	_____	_____	_____
1020	520	41008 8" GATE VALVE & BOX	3.000 EA	_____	_____	_____	_____
1030	510	41104 ADJUST EXIST. VALVE BOX	6.000 EA	_____	_____	_____	_____
1040	510	41827 ADJUST EXIST. FIRE HYDRANT	2.000 EA	_____	_____	_____	_____
1050	510	41976 RELOC. EXIST. WATER METER & BOX	1.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000111306C01

Oversight/State Project No.: 6131-165-659

Order No.: H78

Federal Project No.: STP-5165(004)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS ROADWAY

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1060	510	41977 ADJUST EXIST. WATER METER BOX	4.000 EA	_____	_____	_____	_____
1070	ATTD	42000 SEWER PIPE (2" SANITARY FORCE MAIN)	63.000 LF	_____	_____	_____	_____
1080	520	45562 16" STEEL ENCASE. PIPE	70.000 LF	_____	_____	_____	_____
1090	509	45640 FLOWABLE BACKFILL UTILITY	55.000 CY	_____	_____	_____	_____
1100	701	50108 SIGN PANEL	105.000 SF	_____	_____	_____	_____
1110	700	50300 REMOVE EXISTING 1 POST SIGN STRUCTURE	7.000 EA	_____	_____	_____	_____
1120	700	50340 RELOCATE EXISTING 1 POST GROUND MOUNTED SIGN PANEL	22.000 EA	_____	_____	_____	_____
1130	700	50342 RELOCATE EXISTING 2 POST GROUND MOUNTED SIGN PANEL	7.000 EA	_____	_____	_____	_____
1140	700	50430 SIGN POST STP-1, 2", 14 GAUGE	255.000 LF	_____	_____	_____	_____
1150	700	50485 CONCRETE SIGN FOUNDATION STP-1, TYPE A	53.000 EA	_____	_____	_____	_____
1160	700	51246 CONCRETE FOUND. CF-2	1.000 EA	_____	_____	_____	_____
1170	704	54032 TYPE B CLASS I PVMT LINE MRKG 4"	5,070.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000111306C01

Oversight/State Project No.: 6131-165-659

Order No.: H78

Federal Project No.: STP-5165(004)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS ROADWAY

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1180	704	54034 TYPE B CLASS I PVMT LINE MRKG 6"	404.000 LF	_____	_____	_____	_____
1190	704	54037 TYPE B CLASS I PVMT LINE MRKG 8"	378.000 LF	_____	_____	_____	_____
1200	704	54048 TYPE B CLASS II PAVE. LINE MARKING 24"	342.000 LF	_____	_____	_____	_____
1210	512	54105 ERADICATE EXIST. LINEAR PVMT MARKING	5,600.000 LF	_____	_____	_____	_____
1220	704	54393 PVMT MSG. MARK. "ONLY" TY B, CL II, 6'	2.000 EA	_____	_____	_____	_____
1230	512	54542 TYPE D, CLASS III TEMP. PVMT MRKG 4"	15,500.000 LF	_____	_____	_____	_____
1240	512	54548 TYPE D, CLASS III TEMP. PVMT MRKG 24"	100.000 LF	_____	_____	_____	_____
1250	704	54575 PVMT SYMB MRKG SGL TURN ARROW TY B, CL II	7.000 EA	_____	_____	_____	_____
1260	700	55080 8 CONDUCTOR CABLE	9,815.000 LF	_____	_____	_____	_____
1270	700	55100 10 CONDUCTOR CABLE	1,710.000 LF	_____	_____	_____	_____
1280	700	55126 CONDUCTOR CABLE, NO. 8 EGC	2,637.000 LF	_____	_____	_____	_____
1290	700	55140 CONCRETE FOUNDATION LF-1 TY. A	29.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000111306C01

Oversight/State Project No.: 6131-165-659

Order No.: H78

Federal Project No.: STP-5165(004)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS ROADWAY

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1300	700	55188 LIGHTING POLE LP-2 TYPE D	9.000 EA	_____	_____	_____	_____
1310	700	55343 ELECT. SERVICE SE-6	1.000 EA	_____	_____	_____	_____
1320	705	55352 CONTROL CENTER CCW-1 TYPE C	1.000 EA	_____	_____	_____	_____
1330	700	55586 JUNCTION BOX JB-S1	31.000 EA	_____	_____	_____	_____
1340	700	56021 1" PVC CONDUIT	245.000 LF	_____	_____	_____	_____
1350	700	56050 BORED CONDUIT 2"	60.000 LF	_____	_____	_____	_____
1360	700	56053 2" PVC CONDUIT	2,539.000 LF	_____	_____	_____	_____
1370	700	56200 TRENCH EXCAVATION ECI-1	2,834.000 LF	_____	_____	_____	_____
1380	ATTD	59000 LIGHTING #8 WIRE TAPS	68.000 EA	_____	_____	_____	_____
1390	ATTD	59000 LIGHTING 15' DECORATIVE ALUM. PAINTED LIGHTING POST	20.000 EA	_____	_____	_____	_____
1400	ATTD	59000 LIGHTING 20' ALUMINUM ARM FOR ROADWAY LUMINAIRE	1.000 EA	_____	_____	_____	_____
1410	ATTD	59000 LIGHTING 4' ALUM. ARM FOR POLE	10.000 EA	_____	_____	_____	_____
1420	ATTD	59000 LIGHTING 8' ALUMINUM ARM FOR ROADWAY LUMINAIRE	3.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000111306C01

Oversight/State Project No.: 6131-165-659

Order No.: H78

Federal Project No.: STP-5165(004)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS ROADWAY

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1430	ATTD	59000 LIGHTING POST TOP DECORATIVE PEDESTRIAN LUMINAIRE TYPE 2 DISTRIBUTION, 45 WATT	20.000 EA	_____	_____	_____	_____
1440	ATTD	59000 LIGHTING ROAD TYPE LUMINAIRE, TYPE 3 DISTRIBUTION	14.000 EA	_____	_____	_____	_____
1450	516	70200 CLEARING PARCEL NO. 001 - D1	LUMP SUM	LUMP SUM	_____	_____	_____
1460	516	70200 CLEARING PARCEL NO. 003 - D900	LUMP SUM	LUMP SUM	_____	_____	_____
1470	516	70200 CLEARING PARCEL NO. 006 - D901	LUMP SUM	LUMP SUM	_____	_____	_____
1480	516	70200 CLEARING PARCEL NO. 007- D902	LUMP SUM	LUMP SUM	_____	_____	_____
1490	516	70200 CLEARING PARCEL NO. 009 - D903, D2, D3	LUMP SUM	LUMP SUM	_____	_____	_____
1500	516	70200 CLEARING PARCEL NO. 011 - D4	LUMP SUM	LUMP SUM	_____	_____	_____
1510	516	70200 CLEARING PARCEL NO. 012- D5, D6, D7	LUMP SUM	LUMP SUM	_____	_____	_____
Section: 0001				Total:	_____	_____	_____
				Total Bid:	_____	_____	_____