

Schedule of Items

Proposal ID: C0000111728C01      Oversight/State Project No.: 0029-030-829, C501  
 Order No.: H75      Federal Project No.: HSIP-5B01(298)

Contractor: \_\_\_\_\_

SECTION: 0001      ROADWAY ITEMS

Cat Alt Set ID:      Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	513	00100 MOBILIZATION	LUMP SUM	LUMP SUM			
0020	517	00101 CONSTRUCTION SURVEYING CONSTRUCTION	LUMP SUM	LUMP SUM			
0030	301	00110 CLEARING AND GRUBBING	LUMP SUM	LUMP SUM			
0040	303	00120 REGULAR EXCAVATION	2,333.000 CY				
0050	305	00140 BORROW EXCAVATION	8.000 CY				
0060	302 504	00525 CONCRETE CLASS A3 MISC.	6.000 CY				
0070	509	00529 FLOWABLE BACKFILL	3.000 CY				
0080	302 406	00540 REINF. STEEL	644.000 LB				
0090	302	00571 ENDWALL PIPE GRATE EW-11 TYPE I	55.000 LF				
0100	501	00588 UNDERDRAIN UD-4	1,250.000 LF				
0110	501	00595 OUTLET PIPE	66.000 LF				
0120	302	00596 ENDWALL EW-12	4.000 EA				
0130	302	01156 STORM SEWER PIPE 15"	156.000 LF				
0140	302	06150 15" END SECTION ES-1 OR 2	2.000 EA				

Schedule of Items

Proposal ID: C0000111728C01      Oversight/State Project No.: 0029-030-829, C501  
 Order No.: H75      Federal Project No.: HSIP-5B01(298)

Contractor: \_\_\_\_\_

SECTION: 0001      ROADWAY ITEMS

Cat Alt Set ID:      Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0150	414	09148 EROSION CONTROL STONE CLASS A1 EC-1	4.000 TON	_____	_____	_____	_____
0160	414	09150 EROSION CONTROL STONE CLASS I, EC-1	5.000 TON	_____	_____	_____	_____
0170	305	10068 AGGR. MATL. NO. 25 OR 26	18.000 TON	_____	_____	_____	_____
0180	308	10128 AGGR. BASE MATL. TY. I NO. 21B	1,250.000 TON	_____	_____	_____	_____
0190	515	10628 FLEXIBLE PAVEMENT PLANING 0" - 2"	3,295.000 SY	_____	_____	_____	_____
0200	315	10636 ASPHALT CONC.TY. SM-9.5D	459.000 TON	_____	_____	_____	_____
0210	315	10642 ASPHALT CONCRETE TY. BM-25.0A	750.000 TON	_____	_____	_____	_____
0220	315	11070 SAW-CUT ASPH CONC SAWCUT	1,638.000 LF	_____	_____	_____	_____
0230	502	12030 STD. CURB CG-3	370.000 LF	_____	_____	_____	_____
0240	502	12032 RADIAL CURB CG-3	23.000 LF	_____	_____	_____	_____
0250	502	12700 STD. COMB. CURB & GUTTER CG-7	105.000 LF	_____	_____	_____	_____
0260	502	12710 RADIAL COMB. CURB & GUTTER CG-7	4.000 LF	_____	_____	_____	_____
0270	507	23560 TEMP. SAFETY FENCE 4'	180.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000111728C01      Oversight/State Project No.: 0029-030-829, C501  
 Order No.: H75      Federal Project No.: HSIP-5B01(298)

Contractor: \_\_\_\_\_

SECTION: 0001      ROADWAY ITEMS

Cat Alt Set ID:      Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0280	511	24100 ALLAYING DUST	30.000 HR	_____	_____	_____	_____
0290	512	24160 TEMPORARY (CONSTRUCTION) SIGN	1,201.000 SF	_____	_____	_____	_____
0300	512	24272 TRUCK MOUNTED ATTENUATOR	2,300.000 HR	_____	_____	_____	_____
0310	512	24278 GROUP 2 CHANNELIZING DEVICES	12,570.000 DAY	_____	_____	_____	_____
0320	512	24279 PORTABLE CHANGEABLE MESSAGE SIGN	1,008.000 HR	_____	_____	_____	_____
0330	512	24281 ELECTRONIC ARROW BOARD	2,300.000 HR	_____	_____	_____	_____
0340	512	24282 FLAGGER SERVICE	275.000 HR	_____	_____	_____	_____
0350	508	24410 DEMOLITION OF PAVEMENT COMBINATION	594.000 SY	_____	_____	_____	_____
0360	ATTD	24501 REMOVE EXIST. STORM OR SANITARY SEWER PIPE	54.000 LF	_____	_____	_____	_____
0370	ATTD	24502 REMOVE EXIST. FLARED END SECTION	2.000 EA	_____	_____	_____	_____
0380	ATTD	24503 REMOVE EXIST. TRAFFIC SIGNAL	LUMP SUM	LUMP SUM	_____	_____	_____
0390	505	24600 REMOVE EXISTING GUARDRAIL	341.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000111728C01

Oversight/State Project No.: 0029-030-829, C501

Order No.: H75

Federal Project No.: HSIP-5B01(298)

Contractor: \_\_\_\_\_

SECTION: 0001 ROADWAY ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0400	ATTD	24803 REMOVE EXIST. ENDWALL (15")	2.000 EA	_____	_____	_____	_____
0410	514	25505 FIELD OFFICE TY.I	12.000 MO	_____	_____	_____	_____
0420	602	27022 TOPSOIL CLASS B 2"	1.200 ACRE	_____	_____	_____	_____
0430	603	27101 TEMPORARY SEED	121.000 LB	_____	_____	_____	_____
0440	603	27102 REGULAR SEED	183.000 LB	_____	_____	_____	_____
0450	603	27103 OVERSEEDING	146.000 LB	_____	_____	_____	_____
0460	603	27110 HYDRAULIC EROSION CONTROL PRODUCT TYPE 1	7,321.000 SY	_____	_____	_____	_____
0470	603	27112 HYDRAULIC EROSION CONTROL PRODUCT TYPE 3	5,857.000 SY	_____	_____	_____	_____
0480	603	27230 FERTILIZER NITROGEN - N	116.000 LB	_____	_____	_____	_____
0490	603	27231 FERTILIZER PHOSPHOROUS - P	114.000 LB	_____	_____	_____	_____
0500	603	27232 FERTILIZER POTASSIUM - K	57.000 LB	_____	_____	_____	_____
0510	603	27250 LIME	5.500 TON	_____	_____	_____	_____
0520	606	27318 ROLLED EROSION CTRL PRODUCT EC-2 TYPE 1	737.000 SY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000111728C01      Oversight/State Project No.: 0029-030-829, C501  
 Order No.: H75      Federal Project No.: HSIP-5B01(298)

Contractor: \_\_\_\_\_

SECTION: 0001      ROADWAY ITEMS

Cat Alt Set ID:      Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0530	303	27415 CHECK DAM ROCK TY. II	26.000 EA	_____	_____	_____	_____
0540	303	27430 SILTATION CONTROL EXCAVATION	179.000 CY	_____	_____	_____	_____
0550	303	27505 TEMP. SILT FENCE TYPE A	1,004.000 LF	_____	_____	_____	_____
0560	701	50108 SIGN PANEL	125.000 SF	_____	_____	_____	_____
0570	700	50340 RELOCATE EXISTING 1 POST GROUND MOUNTED SIGN PANEL	11.000 EA	_____	_____	_____	_____
0580	700	50436 SIGN POST STP-1, 2 1/2", 12 GAUGE	91.000 LF	_____	_____	_____	_____
0590	700	50485 CONCRETE SIGN FOUNDATION STP-1, TYPE A	7.000 EA	_____	_____	_____	_____
0600	700	51170 ELECTRICAL SERVICE SE-5	1.000 EA	_____	_____	_____	_____
0610	703	51185 TRAFFIC SIGNAL HEAD SECTION 12" HVS BACKPLATE	33.000 EA	_____	_____	_____	_____
0620	700	51238 CONCRETE FOUNDATION SIGNAL POLE PF-8	24.000 CY	_____	_____	_____	_____
0630	700	51243 CONC FOUNDATION CF-5	1.000 EA	_____	_____	_____	_____
0640	700	51480 SIGNAL MAST ARM POLE MP-3, TYPE E1	2.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000111728C01      Oversight/State Project No.: 0029-030-829, C501  
 Order No.: H75      Federal Project No.: HSIP-5B01(298)

Contractor: \_\_\_\_\_

SECTION: 0001      ROADWAY ITEMS

Cat Alt Set ID:      Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0650	700	51482 SIGNAL MAST ARM POLE MP-3, TYPE F	1.000 EA	_____	_____	_____	_____
0660	700	51487 MAST ARM 49'	2.000 EA	_____	_____	_____	_____
0670	700	51490 MAST ARM 70'	1.000 EA	_____	_____	_____	_____
0680	700	51491 MAST ARM 75' CASE 1 LOADING	1.000 EA	_____	_____	_____	_____
0690	700	51598 8/3 CONDUCTOR CABLE	30.000 LF	_____	_____	_____	_____
0700	700	51607 14/7 CONDUCTOR CABLE	1,610.000 LF	_____	_____	_____	_____
0710	ATTD	51614 CONDUCTOR CABLE RELOCATE / REUSE EXISTING CONDUCTOR CABLE	50.000 LF	_____	_____	_____	_____
0720	700	51721 CAT 5E DIRECT BURIAL CABLE	1,030.000 LF	_____	_____	_____	_____
0730	703	51830 HANGER ASSEMBLY SM-3, ONE WAY	11.000 EA	_____	_____	_____	_____
0740	703	51934 REMOVE EXISTING FOUNDATION	1.000 EA	_____	_____	_____	_____
0750	700	51962 RELOCATE EXIST. COMM. ANTENNA & MAST	1.000 EA	_____	_____	_____	_____
0760	700	51962 RELOCATE EXIST. MULTI SENSOR DETECTION SYSTEM PROCESSOR & CCU	1.000 EA	_____	_____	_____	_____

## Schedule of Items

Proposal ID: C0000111728C01

Oversight/State Project No.: 0029-030-829, C501

Order No.: H75

Federal Project No.: HSIP-5B01(298)

Contractor: \_\_\_\_\_

SECTION: 0001

ROADWAY ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0770	700	51962 RELOCATE EXIST. VIDEO DETECTION CAMERA	4.000 EA	_____	_____	_____	_____
0780	703	51994 UNINTERRUPTIBLE POWER SUPPLY TYPE 2	1.000 EA	_____	_____	_____	_____
0790	703	51995 UNINTERRUPTIBLE POWER SUPPLY BATTERY PACK	1.000 EA	_____	_____	_____	_____
0800	700	52002 TRAFFIC SIGNALIZATION ATC CABINET-COMBINATION CONFIGURATION (16 OUTPUTS)	1.000 EA	_____	_____	_____	_____
0810	700	52002 TRAFFIC SIGNALIZATION LOCAL CONTROLLER (ATC)	1.000 EA	_____	_____	_____	_____
0820	700	52002 TRAFFIC SIGNALIZATION NEMA AUXILLARY COMMUNICATIONS CABINET	1.000 EA	_____	_____	_____	_____
0830	704	54032 TYPE B CLASS I PVMT LINE MRKG 4"	3,946.000 LF	_____	_____	_____	_____
0840	704	54042 TYPE B CLASS I PAVE. LINE MARKING 24"	101.000 LF	_____	_____	_____	_____
0850	512	54105 ERADICATE EXIST. LINEAR PVMT MARKING	69.000 LF	_____	_____	_____	_____
0860	510	54210 REMOVE EXIST. RAISED PAVEMENT MARKER	34.000 EA	_____	_____	_____	_____
0870	ATTD	54219 INLAID PAVEMENT MARKER ASPHALT	48.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000111728C01

Oversight/State Project No.: 0029-030-829, C501

Order No.: H75

Federal Project No.: HSIP-5B01(298)

Contractor: \_\_\_\_\_

SECTION: 0001 ROADWAY ITEMS

Cat Alt Set ID: \_\_\_\_\_ Cat Alt Mbr ID: \_\_\_\_\_

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0880	704	54574 PVMT SYMB MRKG SGL TURN ARROW TY B, CL I	7.000 EA	_____	_____	_____	_____
0890	704	54589 PVMT SYMB MRKG LANE REDUCTION ARROW TY B, CL I	2.000 EA	_____	_____	_____	_____
0900	700	55385 ELECTRICAL SERVICE WORK PAD	1.000 EA	_____	_____	_____	_____
0910	700	55587 JUNCTION BOX JB-S2	2.000 EA	_____	_____	_____	_____
0920	700	55588 JUNCTION BOX JB-S3	1.000 EA	_____	_____	_____	_____
0930	700	56050 BORED CONDUIT 2"	190.000 LF	_____	_____	_____	_____
0940	700	56051 BORED CONDUIT 3"	380.000 LF	_____	_____	_____	_____
0950	700	56053 2" PVC CONDUIT	245.000 LF	_____	_____	_____	_____
0960	700	56054 3" PVC CONDUIT	175.000 LF	_____	_____	_____	_____
0970	700	56200 TRENCH EXCAVATION ECI-1	190.000 LF	_____	_____	_____	_____
0980	700	56205 TEST BORE	3.000 EA	_____	_____	_____	_____
0990	803	57060 CCTV CAMERA DIGITAL	1.000 EA	_____	_____	_____	_____
1000	ATTD	57080 CCTV COMPOSITE CABLE .	295.000 LF	_____	_____	_____	_____

Section: 0001

Total: \_\_\_\_\_



**Total Bid:** \_\_\_\_\_.