

## Schedule of Items

Proposal ID: C0000115493C01

Oversight/State Project No.: 6311-071-454, C501

Order No.: H71

Federal Project No.: NONE

Contractor: \_\_\_\_\_

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	513	00100 MOBILIZATION	LUMP SUM	LUMP SUM			
0020	301	00111 CLEARING AND GRUBBING	40.000 ACRE				
0030	303	00120 REGULAR EXCAVATION	182,989.000 CY				
0040	303	00136 BORROW EXCAVATION	66,880.000 CY				
0050	ATTD	00170 SOIL Bioretention Soil Media	2,424.000 CY				
0060	303	00211 MINOR STRUCTURE EXCAV. PIPE CULVERT	92.000 CY				
0070	303	00212 MINOR STRUCTURE EXCAV. BOX CULVERT	2,366.000 CY				
0080	ATTD	00360 REINFORCED SOIL SLOPE TY. A RSS TY. A	2,106.000 SF				
0090	ATTD	00504 BEDDING MATL. FINE AGGR. OR AGGR. NO. 8	122.000 TON				
0100	ATTD	00505 BEDDING MATL. AGGR. NO. 25 OR 26	309.000 TON				
0110	ATTD	00507 BEDDING MATL. AGGR. NO. 57	567.000 TON				
0120	302	00522 CONCRETE CLASS A4 BOX CULVERT	208.000 CY				

## Schedule of Items

Proposal ID: C0000115493C01

Oversight/State Project No.: 6311-071-454, C501

Order No.: H71

Federal Project No.: NONE

Contractor: \_\_\_\_\_

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0130	302	00523 PRECAST BOX CULVERT 11-2 to 11-1 Single 8'x6' - 17' Cover	147.000 LF	_____	_____	_____	_____
0140	302	00523 PRECAST BOX CULVERT 11-9 to 11-8 Double 12'x8' - 8' Cover	108.000 LF	_____	_____	_____	_____
0150	302	00523 PRECAST BOX CULVERT 12-1 10'x8' Box Culvert Extension - 22' Cover	31.000 LF	_____	_____	_____	_____
0160	302	00523 PRECAST BOX CULVERT 4-14 to 4-13 Double 6'x4' - 2' Cover	119.000 LF	_____	_____	_____	_____
0170	302	00523 PRECAST BOX CULVERT 6-14 to 6-13 Double 8'x6' - 11' Cover	121.000 LF	_____	_____	_____	_____
0180	302	00523 PRECAST BOX CULVERT 9-4 to 9-3 Double 6'x6' - 20' Cover	159.000 LF	_____	_____	_____	_____
0190	302	00523 PRECAST BOX CULVERT 9-6 to 9-5 Single 8'x6' - 15' Cover	158.000 LF	_____	_____	_____	_____
0200	302 504	00525 CONCRETE CLASS A3 MISC.	93.000 CY	_____	_____	_____	_____
0210	302 406	00540 REINF. STEEL	15,164.000 LB	_____	_____	_____	_____
0220	501	00580 UNDERDRAIN UD-1	1,135.000 LF	_____	_____	_____	_____
0230	501	00588 UNDERDRAIN UD-4	10,783.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000115493C01

Oversight/State Project No.: 6311-071-454, C501

Order No.: H71

Federal Project No.: NONE

Contractor: \_\_\_\_\_

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0240	501	00591 CROSSDRAIN CD-2	95.000 LF	_____	_____	_____	_____
0250	501	00595 OUTLET PIPE	431.000 LF	_____	_____	_____	_____
0260	302	00596 ENDWALL EW-12	36.000 EA	_____	_____	_____	_____
0270	302	01150 15" PIPE	138.000 LF	_____	_____	_____	_____
0280	302	01156 STORM SEWER PIPE 15"	2,755.000 LF	_____	_____	_____	_____
0290	302	01180 18" PIPE	48.000 LF	_____	_____	_____	_____
0300	302	01182 18" CONC. PIPE	98.000 LF	_____	_____	_____	_____
0310	302	01186 STORM SEWER PIPE 18"	786.000 LF	_____	_____	_____	_____
0320	302	01242 24" CONC. PIPE	267.000 LF	_____	_____	_____	_____
0330	302	01246 STORM SEWER PIPE 24"	244.000 LF	_____	_____	_____	_____
0340	302	01302 30" CONC. PIPE	141.000 LF	_____	_____	_____	_____
0350	302	01366 STORM SEWER PIPE 36"	121.000 LF	_____	_____	_____	_____
0360	302	01422 42" CONC. PIPE	153.000 LF	_____	_____	_____	_____
0370	302	01602 60" CONC. PIPE	127.000 LF	_____	_____	_____	_____
0380	302	06150 15" END SECTION ES-1 OR 2	20.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000115493C01      Oversight/State Project No.: 6311-071-454, C501  
 Order No.: H71      Federal Project No.: NONE

Contractor: \_\_\_\_\_

SECTION: 0001      REGULAR BID ITEMS

Cat Alt Set ID:      Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0390	302	06180 18" END SECTION ES-1 OR 2	9.000 EA	_____	_____	_____	_____
0400	302	06181 18" END SECTION ES-1	1.000 EA	_____	_____	_____	_____
0410	302	06240 24" END SECTION ES-1 OR 2	3.000 EA	_____	_____	_____	_____
0420	302	06241 24" END SECTION ES-1	5.000 EA	_____	_____	_____	_____
0430	302	06301 30" END SECTION ES-1	2.000 EA	_____	_____	_____	_____
0440	302	07506 DROP INLET DI-5	11.000 EA	_____	_____	_____	_____
0450	302	07508 DROP INLET DI-7	2.000 EA	_____	_____	_____	_____
0460	302	09046 MANHOLE MH-1	48.000 LF	_____	_____	_____	_____
0470	302	09057 FRAME & COVER MH-1	12.000 EA	_____	_____	_____	_____
0480	414	09148 EROSION CONTROL STONE CLASS A1 EC-1	228.000 TON	_____	_____	_____	_____
0490	414	09150 EROSION CONTROL STONE CLASS I, EC-1	7,223.000 TON	_____	_____	_____	_____
0500	610	09155 GABIONS	331.000 CY	_____	_____	_____	_____
0510	303	09250 SLOPE DRAIN	36.000 EA	_____	_____	_____	_____
0520	308	10128 AGGR. BASE MATL. TY. I NO. 21B	32,217.000 TON	_____	_____	_____	_____

## Schedule of Items

Proposal ID: C0000115493C01

Oversight/State Project No.: 6311-071-454, C501

Order No.: H71

Federal Project No.: NONE

Contractor: \_\_\_\_\_

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0530	315	10611 ASPHALT CONCRETE TY. IM- 19.0D	7,187.000 TON	_____	_____	_____	_____
0540	315	10636 ASPHALT CONC.TY. SM-9.5D	6,112.000 TON	_____	_____	_____	_____
0550	315	10642 ASPHALT CONCRETE TY. BM- 25.0A	30,611.000 TON	_____	_____	_____	_____
0560	315	11070 SAW-CUT ASPH CONC 10" DEPTH	318.000 LF	_____	_____	_____	_____
0570	521	13215 MAILBOX POST, SINGLE	2.000 EA	_____	_____	_____	_____
0580	504	13232 GEOTEXTILE DRAINAGE FABRIC	3,168.000 SY	_____	_____	_____	_____
0590	505	13280 GUARDRAIL GR-MGS1	3,312.500 LF	_____	_____	_____	_____
0600	505	13282 GUARDRAIL GR-MGS1, 9' POST	1,225.000 LF	_____	_____	_____	_____
0610	505	13283 RADIAL GUARDRAIL GR- MGS1	244.000 LF	_____	_____	_____	_____
0620	505	13285 RADIAL GUARDRAIL GR- MGS1, 9' POST	25.000 LF	_____	_____	_____	_____
0630	505	13286 GUARDRAIL TERMINAL GR- MGS2	20.000 EA	_____	_____	_____	_____
0640	505	13288 GUARDRAIL HEIGHT TRANSITION GR-MGS4	5.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000115493C01      Oversight/State Project No.: 6311-071-454, C501  
 Order No.: H71      Federal Project No.: NONE

Contractor: \_\_\_\_\_

SECTION: 0001      REGULAR BID ITEMS

Cat Alt Set ID:      Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0650	505	13349 GUARDRAIL TERMINAL SITE PREPARATION	21.000 EA	_____	_____	_____	_____
0660	ATTD	14406 6" PIPE UNDERDRAIN	5,138.000 LF	_____	_____	_____	_____
0670	315, ATTD	15309 PAVEMENT LIQUID ASPHALT COATING (PAVEMENT MARKER GROOVE)	180.000 SY	_____	_____	_____	_____
0680	507	22501 FENCE FE-W1	121.000 LF	_____	_____	_____	_____
0690	507	22541 LINE BRACE UNIT FE-W1,FE-W2	6.000 EA	_____	_____	_____	_____
0700	507	23570 HIGH VISIBILITY FENCE, 4'	8,690.000 LF	_____	_____	_____	_____
0710	511	24100 ALLAYING DUST	550.000 HR	_____	_____	_____	_____
0720	512	24152 TYPE 3 BARRICADE 8'	20.000 EA	_____	_____	_____	_____
0730	512	24160 TEMPORARY (CONSTRUCTION) SIGN	534.000 SF	_____	_____	_____	_____
0740	512	24260 CR. RUN AGGR. NO. 25 OR 26	972.000 TON	_____	_____	_____	_____
0750	ATTD	24262 PORTABLE TEMPORARY RUMBLE STRIP ARRAY	150.000 DAY	_____	_____	_____	_____
0760	512	24278 GROUP 2 CHANNELIZING DEVICES	27,120.000 DAY	_____	_____	_____	_____
0770	512	24279 PORTABLE CHANGEABLE MESSAGE SIGN	1,008.000 HR	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000115493C01      Oversight/State Project No.: 6311-071-454, C501  
 Order No.: H71      Federal Project No.: NONE

Contractor: \_\_\_\_\_

SECTION: 0001      REGULAR BID ITEMS

Cat Alt Set ID:      Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0780	512	24282 FLAGGER SERVICE	2,640.000 HR	_____	_____	_____	_____
0790	508	24400 OBSCURING ROADWAY	24.000 UNIT	_____	_____	_____	_____
0800	508	24430 DEMOLITION OF PAVEMENT FLEXIBLE	8,646.000 SY	_____	_____	_____	_____
0810	505	24600 REMOVE EXISTING GUARDRAIL	1,887.000 LF	_____	_____	_____	_____
0820	514	25505 FIELD OFFICE TY.I	30.000 MO	_____	_____	_____	_____
0830	ATTD	25565 BASELINE PROGRESS SCHEDULE	LUMP SUM	LUMP SUM	_____	_____	_____
0840	ATTD	25567 PROGRESS SCHEDULE UPDATES	30.000 EA	_____	_____	_____	_____
0850	414	26127 DRY RIPRAP CL.I 26"	117.000 TON	_____	_____	_____	_____
0860	603	27101 TEMPORARY SEED	4,031.000 LB	_____	_____	_____	_____
0870	603	27102 REGULAR SEED	13,102.000 LB	_____	_____	_____	_____
0880	603	27103 OVERSEEDING	10,481.000 LB	_____	_____	_____	_____
0890	603	27104 LEGUME SEED	463.000 LB	_____	_____	_____	_____
0900	603	27105 LEGUME OVERSEEDING	370.000 LB	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000115493C01      Oversight/State Project No.: 6311-071-454, C501  
 Order No.: H71      Federal Project No.: NONE

Contractor: \_\_\_\_\_

SECTION: 0001      REGULAR BID ITEMS

Cat Alt Set ID:      Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0910	603	27111 HYDRAULIC EROSION CONTROL PRODUCT TYPE 2	166,254.000 SY	_____	_____	_____	_____
0920	603	27112 HYDRAULIC EROSION CONTROL PRODUCT TYPE 3	380,061.000 SY	_____	_____	_____	_____
0930	603	27230 FERTILIZER NITROGEN - N	6,192.000 LB	_____	_____	_____	_____
0940	603	27231 FERTILIZER PHOSPHOROUS - P	4,112.000 LB	_____	_____	_____	_____
0950	603	27232 FERTILIZER POTASSIUM - K	4,112.000 LB	_____	_____	_____	_____
0960	603	27250 LIME	307.000 TON	_____	_____	_____	_____
0970	604	27300 SOD	2,554.000 SY	_____	_____	_____	_____
0980	606	27319 ROLLED EROSION CTRL PRODUCT EC-2 TYPE 2	12,532.000 SY	_____	_____	_____	_____
0990	606	27321 ROLLED EROSION CTRL PRODUCT EC-2 TYPE 4	2,265.000 SY	_____	_____	_____	_____
1000	606	27325 ROLLED EROSION CTRL PRODUCT EC-3 TYPE 1	309.000 SY	_____	_____	_____	_____
1010	606	27327 ROLLED EROSION CTRL PRODUCT EC-3 TYPE 3	135.000 SY	_____	_____	_____	_____
1020	303	27410 CHECK DAM, ROCK TY. I	96.000 EA	_____	_____	_____	_____
1030	303	27415 CHECK DAM ROCK TY. II	382.000 EA	_____	_____	_____	_____



## Schedule of Items

Proposal ID: C0000115493C01

Oversight/State Project No.: 6311-071-454, C501

Order No.: H71

Federal Project No.: NONE

Contractor: \_\_\_\_\_

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1040	303	27422 DEWATERING BASIN EC-8	7.000 EA	_____	_____	_____	_____
1050	303	27430 SILTATION CONTROL EXCAVATION	13,026.000 CY	_____	_____	_____	_____
1060	303	27451 INLET PROTECTION TYPE A	15.000 EA	_____	_____	_____	_____
1070	303	27461 INLET PROTECTION TYPE B	2.000 EA	_____	_____	_____	_____
1080	303	27500 GEOTEXTILE FABRIC	556.000 SY	_____	_____	_____	_____
1090	303	27505 TEMP. SILT FENCE TYPE A	73,106.000 LF	_____	_____	_____	_____
1100	303	27545 STORM WATER MANAGEMENT BASIN EXCAVATION	5,849.000 CY	_____	_____	_____	_____
1110	302	27550 STORM WATER MANAGEMENT DRAINAGE STR. SWM-1	56.000 LF	_____	_____	_____	_____
1120	ATTD	27553 PERMANENT SWM FACILITY AS-BUILT DOCUMENTATION CONSTRUCTION RECORD DOCUMENTATION	LUMP SUM	LUMP SUM	_____	_____	_____
1130	303	27580 TEMP. SEDIMENT BASIN EXCAVATION	6,267.000 CY	_____	_____	_____	_____
1140	605	28552 WETLAND COMPENSATION SEEDING	LUMP SUM	LUMP SUM	_____	_____	_____
1150	605	39002 SHRUB BLUE JOINT REED GRASS, 1 GAL	77.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000115493C01      Oversight/State Project No.: 6311-071-454, C501  
 Order No.: H71      Federal Project No.: NONE

Contractor: \_\_\_\_\_

SECTION: 0001      REGULAR BID ITEMS

Cat Alt Set ID:      Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1160	605	39002 SHRUB SWITCHGRASS, 1 GAL	77.000 EA	_____	_____	_____	_____
1170	520	40061 6" DI WATER MAIN	5.000 LF	_____	_____	_____	_____
1180	520	40161 16" DI WATER MAIN	454.000 LF	_____	_____	_____	_____
1190	520	40406 16" BEND	4.000 EA	_____	_____	_____	_____
1200	520	40422 16" BRANCH	1.000 EA	_____	_____	_____	_____
1210	520	41006 6" GATE VALVE & BOX	1.000 EA	_____	_____	_____	_____
1220	520	41820 FIRE HYDRANT	1.000 EA	_____	_____	_____	_____
1230	701	50108 SIGN PANEL	2,041.100 SF	_____	_____	_____	_____
1240	700	50300 REMOVE EXISTING 1 POST SIGN STRUCTURE	19.000 EA	_____	_____	_____	_____
1250	700	50302 REMOVE EXISTING 2 POST SIGN STRUCTURE	7.000 EA	_____	_____	_____	_____
1260	700	50320 REMOVE EXISTING 1 POST SIGN PANEL	5.000 EA	_____	_____	_____	_____
1270	700	50419 VIA SIGN POST, W18 X 40	138.000 LF	_____	_____	_____	_____
1280	700	50421 VIA SIGN POST, W21 X 44	149.000 LF	_____	_____	_____	_____

## Schedule of Items

Proposal ID: C0000115493C01

Oversight/State Project No.: 6311-071-454, C501

Order No.: H71

Federal Project No.: NONE

Contractor: \_\_\_\_\_

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1290	700	50430 SIGN POST STP-1, 2", 14 GAUGE	355.000 LF	_____	_____	_____	_____
1300	700	50432 SIGN POST STP-1, 2 3/16", 10 GAUGE	12.000 LF	_____	_____	_____	_____
1310	700	50434 SIGN POST STP-1, 2 1/2", 10 GAUGE	70.000 LF	_____	_____	_____	_____
1320	700	50436 SIGN POST STP-1, 2 1/2", 12 GAUGE	126.000 LF	_____	_____	_____	_____
1330	700	50485 CONCRETE SIGN FOUNDATION STP-1, TYPE A	47.000 EA	_____	_____	_____	_____
1340	700	50486 CONCRETE SIGN FOUNDATION STP-1, TYPE B	6.000 EA	_____	_____	_____	_____
1350	700	50568 CONC. SIGN FOUND., SSP-VI A 4' DIA. X 12' DEPTH	8.000 EA	_____	_____	_____	_____
1360	704	54032 TYPE B CLASS I PVMT LINE MRKG 4"	31,327.000 LF	_____	_____	_____	_____
1370	704	54034 TYPE B CLASS I PVMT LINE MRKG 6"	25,050.000 LF	_____	_____	_____	_____
1380	704	54048 TYPE B CLASS II PAVE. LINE MARKING 24"	523.000 LF	_____	_____	_____	_____
1390	ATTD	54219 INLAID PAVEMENT MARKER ASPHALT	180.000 EA	_____	_____	_____	_____
1400	704	54575 PVMT SYMB MRKG SGL TURN ARROW TY B, CL II	6.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000115493C01      Oversight/State Project No.: 6311-071-454, C501  
 Order No.: H71      Federal Project No.: NONE

Contractor: \_\_\_\_\_

SECTION: 0001      REGULAR BID ITEMS

Cat Alt Set ID:      Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1410	526	70000 DEMO. OF BLDG. PARCEL 003	LUMP SUM	LUMP SUM		_____	_____
1420	526	70000 DEMO. OF BLDG. PARCEL 007	LUMP SUM	LUMP SUM		_____	_____
1430	ATTD	70112 CAT II NF ACM	1,456.000 SF		_____	_____	_____
1440	ATTD	70114 CAT I NF ACM	7.000 SF		_____	_____	_____
1450	516	70200 CLEARING PARCEL NO. PARCEL 003	LUMP SUM	LUMP SUM		_____	_____
1460	516	70200 CLEARING PARCEL NO. PARCEL 007	LUMP SUM	LUMP SUM		_____	_____
<b>Section: 0001</b>				<b>Total:</b>		_____	_____
				<b>Total Bid:</b>		_____	_____