

Schedule of Items

Proposal ID: C0000111635C01B Oversight/State Project No.: 0106-074-786,C501

Order No.: H38

Federal Project No.: STP-5A27(895)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	513	00100 MOBILIZATION	LUMP SUM	LUMP SUM			
0020	517	00101 CONSTRUCTION SURVEYING CONSTRUCTION	LUMP SUM	LUMP SUM			
0030	301	00110 CLEARING AND GRUBBING	LUMP SUM	LUMP SUM			
0040	303	00120 REGULAR EXCAVATION	2,968.000 CY				
0050	305	00140 BORROW EXCAVATION	100.000 CY				
0060	303	00211 MINOR STRUCTURE EXCAV. PIPE CULVERT	682.000 CY				
0070	ATTD	00507 BEDDING MATL. AGGR. NO. 57	12.000 TON				
0080	509	00529 FLOWABLE BACKFILL	58.860 CY				
0090	501	00588 UNDERDRAIN UD-4	2,575.000 LF				
0100	501	00595 OUTLET PIPE	175.000 LF				
0110	302	00596 ENDWALL EW-12	2.000 EA				
0120	302	01150 15" PIPE	20.000 LF				
0130	302	01156 STORM SEWER PIPE 15"	421.000 LF				
0140	302	01180 18" PIPE	36.000 LF				

Schedule of Items

Proposal ID: C0000111635C01B Oversight/State Project No.: 0106-074-786,C501

Order No.: H38

Federal Project No.: STP-5A27(895)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0150	302	01186 STORM SEWER PIPE 18"	269.000 LF	_____	_____	_____	_____
0160	302	01242 24" CONC. PIPE	22.000 LF	_____	_____	_____	_____
0170	302	01244 24" RADIAL PIPE	111.000 LF	_____	_____	_____	_____
0180	302	01246 STORM SEWER PIPE 24"	433.000 LF	_____	_____	_____	_____
0190	302	01422 42" CONC. PIPE	348.000 LF	_____	_____	_____	_____
0200	ATTD, 303	02112 DRAINAGE CULVERT INLET PROTECTION EC-6, TY. C	15.000 EA	_____	_____	_____	_____
0210	302	06181 18" END SECTION ES-1	1.000 EA	_____	_____	_____	_____
0220	302	06241 24" END SECTION ES-1	4.000 EA	_____	_____	_____	_____
0230	302	06817 DROP INLET DI-3B,L=4'	6.000 EA	_____	_____	_____	_____
0240	302	06818 DROP INLET DI-3B,L=6'	2.000 EA	_____	_____	_____	_____
0250	302	06819 DROP INLET DI-3B,L=8'	2.000 EA	_____	_____	_____	_____
0260	302	06836 DROP INLET DI-3C,L=8'	2.000 EA	_____	_____	_____	_____
0270	302	06837 DROP INLET DI-3C,L=10'	2.000 EA	_____	_____	_____	_____
0280	302	06838 DROP INLET DI-3C,L=12'	1.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000111635C01B Oversight/State Project No.: 0106-074-786,C501

Order No.: H38

Federal Project No.: STP-5A27(895)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0290	302	07206 DROP INLET DI-4C,L=8'	1.000 EA	_____	_____	_____	_____
0300	302	07506 DROP INLET DI-5	3.000 EA	_____	_____	_____	_____
0310	ATTD, 302	08990 DROP INLET SPECIAL STRUCTURE MANHOLE	1.000 EA	_____	_____	_____	_____
0320	302	09055 MANHOLE MH-2	13.000 LF	_____	_____	_____	_____
0330	302	09056 MANHOLE MH-1 OR 2	20.000 LF	_____	_____	_____	_____
0340	308	10128 AGGR. BASE MATL. TY. I NO. 21B	1,140.000 TON	_____	_____	_____	_____
0350	315	10608 ASPHALT CONCRETE TY. SM- 12.5D	562.000 TON	_____	_____	_____	_____
0360	315	10611 ASPHALT CONCRETE TY. IM- 19.0D	590.000 TON	_____	_____	_____	_____
0370	515	10628 FLEXIBLE PAVEMENT PLANING 0" - 2"	2,451.000 SY	_____	_____	_____	_____
0380	515	10629 FLEXIBLE PAVEMENT PLANING ABOVE 2" - 4"	425.000 SY	_____	_____	_____	_____
0390	315	10642 ASPHALT CONCRETE TY. BM- 25.0A	642.000 TON	_____	_____	_____	_____
0400	316	11040 CONCRETE ENTRANCE PAVE. 7"	87.000 SY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000111635C01B Oversight/State Project No.: 0106-074-786,C501

Order No.: H38

Federal Project No.: STP-5A27(895)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0410	315	11070 SAW-CUT ASPH CONC (FULL DEPTH)	2,004.000 LF	_____	_____	_____	_____
0420	502	12020 STD. CURB CG-2	237.000 LF	_____	_____	_____	_____
0430	502	12022 RADIAL CURB CG-2	365.000 LF	_____	_____	_____	_____
0440	502	12700 STD. COMB. CURB & GUTTER CG-7	428.000 LF	_____	_____	_____	_____
0450	502	12710 RADIAL COMB. CURB & GUTTER CG-7	1,077.000 LF	_____	_____	_____	_____
0460	ATTD, 502	13120 ENTRANCE GUTTER MODIFIED CG-9D	408.000 SY	_____	_____	_____	_____
0470	521	13215 MAILBOX POST, SINGLE	6.000 EA	_____	_____	_____	_____
0480	521	13216 MAILBOX POST, DOUBLE	1.000 EA	_____	_____	_____	_____
0490	ATTD	14502 REINFORCING STEEL	1,173.000 LB	_____	_____	_____	_____
0500	502	21020 MEDIAN STRIP MS-1	274.000 SY	_____	_____	_____	_____
0510	511	24100 ALLAYING DUST	80.000 HR	_____	_____	_____	_____
0520	512	24150 TYPE 3 BARRICADE 4'	8.000 EA	_____	_____	_____	_____
0530	512	24152 TYPE 3 BARRICADE 8'	12.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000111635C01B Oversight/State Project No.: 0106-074-786,C501

Order No.: H38

Federal Project No.: STP-5A27(895)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0540	512	24160 TEMPORARY (CONSTRUCTION) SIGN	1,855.000 SF	_____	_____	_____	_____
0550	512	24260 CR. RUN AGGR. NO. 25 OR 26	65.000 TON	_____	_____	_____	_____
0560	ATTD	24262 PORTABLE TEMPORARY RUMBLE STRIP ARRAY	388.000 DAY	_____	_____	_____	_____
0570	512	24278 GROUP 2 CHANNELIZING DEVICES	3,738.000 DAY	_____	_____	_____	_____
0580	512	24279 PORTABLE CHANGEABLE MESSAGE SIGN	3,696.000 HR	_____	_____	_____	_____
0590	512	24282 FLAGGER SERVICE	864.000 HR	_____	_____	_____	_____
0600	512	24288 WARNING LIGHT TY. B	11,904.000 DAY	_____	_____	_____	_____
0610	512	24290 TRAFFIC BARRIER SERVICE CONC. MB-7D PC	96.000 LF	_____	_____	_____	_____
0620	508	24430 DEMOLITION OF PAVEMENT FLEXIBLE	2,863.000 SY	_____	_____	_____	_____
0630	510	24500 REMOVE EXIST. CONC. SIGN ISLANDS	325.000 SY	_____	_____	_____	_____
0640	ATTD	25565 BASELINE PROGRESS SCHEDULE	LUMP SUM	LUMP SUM	_____	_____	_____
0650	ATTD	25567 PROGRESS SCHEDULE UPDATES	12.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000111635C01B Oversight/State Project No.: 0106-074-786,C501

Order No.: H38

Federal Project No.: STP-5A27(895)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0660	414	26117 DRY RIPRAP CL. AI	26.000 TON	_____	_____	_____	_____
0670	602	27030 TOPSOIL CLASS A, 3" DEPTH	202.000 CY	_____	_____	_____	_____
0680	603	27101 TEMPORARY SEED	120.000 LB	_____	_____	_____	_____
0690	603	27102 REGULAR SEED	323.000 LB	_____	_____	_____	_____
0700	603	27103 OVERSEEDING	258.000 LB	_____	_____	_____	_____
0710	603	27104 LEGUME SEED	10.000 LB	_____	_____	_____	_____
0720	603	27105 LEGUME OVERSEEDING	5.000 LB	_____	_____	_____	_____
0730	603	27111 HYDRAULIC EROSION CONTROL PRODUCT TYPE 2	6,050.000 SY	_____	_____	_____	_____
0740	603	27112 HYDRAULIC EROSION CONTROL PRODUCT TYPE 3	7,018.000 SY	_____	_____	_____	_____
0750	603	27230 FERTILIZER NITROGEN - N	120.000 LB	_____	_____	_____	_____
0760	603	27231 FERTILIZER PHOSPHOROUS - P	84.000 LB	_____	_____	_____	_____
0770	603	27232 FERTILIZER POTASSIUM - K	84.000 LB	_____	_____	_____	_____
0780	603	27250 LIME	6.600 TON	_____	_____	_____	_____
0790	606	27318 ROLLED EROSION CTRL PRODUCT EC-2 TYPE 1	170.000 SY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000111635C01B Oversight/State Project No.: 0106-074-786,C501

Order No.: H38

Federal Project No.: STP-5A27(895)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0800	606	27320 ROLLED EROSION CTRL PRODUCT EC-2 TYPE 3	70.000 SY	_____	_____	_____	_____
0810	303	27410 CHECK DAM, ROCK TY. I	2.000 EA	_____	_____	_____	_____
0820	303	27415 CHECK DAM ROCK TY. II	1.000 EA	_____	_____	_____	_____
0830	303	27430 SILTATION CONTROL EXCAVATION	260.000 CY	_____	_____	_____	_____
0840	303	27451 INLET PROTECTION TYPE A	4.000 EA	_____	_____	_____	_____
0850	303	27461 INLET PROTECTION TYPE B	14.000 EA	_____	_____	_____	_____
0860	303	27505 TEMP. SILT FENCE TYPE A	593.000 LF	_____	_____	_____	_____
0870	605	28805 BED PREPARATION	59.000 UNIT	_____	_____	_____	_____
0880	605	28810 MULCHING	6.000 CY	_____	_____	_____	_____
0890	605	28811 REMULCHING	4.000 CY	_____	_____	_____	_____
0900	605	28844 OVERSIZE PLANTING PIT	18.000 EA	_____	_____	_____	_____
0910	605	38952 LANDSCAPE GRASS/FORB POLLINATOR SEED MIX	0.150 ACRE	_____	_____	_____	_____
0920	605	38956 LANDSCAPE SPRING WILDFLOWER BULB MIX	59.000 UNIT	_____	_____	_____	_____
0930	605	39001 TREE AMERICAN HOLLY	5.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000111635C01B Oversight/State Project No.: 0106-074-786,C501

Order No.: H38

Federal Project No.: STP-5A27(895)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0940	605	39001 TREE FRINGE TREE	8.000 EA	_____	_____	_____	_____
0950	605	39001 TREE KOUSA DOGWOOD	5.000 EA	_____	_____	_____	_____
0960	605	39005 ORGANIC BACKFILL IMPROVED BACKFILL	180.000 CY	_____	_____	_____	_____
0970	520	40002 3/4" WATER SERVICE LINE	118.000 LF	_____	_____	_____	_____
0980	520	40003 1" WATER SERVICE LINE	105.000 LF	_____	_____	_____	_____
0990	520	40060 6" WATER MAIN	537.000 LF	_____	_____	_____	_____
1000	520	40061 6" DI WATER MAIN	28.000 LF	_____	_____	_____	_____
1010	520	40081 8" DI WATER MAIN	6.000 LF	_____	_____	_____	_____
1020	520	40120 12" WATER MAIN	228.000 LF	_____	_____	_____	_____
1030	520	40121 12" DI WATER MAIN	407.000 LF	_____	_____	_____	_____
1040	520	41006 6" GATE VALVE & BOX	4.000 EA	_____	_____	_____	_____
1050	520	41008 8" GATE VALVE & BOX	1.000 EA	_____	_____	_____	_____
1060	520	41012 12" GATE VALVE & BOX	2.000 EA	_____	_____	_____	_____
1070	520	41820 FIRE HYDRANT	1.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000111635C01B Oversight/State Project No.: 0106-074-786,C501

Order No.: H38

Federal Project No.: STP-5A27(895)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1080	520	41830 1" AIR RELEASE VALVE & BOX	1.000 EA	_____	_____	_____	_____
1090	520	41967 5/8" WATER METER BOX & YOKE	10.000 EA	_____	_____	_____	_____
1100	520	42064 6" SANITARY SERVICE LATERAL CONNECTION	258.000 LF	_____	_____	_____	_____
1110	520	42082 8" DI SANITARY SEWER PIPE	182.000 LF	_____	_____	_____	_____
1120	520	42755 SANITARY SEWER MANHOLE	30.000 LF	_____	_____	_____	_____
1130	520	42764 MANHOLE FRAME & COVER F&C-1	10.000 EA	_____	_____	_____	_____
1140	510	42765 ADJUST EXIST FRAME & COVER	2.000 EA	_____	_____	_____	_____
1150	520	42846 6" SEWER CLEANOUT	6.000 EA	_____	_____	_____	_____
1160	520	45562 16" STEEL ENCASE. PIPE	110.000 LF	_____	_____	_____	_____
1170	520	45582 24" STEEL ENCASE. PIPE	220.000 LF	_____	_____	_____	_____
1180	701	50108 SIGN PANEL	261.500 SF	_____	_____	_____	_____
1190	700	50320 REMOVE EXISTING 1 POST SIGN PANEL	2.000 EA	_____	_____	_____	_____
1200	700	50326 REMOVE EXISTING OVERHEAD SIGNAL SIGN PANEL	1.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000111635C01B Oversight/State Project No.: 0106-074-786,C501

Order No.: H38

Federal Project No.: STP-5A27(895)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1210	700	50430 SIGN POST STP-1, 2", 14 GAUGE	195.000 LF	_____	_____	_____	_____
1220	700	50434 SIGN POST STP-1, 2 1/2", 10 GAUGE	100.000 LF	_____	_____	_____	_____
1230	700	50436 SIGN POST STP-1, 2 1/2", 12 GAUGE	53.000 LF	_____	_____	_____	_____
1240	700	50485 CONCRETE SIGN FOUNDATION STP-1, TYPE A	22.000 EA	_____	_____	_____	_____
1250	700	50486 CONCRETE SIGN FOUNDATION STP-1, TYPE B	8.000 EA	_____	_____	_____	_____
1260	704	54032 TYPE B CLASS I PVMT LINE MRKG 4"	6,100.000 LF	_____	_____	_____	_____
1270	704	54037 TYPE B CLASS I PVMT LINE MRKG 8"	280.000 LF	_____	_____	_____	_____
1280	704	54048 TYPE B CLASS II PAVE. LINE MARKING 24"	85.000 LF	_____	_____	_____	_____
1290	512	54105 ERADICATE EXIST. LINEAR PVMT MARKING	8,286.000 LF	_____	_____	_____	_____
1300	512	54106 ERADICATE EXIST. NONLINEAR PVMT MRKG	575.000 SF	_____	_____	_____	_____
1310	512	54457 TEMP. PVMT SYMBOL MRKG SINGLE TURN ARROW TY. A	2.000 EA	_____	_____	_____	_____
1320	512	54466 TYPE E TEMP. PVMT MRKG 6"	225.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000111635C01B Oversight/State Project No.: 0106-074-786,C501

Order No.: H38

Federal Project No.: STP-5A27(895)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1330	704	54532 TEMP PVMT MRKG (DBL TURN (LT/THRU) ARROW TY. A)	3.000 EA	_____	_____	_____	_____
1340	512	54542 TYPE D, CLASS III TEMP. PVMT MRKG 4"	3,477.000 LF	_____	_____	_____	_____
1350	512	54544 TYPE D, CLASS III TEMP. PVMT MRKG 8"	1,814.000 LF	_____	_____	_____	_____
1360	704	54572 PVMT SYMB MRKG THRU ARROW TY B, CL II	1.000 EA	_____	_____	_____	_____
1370	704	54575 PVMT SYMB MRKG SGL TURN ARROW TY B, CL II	3.000 EA	_____	_____	_____	_____
1380	700	55080 8 CONDUCTOR CABLE	2,350.000 LF	_____	_____	_____	_____
1390	700	55126 CONDUCTOR CABLE, NO. 8 EGC	825.000 LF	_____	_____	_____	_____
1400	700	55140 CONCRETE FOUNDATION LF-1 TY. A	6.000 EA	_____	_____	_____	_____
1410	700	55188 LIGHTING POLE LP-2 TYPE D	6.000 EA	_____	_____	_____	_____
1420	700	55346 ELECT. SERVICE SE-8 TYPE A	1.000 EA	_____	_____	_____	_____
1430	705	55352 CONTROL CENTER CCW-1 TYPE C	1.000 EA	_____	_____	_____	_____
1440	700	55385 ELECTRICAL SERVICE WORK PAD	1.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000111635C01B Oversight/State Project No.: 0106-074-786,C501

Order No.: H38

Federal Project No.: STP-5A27(895)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1450	ATTD	55505 LUMINAIRE LED 150 WATTS	6.000 EA	_____	_____	_____	_____
1460	700	55587 JUNCTION BOX JB-S2	6.000 EA	_____	_____	_____	_____
1470	700	56014 ELECT. SER. GRD. ELECTRODE 10'	5.000 EA	_____	_____	_____	_____
1480	700	56053 2" PVC CONDUIT	825.000 LF	_____	_____	_____	_____
1490	700	56200 TRENCH EXCAVATION ECI-1	800.000 LF	_____	_____	_____	_____
1500	700	56202 TRENCH EXCAVATION ECI-2	50.000 LF	_____	_____	_____	_____
1510	404	60404 CONCRETE CLASS A4	4.150 CY	_____	_____	_____	_____
1520	516	70200 CLEARING PARCEL NO. 007 (D901)	LUMP SUM	LUMP SUM	_____	_____	_____
1530	516	70200 CLEARING PARCEL NO. 007 (D902)	LUMP SUM	LUMP SUM	_____	_____	_____
1540	516	70200 CLEARING PARCEL NO. 007 (D903)	LUMP SUM	LUMP SUM	_____	_____	_____
Section: 0001				Total:	_____	_____	_____

Schedule of Items

Proposal ID: C0000111635C01B Oversight/State Project No.: 0106-074-786,C501

Order No.: H38

Federal Project No.: STP-5A27(895)

Contractor: _____

SECTION: 0002 BID ALTERNATIVE #1 - CONCRETE TRUCK APRON

Cat Alt Set ID: _____ Cat Alt Mbr ID: _____

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1550	308	10128 AGGR. BASE MATL. TY. I NO. 21B	302.000 TON	_____	_____	_____	_____
1560	316	10989 CONT. REINF. CONC. PAVE. 13"	727.000 SY	_____	_____	_____	_____
1570	502	12032 RADIAL CURB CG-3	509.000 LF	_____	_____	_____	_____
Section: 0002				Total:		_____	_____

SECTION: 0003 BID ALTERNATIVE #2 - ASPHALT TRUCK APRON

Cat Alt Set ID: _____ Cat Alt Mbr ID: _____

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1580	308	10128 AGGR. BASE MATL. TY. I NO. 21B	398.000 TON	_____	_____	_____	_____
1590	ATTD	10499 PAVEMENT ASPHALT CONCRETE TRUCK APRON	727.000 SY	_____	_____	_____	_____
1600	315	10608 ASPHALT CONCRETE TY. SM-12.5D	80.000 TON	_____	_____	_____	_____
1610	315	10611 ASPHALT CONCRETE TY. IM-19.0D	120.000 TON	_____	_____	_____	_____
1620	315	10642 ASPHALT CONCRETE TY. BM-25.0A	160.000 TON	_____	_____	_____	_____
Section: 0003				Total:		_____	_____
Total Bid:						_____	_____