

Schedule of Items

Proposal ID: C0000107063C01

Oversight/State Project No.: 0221-009-826, M501

Order No.: H79

Federal Project No.: HSIP-5118(318)

Contractor: \_\_\_\_\_

SECTION: 0001

BASE BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	513	00100 MOBILIZATION	LUMP SUM	LUMP SUM			
0020	517	00101 CONSTRUCTION SURVEYING CONSTRUCTION	LUMP SUM	LUMP SUM			
0030	303	00125 GRADING	LUMP SUM	LUMP SUM			
0040	305	00140 BORROW EXCAVATION	23.000 CY				
0050	302 504	00525 CONCRETE CLASS A3 MISC.	4.000 CY				
0060	302	09057 FRAME & COVER MH-1	1.000 EA				
0070	308	10128 AGGR. BASE MATL. TY. I NO. 21B	22.700 TON				
0080	308	10251 AGGR. MATERIAL NO. 57	11.470 CY				
0090	315	10636 ASPHALT CONC.TY. SM-9.5D	8.680 TON				
0100	315	10642 ASPHALT CONCRETE TY. BM- 25.0A	27.400 TON				
0110	502	12020 STD. CURB CG-2	436.000 LF				
0120	502	12022 RADIAL CURB CG-2	16.000 LF				
0130	502	12600 STD. COMB. CURB & GUTTER CG-6	30.000 LF				

Schedule of Items

Proposal ID: C0000107063C01

Oversight/State Project No.: 0221-009-826, M501

Order No.: H79

Federal Project No.: HSIP-5118(318)

Contractor: \_\_\_\_\_

SECTION: 0001

BASE BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0140	502	12610 RADIAL COMB. CURB & GUTTER CG-6	341.000 LF	_____	_____	_____	_____
0150	504	13108 CG-12 DETECTABLE WARNING SURFACE	38.000 SY	_____	_____	_____	_____
0160	521	13215 MAILBOX POST, SINGLE	1.000 EA	_____	_____	_____	_____
0170	504	13220 HYDRAULIC CEMENT CONC. SIDEWALK 4"	911.000 SY	_____	_____	_____	_____
0180	502 ATTD	13244 SAW CUT H.C.C. ITEMS FULL DEPTH	655.000 LF	_____	_____	_____	_____
0190	ATTD	14100 REMOVE SIDEWALK AND ENTRANCE	97.000 SY	_____	_____	_____	_____
0200	ATTD	14120 REMOVE COMB. CURB AND GUTTER	382.000 LF	_____	_____	_____	_____
0210	512	24150 TYPE 3 BARRICADE 4'	4.000 EA	_____	_____	_____	_____
0220	512	24152 TYPE 3 BARRICADE 8'	21.000 EA	_____	_____	_____	_____
0230	512	24160 TEMPORARY (CONSTRUCTION) SIGN	488.000 SF	_____	_____	_____	_____
0240	512	24272 TRUCK MOUNTED ATTENUATOR	2,233.000 HR	_____	_____	_____	_____
0250	512	24278 GROUP 2 CHANNELIZING DEVICES	9,967.000 DAY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000107063C01      Oversight/State Project No.: 0221-009-826, M501  
 Order No.: H79      Federal Project No.: HSIP-5118(318)

Contractor: \_\_\_\_\_

SECTION: 0001      BASE BID ITEMS

Cat Alt Set ID:      Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0260	512	24279 PORTABLE CHANGEABLE MESSAGE SIGN	540.000 HR	_____	_____	_____	_____
0270	512	24281 ELECTRONIC ARROW BOARD	55.000 HR	_____	_____	_____	_____
0280	512	24282 FLAGGER SERVICE	220.000 HR	_____	_____	_____	_____
0290	508	24430 DEMOLITION OF PAVEMENT FLEXIBLE	48.000 SY	_____	_____	_____	_____
0300	510	24832 ADJUST EXIST. MANHOLE REPLACE OR ROTATE ECCENTRIC TAPER UNIT TO REMOVE CONFLICT W/ CG-12	1.000 EA	_____	_____	_____	_____
0310	514	25507 FIELD OFFICE TY.III	9.000 MO	_____	_____	_____	_____
0320	602	27022 TOPSOIL CLASS B 2"	0.073 ACRE	_____	_____	_____	_____
0330	603	27101 TEMPORARY SEED	37.000 LB	_____	_____	_____	_____
0340	603	27102 REGULAR SEED	86.000 LB	_____	_____	_____	_____
0350	603	27103 OVERSEEDING	68.000 LB	_____	_____	_____	_____
0360	603	27104 LEGUME SEED	4.000 LB	_____	_____	_____	_____
0370	603	27105 LEGUME OVERSEEDING	3.000 LB	_____	_____	_____	_____
0380	603	27111 HYDRAULIC EROSION CONTROL PRODUCT TYPE 2	202.000 SY	_____	_____	_____	_____

## Schedule of Items

Proposal ID: C0000107063C01

Oversight/State Project No.: 0221-009-826, M501

Order No.: H79

Federal Project No.: HSIP-5118(318)

Contractor: \_\_\_\_\_

SECTION: 0001

BASE BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0390	603	27112 HYDRAULIC EROSION CONTROL PRODUCT TYPE 3	3,174.000 SY	_____	_____	_____	_____
0400	603	27230 FERTILIZER NITROGEN - N	31.000 LB	_____	_____	_____	_____
0410	603	27231 FERTILIZER PHOSPHOROUS - P	22.000 LB	_____	_____	_____	_____
0420	603	27232 FERTILIZER POTASSIUM - K	22.000 LB	_____	_____	_____	_____
0430	603	27250 LIME	1.710 TON	_____	_____	_____	_____
0440	303	27430 SILTATION CONTROL EXCAVATION	259.000 CY	_____	_____	_____	_____
0450	303	27461 INLET PROTECTION TYPE B	11.000 EA	_____	_____	_____	_____
0460	303	27505 TEMP. SILT FENCE TYPE A	1,200.000 LF	_____	_____	_____	_____
0470	ATTD	49012 UTILITIES UNPAVED UTILITY TEST HOLES	2.000 EA	_____	_____	_____	_____
0480	701	50108 SIGN PANEL	5.000 SF	_____	_____	_____	_____
0490	700	50300 REMOVE EXISTING 1 POST SIGN STRUCTURE	13.000 EA	_____	_____	_____	_____
0500	700	50340 RELOCATE EXISTING 1 POST GROUND MOUNTED SIGN PANEL	13.000 EA	_____	_____	_____	_____
0510	700	50430 SIGN POST STP-1, 2", 14 GAUGE	108.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000107063C01      Oversight/State Project No.: 0221-009-826, M501  
 Order No.: H79      Federal Project No.: HSIP-5118(318)

Contractor: \_\_\_\_\_

SECTION: 0001      BASE BID ITEMS

Cat Alt Set ID:      Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0520	700	50432 SIGN POST STP-1, 2 3/16", 10 GAUGE	6.000 LF	_____	_____	_____	_____
0530	700	50434 SIGN POST STP-1, 2 1/2", 10 GAUGE	41.000 LF	_____	_____	_____	_____
0540	700	50436 SIGN POST STP-1, 2 1/2", 12 GAUGE	21.000 LF	_____	_____	_____	_____
0550	700	50485 CONCRETE SIGN FOUNDATION STP-1, TYPE A	10.000 EA	_____	_____	_____	_____
0560	700	50486 CONCRETE SIGN FOUNDATION STP-1, TYPE B	2.000 EA	_____	_____	_____	_____
0570	703	51200 PEDESTRIAN ACTUATION PA-4	4.000 EA	_____	_____	_____	_____
0580	700	51210 PEDESTAL POLE PF-2 10'	2.000 EA	_____	_____	_____	_____
0590	700	51240 CONCRETE FOUNDATION PF-2	2.000 EA	_____	_____	_____	_____
0600	700	51602 14/4 CONDUCTOR CABLE	750.000 LF	_____	_____	_____	_____
0610	703	51838 HANGER ASSEMBLY SMB-3, ONE WAY	4.000 EA	_____	_____	_____	_____
0620	703	51935 REMOVE EXISTING SIGNAL HEAD	1.000 EA	_____	_____	_____	_____
0630	703	52403 PEDESTRIAN SIGNAL HEAD SP-8	4.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000107063C01      Oversight/State Project No.: 0221-009-826, M501  
 Order No.: H79      Federal Project No.: HSIP-5118(318)

Contractor: \_\_\_\_\_

SECTION: 0001      BASE BID ITEMS

Cat Alt Set ID:      Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0640	704	54034 TYPE B CLASS I PVMT LINE MRKG 6"	450.000 LF	_____	_____	_____	_____
0650	704	54048 TYPE B CLASS II PAVE. LINE MARKING 24"	131.000 LF	_____	_____	_____	_____
0660	512	54105 ERADICATE EXIST. LINEAR PVMT MARKING	509.000 LF	_____	_____	_____	_____
0670	512	54548 TYPE D, CLASS III TEMP. PVMT MRKG 24"	21.000 LF	_____	_____	_____	_____
0680	704	54575 PVMT SYMB MRKG SGL TURN ARROW TY B, CL II	1.000 EA	_____	_____	_____	_____
0690	700	55589 JUNCTION BOX JB-S4	2.000 EA	_____	_____	_____	_____
0700	700	56051 BORED CONDUIT 3"	300.000 LF	_____	_____	_____	_____
0710	700	56054 3" PVC CONDUIT	50.000 LF	_____	_____	_____	_____
0720	700	56200 TRENCH EXCAVATION ECI-1	75.000 LF	_____	_____	_____	_____
<b>Section: 0001</b>				<b>Total:</b>	_____	_____	_____

Schedule of Items

Proposal ID: C0000107063C01      Oversight/State Project No.: 0221-009-826, M501  
 Order No.: H79      Federal Project No.: HSIP-5118(318)

Contractor: \_\_\_\_\_

SECTION: 0002      ADDITIVE BID ITEMS

Cat Alt Set ID:      Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0730	303	00125 GRADING	LUMP SUM	LUMP SUM			
0740	305	00140 BORROW EXCAVATION	12.500 CY				
0750	308	10128 AGGR. BASE MATL. TY. I NO. 21B	51.900 TON				
0760	308	10251 AGGR. MATERIAL NO. 57	2.840 CY				
0770	315	10636 ASPHALT CONC.TY. SM-9.5D	13.760 TON				
0780	315	10642 ASPHALT CONCRETE TY. BM-25.0A	14.690 TON				
0790	502	12020 STD. CURB CG-2	188.000 LF				
0800	502	12022 RADIAL CURB CG-2	5.000 LF				
0810	502	12600 STD. COMB. CURB & GUTTER CG-6	31.000 LF				
0820	502	12610 RADIAL COMB. CURB & GUTTER CG-6	62.000 LF				
0830	504	13108 CG-12 DETECTABLE WARNING SURFACE	6.000 SY				
0840	521	13215 MAILBOX POST, SINGLE	1.000 EA				
0850	504	13220 HYDRAULIC CEMENT CONC. SIDEWALK 4"	890.000 SY				

Schedule of Items

Proposal ID: C0000107063C01

Oversight/State Project No.: 0221-009-826, M501

Order No.: H79

Federal Project No.: HSIP-5118(318)

Contractor: \_\_\_\_\_

SECTION: 0002 ADDITIVE BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0860	502 ATTD	13244 SAW CUT H.C.C. ITEMS FULL DEPTH	503.000 LF	_____	_____	_____	_____
0870	505	13282 GUARDRAIL GR-MGS1, 9' POST	200.000 LF	_____	_____	_____	_____
0880	505	13286 GUARDRAIL TERMINAL GR-MGS2	1.000 EA	_____	_____	_____	_____
0890	505	13287 GUARDRAIL END ANCHORAGE GR-MGS3	1.000 EA	_____	_____	_____	_____
0900	505	13349 GUARDRAIL TERMINAL SITE PREPARATION	1.000 EA	_____	_____	_____	_____
0910	ATTD	14100 REMOVE SIDEWALK AND ENTRANCE	10.000 SY	_____	_____	_____	_____
0920	ATTD	14120 REMOVE COMB. CURB AND GUTTER	92.000 LF	_____	_____	_____	_____
0930	512	24150 TYPE 3 BARRICADE 4'	14.000 EA	_____	_____	_____	_____
0940	512	24160 TEMPORARY (CONSTRUCTION) SIGN	176.000 SF	_____	_____	_____	_____
0950	512	24272 TRUCK MOUNTED ATTENUATOR	781.000 HR	_____	_____	_____	_____
0960	512	24278 GROUP 2 CHANNELIZING DEVICES	3,394.000 DAY	_____	_____	_____	_____
0970	512	24279 PORTABLE CHANGEABLE MESSAGE SIGN	781.000 HR	_____	_____	_____	_____



Schedule of Items

Proposal ID: C0000107063C01

Oversight/State Project No.: 0221-009-826, M501

Order No.: H79

Federal Project No.: HSIP-5118(318)

Contractor: \_\_\_\_\_

SECTION: 0002 ADDITIVE BID ITEMS

Cat Alt Set ID: \_\_\_\_\_ Cat Alt Mbr ID: \_\_\_\_\_

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0980	512	24281 ELECTRONIC ARROW BOARD	781.000 HR	_____	_____	_____	_____
0990	512	24282 FLAGGER SERVICE	110.000 HR	_____	_____	_____	_____
1000	508	24430 DEMOLITION OF PAVEMENT FLEXIBLE	50.000 SY	_____	_____	_____	_____
1010	505	24600 REMOVE EXISTING GUARDRAIL	521.000 LF	_____	_____	_____	_____
1020	504	25003 HANDRAIL HR-1 TYPE II	125.500 LF	_____	_____	_____	_____
1030	602	27022 TOPSOIL CLASS B 2"	0.147 ACRE	_____	_____	_____	_____
1040	603	27101 TEMPORARY SEED	75.000 LB	_____	_____	_____	_____
1050	603	27102 REGULAR SEED	170.000 LB	_____	_____	_____	_____
1060	603	27103 OVERSEEDING	137.000 LB	_____	_____	_____	_____
1070	603	27104 LEGUME SEED	8.000 LB	_____	_____	_____	_____
1080	603	27105 LEGUME OVERSEEDING	6.000 LB	_____	_____	_____	_____
1090	603	27111 HYDRAULIC EROSION CONTROL PRODUCT TYPE 2	403.000 SY	_____	_____	_____	_____
1100	603	27112 HYDRAULIC EROSION CONTROL PRODUCT TYPE 3	6,349.000 SY	_____	_____	_____	_____
1110	603	27230 FERTILIZER NITROGEN - N	62.000 LB	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000107063C01

Oversight/State Project No.: 0221-009-826, M501

Order No.: H79

Federal Project No.: HSIP-5118(318)

Contractor: \_\_\_\_\_

SECTION: 0002 ADDITIVE BID ITEMS

Cat Alt Set ID: \_\_\_\_\_ Cat Alt Mbr ID: \_\_\_\_\_

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1120	603	27231 FERTILIZER PHOSPHOROUS - P	43.000 LB	_____	_____	_____	_____
1130	603	27232 FERTILIZER POTASSIUM - K	43.000 LB	_____	_____	_____	_____
1140	603	27250 LIME	3.410 TON	_____	_____	_____	_____
1150	303	27430 SILTATION CONTROL EXCAVATION	184.000 CY	_____	_____	_____	_____
1160	303	27461 INLET PROTECTION TYPE B	10.000 EA	_____	_____	_____	_____
1170	303	27505 TEMP. SILT FENCE TYPE A	700.000 LF	_____	_____	_____	_____
1180	700	50300 REMOVE EXISTING 1 POST SIGN STRUCTURE	11.000 EA	_____	_____	_____	_____
1190	700	50340 RELOCATE EXISTING 1 POST GROUND MOUNTED SIGN PANEL	11.000 EA	_____	_____	_____	_____
1200	700	50430 SIGN POST STP-1, 2", 14 GAUGE	65.000 LF	_____	_____	_____	_____
1210	700	50485 CONCRETE SIGN FOUNDATION STP-1, TYPE A	11.000 EA	_____	_____	_____	_____
<b>Section: 0002</b>				<b>Total:</b>		_____	
				<b>Total Bid:</b>		_____	