

Schedule of Items

Proposal ID: CM223PMS121652 Oversight/State Project No.: PM2S-962-F23, P401

Order No.: 210

Federal Project No.: PM02(477)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	310	10417 TACK COAT	17,412.000 GAL	_____	_____	_____	_____
0020	315	10700 RUMBLE STRIP CYLINDRICAL ASPHALT	44,557.000 LF	_____	_____	_____	_____
0030	315	10701 LIQUID ASPHALT RUMBLE STRIP COATING	7,427.000 SY	_____	_____	_____	_____
0040	ATTD	16242 AGGR. BASE MATL. TY. I OR II NO. 21A OR 21B	315.300 TON	_____	_____	_____	_____
0050	315	16360 ASPHALT CONC. TY. SM-12.5E	2,621.440 TON	_____	_____	_____	_____
0060	ATTD	16368 PAVEMENT SHOULDER WEDGE PREP.	19,261.000 LF	_____	_____	_____	_____
0070	315	16370 ASPHALT CONC. TY. IM-19.0D	2,960.850 TON	_____	_____	_____	_____
0080	315	16392 ASPH. CONC. TY. BM-25.0D	14,828.780 TON	_____	_____	_____	_____
0090	317, 315	16403 STONE MATRIX ASPHALT SMA-12.5 64E-22	6,409.440 TON	_____	_____	_____	_____
0100	ATTD	16515 FLEXIBLE PAVE. PLANING 10" DEEP MILLING	2,229.330 SY	_____	_____	_____	_____
0110	ATTD	16515 FLEXIBLE PAVE. PLANING 5" DEEP MILLING	27,606.200 SY	_____	_____	_____	_____
0120	ATTD	16515 FLEXIBLE PAVE. PLANING 6.5" DEEP MILLING	30,618.330 SY	_____	_____	_____	_____

Schedule of Items

Proposal ID: CM223PMS121652 Oversight/State Project No.: PM2S-962-F23, P401

Order No.: 210

Federal Project No.: PM02(477)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0130	515	16522 FLEXIBLE PAVEMENT PLANING 0" - 2"	52,495.390 SY	_____	_____	_____	_____
0140	ATTD	24265 MAINTENANCE OF TRAFFIC PLANT MIX	LUMP SUM	LUMP SUM	_____	_____	_____
0150	704	54076 TYPE B CLASS VI PVMT LINE MRKG 6"	54,907.000 LF	_____	_____	_____	_____
0160	704	54078 TYPE B CLASS VI PVMT LINE MRKG 12"	2,224.000 LF	_____	_____	_____	_____
0170	ATTD	54219 INLAID PAVEMENT MARKER ASPHALT	450.000 EA	_____	_____	_____	_____
0180	ATTD	54402 PAVE. MESSAGE MARKING WRONG WAY ARROW	2.000 EA	_____	_____	_____	_____
0190	512	54428 TEMP. PVMT MRKG, TY. A, 4"	41,952.000 LF	_____	_____	_____	_____
0200	512	54430 TEMP. PVMT MRKG, TY. A, 6"	12,955.000 LF	_____	_____	_____	_____
0210	512	54432 TEMP. PVMT MRKG, TY. A, 8"	2,224.000 LF	_____	_____	_____	_____
0220	704	54590 PVMT SYMB MRKG LANE REDUCTION ARROW TY B, CL II	4.000 EA	_____	_____	_____	_____

Section: 0001

Total: _____

Schedule of Items

Proposal ID: CM223PMS121652 Oversight/State Project No.: PM2S-962-F23, P401
 Order No.: 210 Federal Project No.: PM02(477)

Contractor: _____

SECTION: 0002 ALTERNATE ITEM

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0230	ATTD	00306 SELECT MATERIAL ALTERNATE SHOULDER MATERIAL	1.000 TON	_____	_____	_____	_____
Section: 0002				Total:		_____	_____
				Total Bid:		_____	_____