

Schedule of Items

Proposal ID: C0000017633C01

Oversight/State Project No.: BW00-047-103,C501

Order No.: H64

Federal Project No.: STP-5A04(282)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	513	00100 MOBILIZATION	LUMP SUM	LUMP SUM			
0020	517	00101 CONSTRUCTION SURVEYING CONSTRUCTION	LUMP SUM	LUMP SUM			
0030	301	00111 CLEARING AND GRUBBING	0.410 ACRE				
0040	303	00120 REGULAR EXCAVATION	1,944.000 CY				
0050	303	00136 BORROW EXCAVATION	685.000 CY				
0060	ATTD	00170 SOIL Bio-Retention Soil Media	43.000 CY				
0070	ATTD	00180 UTILITY TEST PIT UNPAVED	13.000 EA				
0080	ATTD	00181 UTILITY TEST PIT ASPHALT CONCRETE	15.000 EA				
0090	ATTD	00507 BEDDING MATL. AGGR. NO. 57	20.000 TON				
0100	501	00580 UNDERDRAIN UD-1	21.000 LF				
0110	501	00588 UNDERDRAIN UD-4	710.000 LF				
0120	302	01126 STORM SEWER PIPE 12"	77.000 LF				
0130	302	01186 STORM SEWER PIPE 18"	870.000 LF				
0140	302	01246 STORM SEWER PIPE 24"	52.000 LF				

Schedule of Items

Proposal ID: C0000017633C01 Oversight/State Project No.: BW00-047-103,C501
 Order No.: H64 Federal Project No.: STP-5A04(282)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0150	302	02090 PIPE 6" Non-Perforated	3.600 LF	_____	_____	_____	_____
0160	302	06180 18" END SECTION ES-1 OR 2	2.000 EA	_____	_____	_____	_____
0170	302	06240 24" END SECTION ES-1 OR 2	1.000 EA	_____	_____	_____	_____
0180	302	06740 DROP INLET DI-1	3.000 EA	_____	_____	_____	_____
0190	302	06815 DROP INLET DI-3A	2.000 EA	_____	_____	_____	_____
0200	302	06818 DROP INLET DI-3B,L=6'	3.000 EA	_____	_____	_____	_____
0210	302	07506 DROP INLET DI-5	3.000 EA	_____	_____	_____	_____
0220	510	08990 DROP INLET Mod. DI-1	1.000 EA	_____	_____	_____	_____
0230	302	09056 MANHOLE MH-1 OR 2	13.000 LF	_____	_____	_____	_____
0240	302	09057 FRAME & COVER MH-1	3.000 EA	_____	_____	_____	_____
0250	414	09150 EROSION CONTROL STONE CLASS I, EC-1	5.300 TON	_____	_____	_____	_____
0260	ATTD	09246 PAVED DITCH Flexible Concrete Mat	10.000 SY	_____	_____	_____	_____
0270	308	10128 AGGR. BASE MATL. TY. I NO. 21B	919.000 TON	_____	_____	_____	_____
0280	515	10628 FLEXIBLE PAVEMENT PLANING 0" - 2"	1,032.000 SY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000017633C01 Oversight/State Project No.: BW00-047-103,C501

Order No.: H64

Federal Project No.: STP-5A04(282)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0290	315	10636 ASPHALT CONC.TY. SM-9.5D	192.000 TON	_____	_____	_____	_____
0300	315	10642 ASPHALT CONCRETE TY. BM-25.0A	381.000 TON	_____	_____	_____	_____
0310	315	11070 SAW-CUT ASPH CONC SAWCUT ASPHALT FULL DEPTH	1,667.000 LF	_____	_____	_____	_____
0320	502	12020 STD. CURB CG-2	474.000 LF	_____	_____	_____	_____
0330	502	12600 STD. COMB. CURB & GUTTER CG-6	22.300 LF	_____	_____	_____	_____
0340	502	12610 RADIAL COMB. CURB & GUTTER CG-6	66.000 LF	_____	_____	_____	_____
0350	502	12700 STD. COMB. CURB & GUTTER CG-7	719.000 LF	_____	_____	_____	_____
0360	502	12710 RADIAL COMB. CURB & GUTTER CG-7	88.000 LF	_____	_____	_____	_____
0370	504	13108 CG-12 DETECTABLE WARNING SURFACE	20.000 SY	_____	_____	_____	_____
0380	504	13220 HYDRAULIC CEMENT CONC. SIDEWALK 4"	1,208.000 SY	_____	_____	_____	_____
0390	504	13232 GEOTEXTILE DRAINAGE FABRIC	122.000 SY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000017633C01

Oversight/State Project No.: BW00-047-103,C501

Order No.: H64

Federal Project No.: STP-5A04(282)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0400	502	13244 SAW CUT H.C.C. ITEMS FULL DEPTH CURB AND/OR SIDEWALK	30.000 LF	_____	_____	_____	_____
0410	ATTD	14100 REMOVE SIDEWALK AND ENTRANCE	256.000 SY	_____	_____	_____	_____
0420	ATTD	14120 REMOVE COMB. CURB AND GUTTER	156.000 LF	_____	_____	_____	_____
0430	ATTD	16240 AGGR. MATL. NO.78	3.000 TON	_____	_____	_____	_____
0440	512	24152 TYPE 3 BARRICADE 8'	2.000 EA	_____	_____	_____	_____
0450	512	24160 TEMPORARY (CONSTRUCTION) SIGN	900.000 SF	_____	_____	_____	_____
0460	512	24272 TRUCK MOUNTED ATTENUATOR	2,000.000 HR	_____	_____	_____	_____
0470	512	24278 GROUP 2 CHANNELIZING DEVICES	15,600.000 DAY	_____	_____	_____	_____
0480	512	24281 ELECTRONIC ARROW BOARD	3,200.000 HR	_____	_____	_____	_____
0490	508	24430 DEMOLITION OF PAVEMENT FLEXIBLE	799.000 SY	_____	_____	_____	_____
0500	703.03	24825 MODIFY EXIST. CONTROLLER CABINET	1.000 EA	_____	_____	_____	_____
0510	504	25003 HANDRAIL HR-1 TYPE II	225.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000017633C01 Oversight/State Project No.: BW00-047-103,C501
 Order No.: H64 Federal Project No.: STP-5A04(282)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0520	602	27022 TOPSOIL CLASS B 2"	0.230 ACRE	_____	_____	_____	_____
0530	603	27101 TEMPORARY SEED	23.000 LB	_____	_____	_____	_____
0540	603	27102 REGULAR SEED	81.000 LB	_____	_____	_____	_____
0550	603	27103 OVERSEEDING	64.000 LB	_____	_____	_____	_____
0560	603	27111 HYDRAULIC EROSION CONTROL PRODUCT TYPE 2	182.000 SY	_____	_____	_____	_____
0570	603	27112 HYDRAULIC EROSION CONTROL PRODUCT TYPE 3	2,323.000 SY	_____	_____	_____	_____
0580	603	27230 FERTILIZER NITROGEN - N	23.000 LB	_____	_____	_____	_____
0590	603	27231 FERTILIZER PHOSPHOROUS - P	16.000 LB	_____	_____	_____	_____
0600	603	27232 FERTILIZER POTASSIUM - K	16.000 LB	_____	_____	_____	_____
0610	603	27250 LIME	1.270 TON	_____	_____	_____	_____
0620	303	27284 EROSION CONTROL MULCH	863.000 SY	_____	_____	_____	_____
0630	604	27300 SOD	918.000 SY	_____	_____	_____	_____
0640	303	27410 CHECK DAM, ROCK TY. I	1.000 EA	_____	_____	_____	_____
0650	303	27415 CHECK DAM ROCK TY. II	11.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000017633C01 Oversight/State Project No.: BW00-047-103,C501

Order No.: H64

Federal Project No.: STP-5A04(282)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0660	303	27430 SILTATION CONTROL EXCAVATION	625.000 CY	_____	_____	_____	_____
0670	303	27451 INLET PROTECTION TYPE A	9.000 EA	_____	_____	_____	_____
0680	303	27461 INLET PROTECTION TYPE B	6.000 EA	_____	_____	_____	_____
0690	303	27505 TEMP. SILT FENCE TYPE A	2,552.000 LF	_____	_____	_____	_____
0700	303	27545 STORM WATER MANAGEMENT BASIN EXCAVATION	61.000 CY	_____	_____	_____	_____
0710	ATTD	27553 PERMANENT SWM FACILITY AS-BUILT DOCUMENTATION CONSTRUCTION RECORD DOCUMENTATION	LUMP SUM	LUMP SUM	_____	_____	_____
0720	303	27580 TEMP. SEDIMENT BASIN EXCAVATION	156.000 CY	_____	_____	_____	_____
0730	605	38950 LANDSCAPE JAMESTOWN MAPLE TREE 10-15 GAL.	24.000 EA	_____	_____	_____	_____
0740	ATTD	38952 LANDSCAPE GRASS FORB POLLINATOR MIX	0.200 ACRE	_____	_____	_____	_____
0750	ATTD	38954 LANDSCAPE IMPROVED BACKFILL	199.000 CY	_____	_____	_____	_____
0760	ATTD	38956 LANDSCAPE SPRING WILDFLOWER BULB MIX	10.000 UNIT	_____	_____	_____	_____
0770	520	40061 6" DI WATER MAIN	9.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000017633C01 Oversight/State Project No.: BW00-047-103,C501

Order No.: H64

Federal Project No.: STP-5A04(282)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0780	520	40161 16" DI WATER MAIN	277.000 LF	_____	_____	_____	_____
0790	520	40406 16" BEND	4.000 EA	_____	_____	_____	_____
0800	520	40422 16" BRANCH	1.000 EA	_____	_____	_____	_____
0810	520	41006 6" GATE VALVE & BOX	1.000 EA	_____	_____	_____	_____
0820	520	41820 FIRE HYDRANT	1.000 EA	_____	_____	_____	_____
0830	520	42000 SEWER PIPE NS 3" SANITARY SEWER FORCE MAIN	170.000 LF	_____	_____	_____	_____
0840	520	44301 SEWER UTILITY NS 3" GATE VALVE & BOX FORCE MAIN	1.000 EA	_____	_____	_____	_____
0850	509	45640 FLOWABLE BACKFILL UTILITY	3.000 CY	_____	_____	_____	_____
0860	701	50108 SIGN PANEL	241.180 SF	_____	_____	_____	_____
0870	700	50430 SIGN POST STP-1, 2", 14 GAUGE	55.500 LF	_____	_____	_____	_____
0880	700	50432 SIGN POST STP-1, 2 3/16", 10 GAUGE	78.500 LF	_____	_____	_____	_____
0890	700	50434 SIGN POST STP-1, 2 1/2", 10 GAUGE	173.500 LF	_____	_____	_____	_____
0900	700	50436 SIGN POST STP-1, 2 1/2", 12 GAUGE	53.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000017633C01

Oversight/State Project No.: BW00-047-103,C501

Order No.: H64

Federal Project No.: STP-5A04(282)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0910	700	50485 CONCRETE SIGN FOUNDATION STP-1, TYPE A	11.000 EA	_____	_____	_____	_____
0920	700	50486 CONCRETE SIGN FOUNDATION STP-1, TYPE B	17.000 EA	_____	_____	_____	_____
0930	700	51212 PEDESTAL POLE PF-2 12'	6.000 EA	_____	_____	_____	_____
0940	700	51240 CONCRETE FOUNDATION PF-2	11.000 EA	_____	_____	_____	_____
0950	700	51602 14/4 CONDUCTOR CABLE	3,670.000 LF	_____	_____	_____	_____
0960	700	51615 14/1 ENCLOSED COND. CABLE	330.000 LF	_____	_____	_____	_____
0970	700	51700 14/2 CONDUCTOR CABLE SHIELDED	830.000 LF	_____	_____	_____	_____
0980	703	51838 HANGER ASSEMBLY SMB-3, ONE WAY	6.000 EA	_____	_____	_____	_____
0990	703	51912 LOOP SAW CUT 3/8"	48.000 LF	_____	_____	_____	_____
1000	703	51913 LOOP SAWCUT 5/8"	50.000 LF	_____	_____	_____	_____
1010	703	51937 REMOVE EXISTING MANHOLE/JUNCTION BOX	2.000 EA	_____	_____	_____	_____
1020	ATTD	52002 TRAFFIC SIGNALIZATION ACCESSIBLE PED. PUSH BUTTON (PA-4)	6.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000017633C01 Oversight/State Project No.: BW00-047-103,C501

Order No.: H64

Federal Project No.: STP-5A04(282)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1030	703	52403 PEDESTRIAN SIGNAL HEAD SP-8	6.000 EA	_____	_____	_____	_____
1040	704	54034 TYPE B CLASS I PVMT LINE MRKG 6"	2,000.000 LF	_____	_____	_____	_____
1050	704	54042 TYPE B CLASS I PAVE. LINE MARKING 24"	500.000 LF	_____	_____	_____	_____
1060	512	54105 ERADICATE EXIST. LINEAR PVMT MARKING	1,000.000 LF	_____	_____	_____	_____
1070	512	54106 ERADICATE EXIST. NONLINEAR PVMT MRKG	100.000 SF	_____	_____	_____	_____
1080	704	54393 PVMT MSG. MARK. "ONLY" TY B, CL II, 6'	1.000 EA	_____	_____	_____	_____
1090	704	54402 PAVE. MESSAGE MARKING MESSAGE MARKING 'BIKE'	1.000 EA	_____	_____	_____	_____
1100	704	54402 PAVE. MESSAGE MARKING MESSAGE MARKING 'ENDS'	1.000 EA	_____	_____	_____	_____
1110	704	54402 PAVE. MESSAGE MARKING MESSAGE MARKING 'LANE'	1.000 EA	_____	_____	_____	_____
1120	704	54575 PVMT SYMB MRKG SGL TURN ARROW TY B, CL II	3.000 EA	_____	_____	_____	_____
1130	704	54656 PVMT SYMB MRKG BICYCLE TURN ARROW TY B CL II	4.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000017633C01 Oversight/State Project No.: BW00-047-103,C501

Order No.: H64

Federal Project No.: STP-5A04(282)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1140	704	54660 PVMT SYMB MRKG HELMETED BICYCLIST TY B CL II	4.000 EA	_____	_____	_____	_____
1150	700	55587 JUNCTION BOX JB-S2	11.000 EA	_____	_____	_____	_____
1160	700	56014 ELECT. SER. GRD. ELECTRODE 10'	11.000 EA	_____	_____	_____	_____
1170	700	56022 1" METAL CONDUIT	50.000 LF	_____	_____	_____	_____
1180	700	56050 BORED CONDUIT 2"	600.000 LF	_____	_____	_____	_____
1190	700	56053 2" PVC CONDUIT	680.000 LF	_____	_____	_____	_____
1200	700	56054 3" PVC CONDUIT	25.000 LF	_____	_____	_____	_____
1210	700	56200 TRENCH EXCAVATION ECI-1	705.000 LF	_____	_____	_____	_____
1220	404	60403 CONCRETE CLASS A3	8.240 CY	_____	_____	_____	_____
1230	516	70000 DEMO. OF BLDG. D-1 (C&F SIGN)	LUMP SUM	LUMP SUM	_____	_____	_____
1240	516	70000 DEMO. OF BLDG. D-2 (C&F SIGN)	LUMP SUM	LUMP SUM	_____	_____	_____
1250	516	70000 DEMO. OF BLDG. D-3 (C&F SIGN)	LUMP SUM	LUMP SUM	_____	_____	_____
Section: 0001				Total:	_____	_____	_____
				Total Bid:	_____	_____	_____

