

Schedule of Items

Proposal ID: CM623PMX121872 Oversight/State Project No.: PM6X-966-F23, P401

Order No.: 612

Federal Project No.: PM06403

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	310	10417 TACK COAT	25,427.000 GAL	_____	_____	_____	_____
0020	315	16350 ASPHALT CONC. TY. SM-12.5A	23,359.570 TON	_____	_____	_____	_____
0030	ATTD	16393 ASPH. CONC. PATCH TY. IM-19.0A	602.000 TON	_____	_____	_____	_____
0040	515	16522 FLEXIBLE PAVEMENT PLANING 0" - 2"	256,472.200 SY	_____	_____	_____	_____
0050	ATTD	24265 MAINTENANCE OF TRAFFIC PLANT MIX	LUMP SUM	LUMP SUM	_____	_____	_____
0060	512	24282 FLAGGER SERVICE	3,000.000 HR	_____	_____	_____	_____
0070	700	51615 14/1 ENCLOSED COND. CABLE	46,228.000 LF	_____	_____	_____	_____
0080	703	51912 LOOP SAW CUT 3/8"	16,842.000 LF	_____	_____	_____	_____
0090	703	51913 LOOP SAWCUT 5/8"	3,332.000 LF	_____	_____	_____	_____
0100	704	54032 TYPE B CLASS I PVMT LINE MRKG 4"	113,712.000 LF	_____	_____	_____	_____
0110	704	54037 TYPE B CLASS I PVMT LINE MRKG 8"	2,561.000 LF	_____	_____	_____	_____
0120	704	54042 TYPE B CLASS I PAVE. LINE MARKING 24"	6,911.000 LF	_____	_____	_____	_____
0130	704	54392 PVMT MSG. MARK. "ONLY" TY B, CL. I, 6'	6.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: CM623PMX121872 Oversight/State Project No.: PM6X-966-F23, P401

Order No.: 612

Federal Project No.: PM06403

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0140	704	54395 PVMT MSG. MARK. "SCHOOL" TY B, CL I, 6'	2.000 EA	_____	_____	_____	_____
0150	512	54428 TEMP. PVMT MRKG, TY. A, 4"	227,234.000 LF	_____	_____	_____	_____
0160	704	54574 PVMT SYMB MRKG SGL TURN ARROW TY B, CL I	220.000 EA	_____	_____	_____	_____
0170	704	54577 PVMT SYMB MRKG DBL TURN ARROW THRU/LT OR RT TY B, CL I	11.000 EA	_____	_____	_____	_____
0180	704	54589 PVMT SYMB MRKG LANE REDUCTION ARROW TY B, CL I	4.000 EA	_____	_____	_____	_____
0190	700	56021 1" PVC CONDUIT	2,046.000 LF	_____	_____	_____	_____
Section: 0001				Total:		_____	
				Total Bid:		_____	