

Schedule of Items

Proposal ID: C0000121888N01

Oversight/State Project No.: PM9U-96A-F23, N501

Order No.: 906

Federal Project No.: PM09(369)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	303	00118 EXCAVATION - RHS OF RIGHT TRAVEL LANE & 3RD LANE (MIN. OF 6 FT WIDE)	3,490.400 CY	_____	_____	_____	_____
0020	305	00270 SELECT MATL. TY. I MIN. CBR- 30	1,463.000 TON	_____	_____	_____	_____
0030	305	00355 GEOTEXTILE SUBGRADE STABILIZATION	2,217.000 SY	_____	_____	_____	_____
0040	308	10128 AGGR. BASE MATL. TY. I NO. 21B	1,626.240 TON	_____	_____	_____	_____
0050	310	10417 TACK COAT	33,151.000 GAL	_____	_____	_____	_____
0060	315	10703 RUMBLE STRIP SINUSOIDAL ASPHALT	3,000.000 LF	_____	_____	_____	_____
0070	315	11070 SAW-CUT ASPH CONC SAW & SEAL	480.000 LF	_____	_____	_____	_____
0080	ATTD	16242 AGGR. BASE MATL. TY. I OR II NO. 21A OR 21B	204.000 TON	_____	_____	_____	_____
0090	ATTD	16368 PAVEMENT SHOULDER WEDGE PREP.	42,090.000 LF	_____	_____	_____	_____
0100	315	16390 ASPH. CONC. TY. BM-25.0A	4,878.720 TON	_____	_____	_____	_____
0110	ATTD	16455 ASPH. CONC. BMD P+VO SM- 9.5D	14,777.950 TON	_____	_____	_____	_____
0120	ATTD	16457 ASPH. CONC. BMD P+VO SM- 12.5D	10,466.440 TON	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000121888N01

Oversight/State Project No.: PM9U-96A-F23, N501

Order No.: 906

Federal Project No.: PM09(369)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0130	ATTD	16502 SURF. PREPARATION & RESTORATION TYPE II	451.000 TON	_____	_____	_____	_____
0140	515	16522 FLEXIBLE PAVEMENT PLANING 0" - 2"	161,145.600 SY	_____	_____	_____	_____
0150	515	16523 FLEXIBLE PAVEMENT PLANING ABOVE 2" - 4"	85,184.000 SY	_____	_____	_____	_____
0160	512	24265 MAINTENANCE OF TRAFFIC MOT (SR-7EB, MP 11.17 - MP 13.08)	LUMP SUM	LUMP SUM	_____	_____	_____
0170	512	24265 MAINTENANCE OF TRAFFIC MOT (US-15NB, MP 1.27 - MP 2.03)	LUMP SUM	LUMP SUM	_____	_____	_____
0180	512	24265 MAINTENANCE OF TRAFFIC MOT (US-15NB, MP 5.61 - MP 8.03)	LUMP SUM	LUMP SUM	_____	_____	_____
0190	512	24265 MAINTENANCE OF TRAFFIC MOT (US-15SB, MP 4.14 - MP 5.74)	LUMP SUM	LUMP SUM	_____	_____	_____
0200	512	24265 MAINTENANCE OF TRAFFIC MOT (US-15SB, MP 5.74 - MP 8.03)	LUMP SUM	LUMP SUM	_____	_____	_____
0210	512	24265 MAINTENANCE OF TRAFFIC MOT (US-50EB, MP 16.08 - MP 18.18)	LUMP SUM	LUMP SUM	_____	_____	_____
0220	512	24282 FLAGGER SERVICE	1,790.000 HR	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000121888N01

Oversight/State Project No.: PM9U-96A-F23, N501

Order No.: 906

Federal Project No.: PM09(369)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0230	700	51615 14/1 ENCLOSED COND. CABLE	22,090.000 LF	_____	_____	_____	_____
0240	703	51912 LOOP SAW CUT 3/8"	7,326.000 LF	_____	_____	_____	_____
0250	703	51913 LOOP SAWCUT 5/8"	1,666.000 LF	_____	_____	_____	_____
0260	704	54032 TYPE B CLASS I PVMT LINE MRKG 4"	124,582.000 LF	_____	_____	_____	_____
0270	704	54034 TYPE B CLASS I PVMT LINE MRKG 6"	25,546.000 LF	_____	_____	_____	_____
0280	704	54040 TYPE B CLASS I PVMT LINE MRKG 12"	490.000 LF	_____	_____	_____	_____
0290	704	54042 TYPE B CLASS I PAVE. LINE MARKING 24"	3,414.000 LF	_____	_____	_____	_____
0300	ATTD	54219 INLAID PAVEMENT MARKER ASPHALT	1,249.000 EA	_____	_____	_____	_____
0310	704	54400 PVMT MESSAGE MARK. ONLY	5.000 EA	_____	_____	_____	_____
0320	512	54428 TEMP. PVMT MRKG, TY. A, 4"	82,746.000 LF	_____	_____	_____	_____
0330	512	54430 TEMP. PVMT MRKG, TY. A, 6"	24,889.000 LF	_____	_____	_____	_____
0340	512	54440 TEMP. PVMT MRKG, TY. A, 24"	1,145.000 LF	_____	_____	_____	_____
0350	512	54457 TEMP. PVMT SYMBOL MRKG SINGLE TURN ARROW TY. A	28.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000121888N01 Oversight/State Project No.: PM9U-96A-F23, N501

Order No.: 906

Federal Project No.: PM09(369)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0360	704	54571 PVMT SYMB MRKG THRU ARROW TY B, CL I	1.000 EA	_____	_____	_____	_____
0370	704	54574 PVMT SYMB MRKG SGL TURN ARROW TY B, CL I	122.000 EA	_____	_____	_____	_____
0380	704	54576 PVMT SYMB MRKG DBL TURN ARROW THRU/LT OR RT TY A	3.000 EA	_____	_____	_____	_____
0390	704	54577 PVMT SYMB MRKG DBL TURN ARROW THRU/LT OR RT TY B, CL I	7.000 EA	_____	_____	_____	_____
0400	704	54589 PVMT SYMB MRKG LANE REDUCTION ARROW TY B, CL I	3.000 EA	_____	_____	_____	_____
0410	700	56022 1" METAL CONDUIT	186.000 LF	_____	_____	_____	_____
Section: 0001				Total:	_____	_____	_____

SECTION: 0002 ALTERNATE ITEM

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0420	ATTD	00306 SELECT MATERIAL ALTERNATE SHOULDER MATERIAL	1.000 TON	_____	_____	_____	_____
Section: 0002				Total:	_____	_____	_____
				Total Bid:	_____	_____	_____