

Schedule of Items

Proposal ID: C0000121717N01 Oversight/State Project No.: PM9N-053-F23, N501
 Order No.: 908 Federal Project No.: PM09(370)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	310	10417 TACK COAT	32,381.000 GAL	_____	_____	_____	_____
0020	ATTD	16242 AGGR. BASE MATL. TY. I OR II NO. 21A OR 21B	130.000 TON	_____	_____	_____	_____
0030	315	16340 ASPHALT CONC. TY. SM-9.5D	29,996.280 TON	_____	_____	_____	_____
0040	ATTD	16368 PAVEMENT SHOULDER WEDGE PREP.	18,750.000 LF	_____	_____	_____	_____
0050	ATTD	16502 SURF. PREPARATION & RESTORATION TYPE II	695.000 TON	_____	_____	_____	_____
0060	515	16522 FLEXIBLE PAVEMENT PLANING 0" - 2"	323,810.160 SY	_____	_____	_____	_____
0070	ATTD	24262 PORTABLE TEMPORARY RUMBLE STRIP ARRAY	40.000 DAY	_____	_____	_____	_____
0080	512	24265 MAINTENANCE OF TRAFFIC MOT	LUMP SUM	LUMP SUM	_____	_____	_____
0090	512	24282 FLAGGER SERVICE	2,111.000 HR	_____	_____	_____	_____
0100	700	51615 14/1 ENCLOSED COND. CABLE	11,940.000 LF	_____	_____	_____	_____
0110	703	51912 LOOP SAW CUT 3/8"	5,544.000 LF	_____	_____	_____	_____
0120	703	51913 LOOP SAWCUT 5/8"	1,170.000 LF	_____	_____	_____	_____
0130	704	54032 TYPE B CLASS I PVMT LINE MRKG 4"	203,973.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000121717N01 Oversight/State Project No.: PM9N-053-F23, N501
 Order No.: 908 Federal Project No.: PM09(370)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0140	704	54034 TYPE B CLASS I PVMT LINE MRKG 6"	877.000 LF	_____	_____	_____	_____
0150	704	54042 TYPE B CLASS I PAVE. LINE MARKING 24"	5,159.000 LF	_____	_____	_____	_____
0160	704	54400 PVMT MESSAGE MARK. ONLY	25.000 EA	_____	_____	_____	_____
0170	512	54428 TEMP. PVMT MRKG, TY. A, 4"	135,722.000 LF	_____	_____	_____	_____
0180	512	54430 TEMP. PVMT MRKG, TY. A, 6"	877.000 LF	_____	_____	_____	_____
0190	512	54440 TEMP. PVMT MRKG, TY. A, 24"	663.000 LF	_____	_____	_____	_____
0200	512	54457 TEMP. PVMT SYMBOL MRKG SINGLE TURN ARROW TY. A	31.000 EA	_____	_____	_____	_____
0210	704	54571 PVMT SYMB MRKG THRU ARROW TY B, CL I	2.000 EA	_____	_____	_____	_____
0220	704	54574 PVMT SYMB MRKG SGL TURN ARROW TY B, CL I	190.000 EA	_____	_____	_____	_____
0230	704	54577 PVMT SYMB MRKG DBL TURN ARROW THRU/LT OR RT TY B, CL I	1.000 EA	_____	_____	_____	_____
0240	700	56022 1" METAL CONDUIT	130.000 LF	_____	_____	_____	_____
Section: 0001				Total:	_____	_____	_____

Schedule of Items

Proposal ID: C0000121717N01

Oversight/State Project No.: PM9N-053-F23, N501

Order No.: 908

Federal Project No.: PM09(370)

Contractor: _____

SECTION: 0002 ALTERNATE ITEM

Cat Alt Set ID: _____ Cat Alt Mbr ID: _____

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0250	ATTD	00306 SELECT MATERIAL ALTERNATE SHOULDER MATERIAL	1.000 TON	_____	_____	_____	_____
Section: 0002				Total:		_____	_____
				Total Bid:		_____	_____