

Schedule of Items

Proposal ID: C0000121351B69

Oversight/State Project No.: 0622-086-841, B669

Order No.: H97

Federal Project No.: STP-BR01(390)

Contractor: \_\_\_\_\_

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	513	00100 MOBILIZATION	LUMP SUM	LUMP SUM			
0020	ATTD 512	00162 ACCESS ROAD TEMPORARY CONSTRUCTION ACCESS	LUMP SUM	LUMP SUM			
0030	308	10128 AGGR. BASE MATL. TY. I NO. 21B	33.000 TON				
0040	315	10609 ASPHALT CONCRETE TY. SM-12.5E	16.000 TON				
0050	315	10642 ASPHALT CONCRETE TY. BM-25.0A	63.000 TON				
0060	315	11070 SAW-CUT ASPH CONC SAW-CUT ASHPAHLT CONCRETE	58.000 LF				
0070	515	16524 FLEXIBLE PAVEMENT PLANING ABOVE 4"	145.000 SY				
0080	512	24160 TEMPORARY (CONSTRUCTION) SIGN	302.000 SF				
0090	ATTD	24262 PORTABLE TEMPORARY RUMBLE STRIP ARRAY	36.000 DAY				
0100	ATTD	24265 MAINTENANCE OF TRAFFIC STEEL ROADWAY PLATE	LUMP SUM	LUMP SUM			
0110	512	24278 GROUP 2 CHANNELIZING DEVICES	1,400.000 DAY				
0120	512	24282 FLAGGER SERVICE	40.000 HR				

Schedule of Items

Proposal ID: C0000121351B69      Oversight/State Project No.: 0622-086-841, B669  
 Order No.: H97      Federal Project No.: STP-BR01(390)

Contractor: \_\_\_\_\_

SECTION: 0001      REGULAR BID ITEMS

Cat Alt Set ID:      Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0130	512	51955 TEMPORARY TRAFFIC CONTROL SIGNAL STR. NO. 6395	LUMP SUM	LUMP SUM			
0140	704	54020 TYPE A PVMT LINE MRKG 4"	1,050.000 LF				
0150	ATTD 412	62534 BRIDGE SUPERSTRUCTURE DECK SLAB CLOSURE	24.000 SY				
0160	ATTD 412	66924 BRIDGE SUBSTRUCTURE ANCHOR BOLT REPLACEMENT	40.000 EA				
0170	ATTD 412	66924 BRIDGE SUBSTRUCTURE REPLACE BEARING	20.000 EA				
0180	412	68180 EMBEDDED GALVANIC ANODES	352.000 EA				
0190	412	68320 PATCHING TYPE B	20.000 SY				
0200	412	68330 PATCHING TYPE C	5.000 SY				
0210	416	68406 WATERPROOFING - EPOXY RESIN TYPE EP-3B/EP-3T	230.000 SY				
0220	411	68470 PRE. & OVERCOAT EX. STR. STR. NO. 6395, TYPE B	LUMP SUM	LUMP SUM			
0230	411	68476 ENV. & WORK. PROTECTION STR. NO. 6395, TYPE B	LUMP SUM	LUMP SUM			
0240	411	68490 DISPOSAL OF MATERIAL STR. NO. 6395, TYPE B	LUMP SUM	LUMP SUM			

Schedule of Items

Proposal ID: C0000121351B69

Oversight/State Project No.: 0622-086-841, B669

Order No.: H97

Federal Project No.: STP-BR01(390)

Contractor: \_\_\_\_\_

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0250	421	68550 ELASTOMERIC EXPANSION DAM 0" TO 2"	56.000 LF	_____	_____	_____	_____
0260	412	68572 RECONSTRUCT EXPANSION JOINT	56.000 LF	_____	_____	_____	_____
0270	426	68591 JACKING AND BLOCKING BEAM	20.000 EA	_____	_____	_____	_____
0280	431	68675 EPOXY OVERLAY	354.000 SY	_____	_____	_____	_____
0290	ATTD 412	68902 SUPERSTR. WID./REPAIR BEAM REPAIR TYPE WF (WEB AND FLANGE)	53.500 LF	_____	_____	_____	_____
0300	ATTD 412	68904 SUPERSTR. WID./REPAIR BEAM REPAIR TYPE DIA (DIAPHRAGM)	15.000 EA	_____	_____	_____	_____
0310	ATTD 412	68904 SUPERSTR. WID./REPAIR BEAM REPAIR TYPE SR (STIFFENER REPLACEMENT)	10.000 EA	_____	_____	_____	_____
0320	412	69500 CONCRETE SUBSTRUCT. SURFACE REPAIR	64.000 SY	_____	_____	_____	_____
0330	416	69835 WATERPROOFING - EPOXY RESIN TYPE EP-3B/EP-3T	170.000 SY	_____	_____	_____	_____
<b>Section: 0001</b>				<b>Total:</b>		_____	
				<b>Total Bid:</b>		_____	