

Schedule of Items

Proposal ID: CM623PMR121844 Oversight/State Project No.: PM6R-966-F23, P401

Order No.: 617

Federal Project No.: PM06403

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	310	10417 TACK COAT	20,490.000 GAL	_____	_____	_____	_____
0020	315	10700 RUMBLE STRIP CYLINDRICAL ASPHALT	138,654.000 LF	_____	_____	_____	_____
0030	315	16350 ASPHALT CONC. TY. SM-12.5A	17,236.100 TON	_____	_____	_____	_____
0040	ATTD	16368 PAVEMENT SHOULDER WEDGE PREP.	93,032.000 LF	_____	_____	_____	_____
0050	ATTD	16393 ASPH. CONC. PATCH TY. IM-19.0A	801.000 TON	_____	_____	_____	_____
0060	515	16522 FLEXIBLE PAVEMENT PLANING 0" - 2"	202,662.270 SY	_____	_____	_____	_____
0070	ATTD	24262 PORTABLE TEMPORARY RUMBLE STRIP ARRAY	96.000 DAY	_____	_____	_____	_____
0080	ATTD	24265 MAINTENANCE OF TRAFFIC PLANT MIX	LUMP SUM	LUMP SUM	_____	_____	_____
0090	512	24282 FLAGGER SERVICE	954.000 HR	_____	_____	_____	_____
0100	700	51615 14/1 ENCLOSED COND. CABLE	2,624.000 LF	_____	_____	_____	_____
0110	703	51912 LOOP SAW CUT 3/8"	948.000 LF	_____	_____	_____	_____
0120	703	51913 LOOP SAWCUT 5/8"	192.000 LF	_____	_____	_____	_____
0130	704	54032 TYPE B CLASS I PVMT LINE MRKG 4"	121,015.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: CM623PMR121844 Oversight/State Project No.: PM6R-966-F23, P401

Order No.: 617

Federal Project No.: PM06403

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0140	704	54034 TYPE B CLASS I PVMT LINE MRKG 6"	112,504.000 LF	_____	_____	_____	_____
0150	704	54042 TYPE B CLASS I PAVE. LINE MARKING 24"	464.000 LF	_____	_____	_____	_____
0160	ATTD	54219 INLAID PAVEMENT MARKER ASPHALT	922.000 EA	_____	_____	_____	_____
0170	512	54428 TEMP. PVMT MRKG, TY. A, 4"	446,650.000 LF	_____	_____	_____	_____
0180	704	54574 PVMT SYMB MRKG SGL TURN ARROW TY B, CL I	31.000 EA	_____	_____	_____	_____
0190	704	54577 PVMT SYMB MRKG DBL TURN ARROW THRU/LT OR RT TY B, CL I	4.000 EA	_____	_____	_____	_____
0200	700	56021 1" PVC CONDUIT	90.000 LF	_____	_____	_____	_____

Section: 0001

Total: _____

Total Bid: _____