

Schedule of Items

Proposal ID: C0000115726C01

Oversight/State Project No.: 0206-048-609, C501

Order No.: H96

Federal Project No.: STP-048-6(065)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	513	00100 MOBILIZATION	LUMP SUM	LUMP SUM			
0020	517	00101 CONSTRUCTION SURVEYING CONSTRUCTION	LUMP SUM	LUMP SUM			
0030	301	00110 CLEARING AND GRUBBING	LUMP SUM	LUMP SUM			
0040	303	00120 REGULAR EXCAVATION	170.000 CY				
0050	303	00150 EMBANKMENT	29.000 CY				
0060	203	00506 BEDDING MATL. AGGR. NO. OPEN GRADED COURSE AGGREGATE, NO. 3	66.000 TON				
0070	302 504	00525 CONCRETE CLASS A3 MISC.	4.100 CY				
0080	509	00529 FLOWABLE BACKFILL	16.000 CY				
0090	302 406	00540 REINF. STEEL	1,085.000 LB				
0100	302	00560 STRUCTURAL STEEL JB-1	50.000 LB				
0110	501	00588 UNDERDRAIN UD-4	493.000 LF				
0120	302	01156 STORM SEWER PIPE 15"	92.000 LF				
0130	302	01186 STORM SEWER PIPE 18"	9.000 LF				
0140	302	01486 STORM SEWER PIPE 48"	76.000 LF				

Schedule of Items

Proposal ID: C0000115726C01 Oversight/State Project No.: 0206-048-609, C501
 Order No.: H96 Federal Project No.: STP-048-6(065)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0150	302	02092 SPEC. DES. DRAINAGE CONTROL STRUCTURE 3-2	1.000 EA	_____	_____	_____	_____
0160	302	06749 DROP INLET DI-2B,L=8'	1.000 EA	_____	_____	_____	_____
0170	302	07508 DROP INLET DI-7	1.000 EA	_____	_____	_____	_____
0180	302	09057 FRAME & COVER MH-1	1.000 EA	_____	_____	_____	_____
0190	308	10128 AGGR. BASE MATL. TY. I NO. 21B	170.000 TON	_____	_____	_____	_____
0200	315	10607 ASPHALT CONCRETE TY. SM-12.5A	56.000 TON	_____	_____	_____	_____
0210	315	10610 ASPHALT CONCRETE TY. IM-19.0A	56.000 TON	_____	_____	_____	_____
0220	315	10642 ASPHALT CONCRETE TY. BM-25.0A	84.000 TON	_____	_____	_____	_____
0230	315	10700 RUMBLE STRIP CYLINDRICAL ASPHALT	50.000 LF	_____	_____	_____	_____
0240	502	12700 STD. COMB. CURB & GUTTER CG-7	451.000 LF	_____	_____	_____	_____
0250	502	12710 RADIAL COMB. CURB & GUTTER CG-7	60.000 LF	_____	_____	_____	_____
0260	ATTD	14260 CRUSHER RUN AGGREGATE NO. 25 OR 26	40.000 TON	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000115726C01 Oversight/State Project No.: 0206-048-609, C501
 Order No.: H96 Federal Project No.: STP-048-6(065)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0270	507	23570 HIGH VISIBILITY FENCE, 4'	122.000 LF	_____	_____	_____	_____
0280	511	24100 ALLAYING DUST	10.000 HR	_____	_____	_____	_____
0290	512	24160 TEMPORARY (CONSTRUCTION) SIGN	448.000 SF	_____	_____	_____	_____
0300	ATTD	24262 PORTABLE TEMPORARY RUMBLE STRIP ARRAY	48.000 DAY	_____	_____	_____	_____
0310	512	24272 TRUCK MOUNTED ATTENUATOR	732.000 HR	_____	_____	_____	_____
0320	512	24278 GROUP 2 CHANNELIZING DEVICES	2,920.000 DAY	_____	_____	_____	_____
0330	512	24281 ELECTRONIC ARROW BOARD	700.000 HR	_____	_____	_____	_____
0340	512	24282 FLAGGER SERVICE	208.000 HR	_____	_____	_____	_____
0350	512	24332 MODIFY SIGNAL DURING CONSTRUCTION	LUMP SUM	LUMP SUM	_____	_____	_____
0360	508	24430 DEMOLITION OF PAVEMENT FLEXIBLE	56.000 SY	_____	_____	_____	_____
0370	512	24501 REMOVE EXIST. CONDUIT	740.000 LF	_____	_____	_____	_____
0380	302	24825 MODIFY EXIST. DROP INLET	1.000 EA	_____	_____	_____	_____
0390	514	25507 FIELD OFFICE TY.III	6.000 MO	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000115726C01 Oversight/State Project No.: 0206-048-609, C501
 Order No.: H96 Federal Project No.: STP-048-6(065)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0400	603	27101 TEMPORARY SEED	23.000 LB	_____	_____	_____	_____
0410	603	27102 REGULAR SEED	43.000 LB	_____	_____	_____	_____
0420	603	27103 OVERSEEDING	35.000 LB	_____	_____	_____	_____
0430	603	27111 HYDRAULIC EROSION CONTROL PRODUCT TYPE 2	1,392.000 SY	_____	_____	_____	_____
0440	603	27112 HYDRAULIC EROSION CONTROL PRODUCT TYPE 3	1,113.000 SY	_____	_____	_____	_____
0450	603	27230 FERTILIZER NITROGEN - N	22.000 LB	_____	_____	_____	_____
0460	603	27231 FERTILIZER PHOSPHOROUS - P	30.000 LB	_____	_____	_____	_____
0470	603	27232 FERTILIZER POTASSIUM - K	15.000 LB	_____	_____	_____	_____
0480	603	27250 LIME	1.040 TON	_____	_____	_____	_____
0490	606	27318 ROLLED EROSION CTRL PRODUCT EC-2 TYPE 1	121.000 SY	_____	_____	_____	_____
0500	303	27430 SILTATION CONTROL EXCAVATION	151.000 CY	_____	_____	_____	_____
0510	303	27451 INLET PROTECTION TYPE A	2.000 EA	_____	_____	_____	_____
0520	303	27461 INLET PROTECTION TYPE B	1.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000115726C01

Oversight/State Project No.: 0206-048-609, C501

Order No.: H96

Federal Project No.: STP-048-6(065)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0530	303	27505 TEMP. SILT FENCE TYPE A	799.000 LF	_____	_____	_____	_____
0540	520	40002 3/4" WATER SERVICE LINE	17.000 LF	_____	_____	_____	_____
0550	520	40020 2" WATER MAIN	25.000 LF	_____	_____	_____	_____
0560	520	41970 5/8" WATER METER & BOX	1.000 EA	_____	_____	_____	_____
0570	701	50108 SIGN PANEL	8.000 SF	_____	_____	_____	_____
0580	700	50430 SIGN POST STP-1, 2", 14 GAUGE	12.000 LF	_____	_____	_____	_____
0590	700	50432 SIGN POST STP-1, 2 3/16", 10 GAUGE	47.000 LF	_____	_____	_____	_____
0600	700	50434 SIGN POST STP-1, 2 1/2", 10 GAUGE	47.000 LF	_____	_____	_____	_____
0610	700	50436 SIGN POST STP-1, 2 1/2", 12 GAUGE	12.000 LF	_____	_____	_____	_____
0620	700	50485 CONCRETE SIGN FOUNDATION STP-1, TYPE A	2.000 EA	_____	_____	_____	_____
0630	700	50486 CONCRETE SIGN FOUNDATION STP-1, TYPE B	3.000 EA	_____	_____	_____	_____
0640	ATTD	50759 RELOC. EXIST. SIGN PANEL TY. SP-1	16.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000115726C01

Oversight/State Project No.: 0206-048-609, C501

Order No.: H96

Federal Project No.: STP-048-6(065)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0650	703	51185 TRAFFIC SIGNAL HEAD SECTION 12" HVS BACKPLATE	5.000 EA	_____	_____	_____	_____
0660	700	51607 14/7 CONDUCTOR CABLE	50.000 LF	_____	_____	_____	_____
0670	703	51830 HANGER ASSEMBLY SM-3, ONE WAY	1.000 EA	_____	_____	_____	_____
0680	703	51935 REMOVE EXISTING SIGNAL HEAD	1.000 EA	_____	_____	_____	_____
0690	703	51937 REMOVE EXISTING MANHOLE/JUNCTION BOX	4.000 EA	_____	_____	_____	_____
0700	704	54032 TYPE B CLASS I PVMT LINE MRKG 4"	772.000 LF	_____	_____	_____	_____
0710	704	54042 TYPE B CLASS I PAVE. LINE MARKING 24"	12.000 LF	_____	_____	_____	_____
0720	ATTD	54219 INLAID PAVEMENT MARKER ASPHALT	6.000 EA	_____	_____	_____	_____
0730	512	54466 TYPE E TEMP. PVMT MRKG 6"	1,200.000 LF	_____	_____	_____	_____
0740	512	54542 TYPE D, CLASS III TEMP. PVMT MRKG 4"	1,700.000 LF	_____	_____	_____	_____
0750	704	54574 PVMT SYMB MRKG SGL TURN ARROW TY B, CL I	2.000 EA	_____	_____	_____	_____
0760	700	55126 CONDUCTOR CABLE, NO. 8 EGC	10.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000115726C01

Oversight/State Project No.: 0206-048-609, C501

Order No.: H96

Federal Project No.: STP-048-6(065)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0770	700	56036 3" METAL CONDUIT	10.000 LF	_____	_____	_____	_____
0780	412	68576 SAW CUTTING	500.000 LF	_____	_____	_____	_____
Section: 0001				Total:		_____	
				Total Bid:		_____	