

Schedule of Items

Proposal ID: C0000119698B42 Oversight/State Project No.: 0604-010-842, B642
 Order No.: H98 Federal Project No.: STP-BR01(391)

Contractor: _____

SECTION: 0001 REGULAT ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	513	00100 MOBILIZATION	LUMP SUM	LUMP SUM			
0020	517	00101 CONSTRUCTION SURVEYING CONSTRUCTION	LUMP SUM	LUMP SUM			
0030	302	01240 24" PIPE	58.000 LF				
0040	302	06240 24" END SECTION ES-1 OR 2	2.000 EA				
0050	414	09150 EROSION CONTROL STONE CLASS I, EC-1	10.000 TON				
0060	305	10113 AGGR. BASE MATL. TY. I NO. 21A OR 21B	60.000 TON				
0070	315	10607 ASPHALT CONCRETE TY. SM- 12.5A	115.000 TON				
0080	515	10628 FLEXIBLE PAVEMENT PLANING 0" - 2"	668.000 SY				
0090	512	13496 TRAF. BARR. SER. CONC. DOUBLE FACE PAR.MB-11A	80.000 LF				
0100	507	22501 FENCE FE-W1	300.000 LF				
0110	507	22541 LINE BRACE UNIT FE-W1,FE- W2	8.000 EA				
0120	507	22908 GATE FE-G L=12'	1.000 EA				
0130	512	24152 TYPE 3 BARRICADE 8'	12.000 EA				

Schedule of Items

Proposal ID: C0000119698B42 Oversight/State Project No.: 0604-010-842, B642
 Order No.: H98 Federal Project No.: STP-BR01(391)

Contractor: _____

SECTION: 0001 REGULAT ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0140	512	24160 TEMPORARY (CONSTRUCTION) SIGN	600.000 SF	_____	_____	_____	_____
0150	512	24278 GROUP 2 CHANNELIZING DEVICES	2,880.000 DAY	_____	_____	_____	_____
0160	512	24288 WARNING LIGHT TY. B	2,160.000 DAY	_____	_____	_____	_____
0170	414	26239 DRY RIPRAP CL.II 38"	30.000 TON	_____	_____	_____	_____
0180	303	27417 CHECK DAM SEDIMENT RETENTION ROLL 18"	3.000 EA	_____	_____	_____	_____
0190	303	27422 DEWATERING BASIN EC-8	3.000 EA	_____	_____	_____	_____
0200	303	27430 SILTATION CONTROL EXCAVATION	171.000 CY	_____	_____	_____	_____
0210	303	27505 TEMP. SILT FENCE TYPE A	1,000.000 LF	_____	_____	_____	_____
0220	701	50108 SIGN PANEL	24.000 SF	_____	_____	_____	_____
0230	700	50430 SIGN POST STP-1, 2", 14 GAUGE	56.000 LF	_____	_____	_____	_____
0240	700	50485 CONCRETE SIGN FOUNDATION STP-1, TYPE A	8.000 EA	_____	_____	_____	_____
0250	703	51911 SAW CUT ASPHALT FULL DEPTH	100.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000119698B42 Oversight/State Project No.: 0604-010-842, B642
 Order No.: H98 Federal Project No.: STP-BR01(391)

Contractor: _____

SECTION: 0001 REGULAT ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0260	ATTD,404	61020 VIRGINIA ADJACENT MEMBER CONNECTION BLOCK-OUTS	161.200 CF	_____	_____	_____	_____
0270	405	61181 PREST. CONC. SLAB 4' X 18" X(+30' - 35')	20.000 EA	_____	_____	_____	_____
0280	401	64015 SELECT BACKFILL ABUTMENT ZONE	26.000 TON	_____	_____	_____	_____
0290	PLAN	66927 BRIDGE SUBSTRUCTURE TEMPORARY WORKBRIDGES	LUMP SUM	LUMP SUM	_____	_____	_____
0300	505	68019 GUARDRAIL, THRIE BEAM	388.000 LF	_____	_____	_____	_____
0310	413	68476 ENV.& WORK. PROTECTION Type B	LUMP SUM	LUMP SUM	_____	_____	_____
0320	413	68492 MATERIAL DISPOSAL Type B	LUMP SUM	LUMP SUM	_____	_____	_____
0330	413	68900 REM. PORT. OF EX. STR. VIRGINIA STR. NO. 6063	LUMP SUM	LUMP SUM	_____	_____	_____
0340	413	68900 REM. PORT. OF EX. STR. VIRGINIA STR. NO. 6064	LUMP SUM	LUMP SUM	_____	_____	_____
0350	509	69007 FLOWABLE BACKFILL	10.000 CY	_____	_____	_____	_____
0360	401	69011 STRUCTURE EXCAVATION	68.000 CY	_____	_____	_____	_____
0370	401	69014 SELECT BACKFILL ABUTMENT ZONE	24.000 TON	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000119698B42 Oversight/State Project No.: 0604-010-842, B642
 Order No.: H98 Federal Project No.: STP-BR01(391)

Contractor: _____

SECTION: 0001 REGULAT ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0380	412	69030 CONCRETE CLASS A3	55.100 CY	_____	_____	_____	_____
0390	406	69091 CORROSION RESISTANT REINF. STEEL CL. I	7,610.000 LB	_____	_____	_____	_____
0400	412	69500 CONCRETE SUBSTRUCT. SURFACE REPAIR	7.000 SY	_____	_____	_____	_____
0410	401	69620 COFFERDAM	3.000 EA	_____	_____	_____	_____
0420	416	69835 WATERPROOFING - EPOXY RESIN TYPE EP-3B/EP-3T	356.000 SY	_____	_____	_____	_____
Section: 0001				Total:	_____	_____	_____
				Total Bid:	_____	_____	_____