

Schedule of Items

Proposal ID: C0000117882D43

Oversight/State Project No.: 0707-056-733, D643

Order No.: J18

Federal Project No.: NONE

Contractor: \_\_\_\_\_

SECTION: 0001 REGULAR ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	513	00100 MOBILIZATION	LUMP SUM	LUMP SUM			
0020	517	00101 CONSTRUCTION SURVEYING CONSTRUCTION	LUMP SUM	LUMP SUM			
0030	301	00111 CLEARING AND GRUBBING	0.300 ACRE				
0040	303	00120 REGULAR EXCAVATION	657.000 CY				
0050	303	00212 MINOR STRUCTURE EXCAV. BOX CULVERT	211.000 CY				
0060	302	00506 BEDDING MATL. AGGR. NO. No. 57 Stone	15.000 TON				
0070	302	00523 PRECAST BOX CULVERT Precast 10'x6' Box Culvert	40.000 LF				
0080	302	01150 15" PIPE	29.000 LF				
0090	302	01240 24" PIPE	110.000 LF				
0100	414	09148 EROSION CONTROL STONE CLASS A1 EC-1	136.000 TON				
0110	308	10128 AGGR. BASE MATL. TY. I NO. 21B	836.000 TON				
0120	515	10628 FLEXIBLE PAVEMENT PLANING 0" - 2"	140.000 SY				
0130	315	10635 ASPHALT CONC.TY. SM-9.5A	23.000 TON				

Schedule of Items

Proposal ID: C0000117882D43 Oversight/State Project No.: 0707-056-733, D643

Order No.: J18

Federal Project No.: NONE

Contractor: \_\_\_\_\_

SECTION: 0001 REGULAR ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0140	315	10642 ASPHALT CONCRETE TY. BM-25.0A	32.000 TON	_____	_____	_____	_____
0150	315	11070 SAW-CUT ASPH CONC Full Depth Sawcut	44.000 LF	_____	_____	_____	_____
0160	505	13372 SP. DES. GR.BR.ATTACH BR-GR Special Design GR attachment	6.000 EA	_____	_____	_____	_____
0170	410 505	13375 RAILING, TEXAS T-6	50.000 LF	_____	_____	_____	_____
0180	512	13496 TRAF. BARR. SER. CONC. DOUBLE FACE PAR.MB-11A	40.000 LF	_____	_____	_____	_____
0190	507	22501 FENCE FE-W1	345.000 LF	_____	_____	_____	_____
0200	507	22541 LINE BRACE UNIT FE-W1,FE-W2	2.000 EA	_____	_____	_____	_____
0210	511	24100 ALLAYING DUST	80.000 HR	_____	_____	_____	_____
0220	512	24152 TYPE 3 BARRICADE 8'	4.000 EA	_____	_____	_____	_____
0230	512	24160 TEMPORARY (CONSTRUCTION) SIGN	226.000 SF	_____	_____	_____	_____
0240	512	24278 GROUP 2 CHANNELIZING DEVICES	1,200.000 DAY	_____	_____	_____	_____
0250	512	24282 FLAGGER SERVICE	64.000 HR	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000117882D43

Oversight/State Project No.: 0707-056-733, D643

Order No.: J18

Federal Project No.: NONE

Contractor: \_\_\_\_\_

SECTION: 0001 REGULAR ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0260	508	24430 DEMOLITION OF PAVEMENT FLEXIBLE	136.000 SY	_____	_____	_____	_____
0270	414	26127 DRY RIPRAP CL.I 26"	25.000 TON	_____	_____	_____	_____
0280	603	27102 REGULAR SEED	59.000 LB	_____	_____	_____	_____
0290	603	27103 OVERSEEDING	37.000 LB	_____	_____	_____	_____
0300	603	27104 LEGUME SEED	8.000 LB	_____	_____	_____	_____
0310	603	27105 LEGUME OVERSEEDING	5.000 LB	_____	_____	_____	_____
0320	603	27210 FERTILIZER 10-20-10	198.000 LB	_____	_____	_____	_____
0330	603	27250 LIME	1.300 TON	_____	_____	_____	_____
0340	606	27321 ROLLED EROSION CTRL PRODUCT EC-2 TYPE 4	172.000 SY	_____	_____	_____	_____
0350	303	27415 CHECK DAM ROCK TY. II	7.000 EA	_____	_____	_____	_____
0360	303	27422 DEWATERING BASIN EC-8	2.000 EA	_____	_____	_____	_____
0370	303	27430 SILTATION CONTROL EXCAVATION	100.000 CY	_____	_____	_____	_____
0380	303	27500 GEOTEXTILE FABRIC	136.000 SY	_____	_____	_____	_____
0390	303	27505 TEMP. SILT FENCE TYPE A	538.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000117882D43      Oversight/State Project No.: 0707-056-733, D643  
 Order No.: J18      Federal Project No.: NONE

Contractor: \_\_\_\_\_

SECTION: 0001      REGULAR ITEMS

Cat Alt Set ID:      Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0400	413	67900 DISM.& REM. EX. STR. Remove Str. No. 6119	LUMP SUM	LUMP SUM		_____.	_____
0410	411	68476 ENV.& WORK. PROTECTION Removal and Disposal of Type B Structure	LUMP SUM	LUMP SUM		_____.	_____
0420	411	68490 DISPOSAL OF MATERIAL Disposal of Type B Structure (No. 6119)	LUMP SUM	LUMP SUM		_____.	_____
<b>Section: 0001</b>				<b>Total:</b>		_____.	_____
				<b>Total Bid:</b>		_____.	_____