

Schedule of Items

Proposal ID: CM523PME121423 Oversight/State Project No.: PM5E-047-760, P401

Order No.: 509

Federal Project No.: PM05(521)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	312	10416 LIQUID ASPHALT	1,785.000 GAL	_____	_____	_____	_____
0020	310	10417 TACK COAT	47,992.000 GAL	_____	_____	_____	_____
0030	315	10497 PAVEMENT NS PAVEMENT, PAVEMENT CRACK SEAL TY B	200.000 LB	_____	_____	_____	_____
0040	315	11070 SAW-CUT ASPH CONC SAW CUT ASPHALT PAVEMENT 2" DEPTH	450.000 LF	_____	_____	_____	_____
0050	ATTD	15332 TRAVEL LANE PATCHING (PATCH MIX TYPE) ASPHALT PATCH w/ IM-19.0A	491.950 TON	_____	_____	_____	_____
0060	ATTD	16242 AGGR. BASE MATL. TY. I OR II NO. 21A OR 21B	797.810 TON	_____	_____	_____	_____
0070	315	16335 ASPHALT CONC. TY. SM-9.5A	7,513.150 TON	_____	_____	_____	_____
0080	315	16340 ASPHALT CONC. TY. SM-9.5D	6,744.270 TON	_____	_____	_____	_____
0090	315	16355 ASPHALT CONC. TY. SM- 12.5D	31,115.250 TON	_____	_____	_____	_____
0100	315	16374 ASPH. CONC. TY. IM-19.0D T	61.950 TON	_____	_____	_____	_____
0110	515	16516 FLEXIBLE PAVE. TIE-IN PLANING 0" - 2"	281.600 SY	_____	_____	_____	_____
0120	515	16522 FLEXIBLE PAVEMENT PLANING 0" - 2"	435,825.400 SY	_____	_____	_____	_____

Schedule of Items

Proposal ID: CM523PME121423 Oversight/State Project No.: PM5E-047-760, P401

Order No.: 509

Federal Project No.: PM05(521)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0130	400	24265 MAINTENANCE OF TRAFFIC PLANT MIX	LUMP SUM	LUMP SUM			
0140	512	24282 FLAGGER SERVICE	600.000 HR				
0150	700	51615 14/1 ENCLOSED COND. CABLE	7,972.000 LF				
0160	703	51912 LOOP SAW CUT 3/8"	2,352.000 LF				
0170	703	51913 LOOP SAWCUT 5/8"	320.000 LF				
0180	704	54032 TYPE B CLASS I PVMT LINE MRKG 4"	345,527.000 LF				
0190	704	54034 TYPE B CLASS I PVMT LINE MRKG 6"	74,052.000 LF				
0200	704	54037 TYPE B CLASS I PVMT LINE MRKG 8"	82.000 LF				
0210	704	54040 TYPE B CLASS I PVMT LINE MRKG 12"	624.000 LF				
0220	704	54042 TYPE B CLASS I PAVE. LINE MARKING 24"	3,123.000 LF				
0230	ATTD	54219 INLAID PAVEMENT MARKER ASPHALT	1,273.000 EA				
0240	704	54392 PVMT MSG. MARK. "ONLY" TY B, CL. I, 6'	5.000 EA				

Schedule of Items

Proposal ID: CM523PME121423 Oversight/State Project No.: PM5E-047-760, P401

Order No.: 509

Federal Project No.: PM05(521)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0250	704	54395 PVMT MSG. MARK. "SCHOOL" TY B, CL I, 6'	3.000 EA	_____	_____	_____	_____
0260	704	54398 PVMT MESSAGE MARK. R/R CROSSING TY B, CL I	4.000 EA	_____	_____	_____	_____
0270	512	54428 TEMP. PVMT MRKG, TY. A, 4"	304,870.000 LF	_____	_____	_____	_____
0280	512	54430 TEMP. PVMT MRKG, TY. A, 6"	73,721.000 LF	_____	_____	_____	_____
0290	512	54436 TEMP. PVMT MRKG, TY. A, 12"	596.000 LF	_____	_____	_____	_____
0300	704	54571 PVMT SYMB MRKG THRU ARROW TY B, CL I	11.000 EA	_____	_____	_____	_____
0310	704	54574 PVMT SYMB MRKG SGL TURN ARROW TY B, CL I	295.000 EA	_____	_____	_____	_____
0320	704	54577 PVMT SYMB MRKG DBL TURN ARROW THRU/LT OR RT TY B, CL I	12.000 EA	_____	_____	_____	_____
0330	704	54621 PVMT SYMB MRKG YIELD (1' X 1.5') TY B, CL I	14.000 EA	_____	_____	_____	_____
0340	700	56021 1" PVC CONDUIT	170.000 LF	_____	_____	_____	_____
Section: 0001				Total:		_____	

Schedule of Items

Proposal ID: CM523PME121423 Oversight/State Project No.: PM5E-047-760, P401
 Order No.: 509 Federal Project No.: PM05(521)

Contractor: _____

SECTION: 0002 ALTERNATE ITEM

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0350	ATTD	00306 SELECT MATERIAL ALTERNATE SHOULDER MATERIAL	1.000 TON	_____	_____	_____	_____
Section: 0002				Total:		_____	_____
				Total Bid:		_____	_____