

Schedule of Items

Proposal ID: CM623PMT121874 Oversight/State Project No.: PM6T-966-F23,P401

Order No.: 613

Federal Project No.: PM06403

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	315	10700 RUMBLE STRIP CYLINDRICAL ASPHALT	59,240.000 LF	_____	_____	_____	_____
0020	315	16378 THIN HOT MIX ASPHALT CONCRETE	8,910.230 TON	_____	_____	_____	_____
0030	ATTD	16393 ASPH. CONC. PATCH TY. IM-19.0A	755.000 TON	_____	_____	_____	_____
0040	515	16522 FLEXIBLE PAVEMENT PLANING 0" - 2"	219,351.600 SY	_____	_____	_____	_____
0050	ATTD	24265 MAINTENANCE OF TRAFFIC PLANT MIX	LUMP SUM	LUMP SUM	_____	_____	_____
0060	512	24282 FLAGGER SERVICE	1,698.000 HR	_____	_____	_____	_____
0070	700	51615 14/1 ENCLOSED COND. CABLE	26,508.000 LF	_____	_____	_____	_____
0080	703	51912 LOOP SAW CUT 3/8"	10,314.000 LF	_____	_____	_____	_____
0090	703	51913 LOOP SAWCUT 5/8"	2,032.000 LF	_____	_____	_____	_____
0100	704	54032 TYPE B CLASS I PVMT LINE MRKG 4"	61,718.000 LF	_____	_____	_____	_____
0110	704	54034 TYPE B CLASS I PVMT LINE MRKG 6"	24,043.000 LF	_____	_____	_____	_____
0120	704	54042 TYPE B CLASS I PAVE. LINE MARKING 24"	3,275.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: CM623PMT121874 Oversight/State Project No.: PM6T-966-F23,P401

Order No.: 613

Federal Project No.: PM06403

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: _____ Cat Alt Mbr ID: _____

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0130	ATTD	54219 INLAID PAVEMENT MARKER ASPHALT	884.000 EA	_____	_____	_____	_____
0140	704	54392 PVMT MSG. MARK. "ONLY" TY B, CL. I, 6'	5.000 EA	_____	_____	_____	_____
0150	512	54428 TEMP. PVMT MRKG, TY. A, 4"	171,522.000 LF	_____	_____	_____	_____
0160	704	54574 PVMT SYMB MRKG SGL TURN ARROW TY B, CL I	127.000 EA	_____	_____	_____	_____
0170	704	54577 PVMT SYMB MRKG DBL TURN ARROW THRU/LT OR RT TY B, CL I	13.000 EA	_____	_____	_____	_____
0180	704	54626 PVMT SYMB MRKG YIELD (2' X 3') TY B, CL II	20.000 EA	_____	_____	_____	_____
0190	700	56021 1" PVC CONDUIT	1,140.000 LF	_____	_____	_____	_____
Section: 0001				Total:		_____	
				Total Bid:		_____	