

Schedule of Items

Proposal ID: C0000115614C01

Oversight/State Project No.: 0001-088-741,C501

Order No.: J02

Federal Project No.: CMAQ-5111(439)

Contractor: \_\_\_\_\_

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	513	00100 MOBILIZATION	LUMP SUM	LUMP SUM			
0020	517	00101 CONSTRUCTION SURVEYING CONSTRUCTION	LUMP SUM	LUMP SUM			
0030	301	00110 CLEARING AND GRUBBING	LUMP SUM	LUMP SUM			
0040	303	00120 REGULAR EXCAVATION	1,592.000 CY				
0050	501	00588 UNDERDRAIN UD-4	700.000 LF				
0060	302	01152 15" CONC. PIPE	313.000 LF				
0070	302	01182 18" CONC. PIPE	173.000 LF				
0080	302	01242 24" CONC. PIPE	17.000 LF				
0090	ATTD	02112 DRAINAGE TIMBER WEIR	1.000 EA				
0100	302	06181 18" END SECTION ES-1	1.000 EA				
0110	302	06745 DROP INLET DI-2A	1.000 EA				
0120	302	06817 DROP INLET DI-3B,L=4'	2.000 EA				
0130	302	06818 DROP INLET DI-3B,L=6'	3.000 EA				
0140	302	06819 DROP INLET DI-3B,L=8'	1.000 EA				

Schedule of Items

Proposal ID: C0000115614C01 Oversight/State Project No.: 0001-088-741,C501

Order No.: J02

Federal Project No.: CMAQ-5111(439)

Contractor: \_\_\_\_\_

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0150	302	06820 DROP INLET DI-3B,L=10'	1.000 EA	_____	_____	_____	_____
0160	302	06822 DROP INLET DI-3B,L=14'	1.000 EA	_____	_____	_____	_____
0170	302	06836 DROP INLET DI-3C,L=8'	1.000 EA	_____	_____	_____	_____
0180	302	09056 MANHOLE MH-1 OR 2	6.300 LF	_____	_____	_____	_____
0190	302	09057 FRAME & COVER MH-1	2.000 EA	_____	_____	_____	_____
0200	414	09150 EROSION CONTROL STONE CLASS I, EC-1	18.000 TON	_____	_____	_____	_____
0210	308	10128 AGGR. BASE MATL. TY. I NO. 21B	1,422.000 TON	_____	_____	_____	_____
0220	315	10609 ASPHALT CONCRETE TY. SM-12.5E	1,202.000 TON	_____	_____	_____	_____
0230	315	10610 ASPHALT CONCRETE TY. IM-19.0A	301.000 TON	_____	_____	_____	_____
0240	515	10628 FLEXIBLE PAVEMENT PLANING 0" - 2"	7,129.000 SY	_____	_____	_____	_____
0250	315	10642 ASPHALT CONCRETE TY. BM-25.0A	635.000 TON	_____	_____	_____	_____
0260	315	11070 SAW-CUT ASPH CONC FULL DEPTH	2,502.000 LF	_____	_____	_____	_____
0270	502	12020 STD. CURB CG-2	460.000 LF	_____	_____	_____	_____

## Schedule of Items

Proposal ID: C0000115614C01 Oversight/State Project No.: 0001-088-741,C501

Order No.: J02

Federal Project No.: CMAQ-5111(439)

Contractor: \_\_\_\_\_

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0280	502	12022 RADIAL CURB CG-2	50.000 LF	_____	_____	_____	_____
0290	502	12600 STD. COMB. CURB & GUTTER CG-6	1,074.000 LF	_____	_____	_____	_____
0300	502	12610 RADIAL COMB. CURB & GUTTER CG-6	315.000 LF	_____	_____	_____	_____
0310	502	13102 RADIAL COMB. CURB & GUTTER CG-11	376.000 LF	_____	_____	_____	_____
0320	504	13108 CG-12 DETECTABLE WARNING SURFACE	32.000 SY	_____	_____	_____	_____
0330	504	13220 HYDRAULIC CEMENT CONC. SIDEWALK 4"	517.000 SY	_____	_____	_____	_____
0340	502	13244 SAW CUT H.C.C. ITEMS CURB, GUTTER, AND ENTRANCES	355.000 LF	_____	_____	_____	_____
0350	502	13244 SAW CUT H.C.C. ITEMS SIDEWALK	28.000 LF	_____	_____	_____	_____
0360	ATTD	14100 REMOVE SIDEWALK AND ENTRANCE	307.000 SY	_____	_____	_____	_____
0370	ATTD	14120 REMOVE COMB. CURB AND GUTTER	1,841.000 LF	_____	_____	_____	_____
0380	502	21020 MEDIAN STRIP MS-1	40.000 SY	_____	_____	_____	_____
0390	502	21110 MEDIAN STRIP MS-1A	9.000 SY	_____	_____	_____	_____

## Schedule of Items

Proposal ID: C0000115614C01 Oversight/State Project No.: 0001-088-741,C501

Order No.: J02

Federal Project No.: CMAQ-5111(439)

Contractor: \_\_\_\_\_

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0400	507	22501 FENCE FE-W1	60.000 LF	_____	_____	_____	_____
0410	507	22541 LINE BRACE UNIT FE-W1,FE- W2	1.000 EA	_____	_____	_____	_____
0420	ATTD	23600 FENCE MODIFY PARCEL 002	30.000 LF	_____	_____	_____	_____
0430	511	24100 ALLAYING DUST	320.000 HR	_____	_____	_____	_____
0440	512	24150 TYPE 3 BARRICADE 4'	5.000 EA	_____	_____	_____	_____
0450	512	24160 TEMPORARY (CONSTRUCTION) SIGN	128.750 SF	_____	_____	_____	_____
0460	512	24272 TRUCK MOUNTED ATTENUATOR	3,552.000 HR	_____	_____	_____	_____
0470	512	24278 GROUP 2 CHANNELIZING DEVICES	20,188.000 DAY	_____	_____	_____	_____
0480	512	24279 PORTABLE CHANGEABLE MESSAGE SIGN	2,016.000 HR	_____	_____	_____	_____
0490	512	24281 ELECTRONIC ARROW BOARD	3,552.000 HR	_____	_____	_____	_____
0500	512	24282 FLAGGER SERVICE	160.000 HR	_____	_____	_____	_____
0510	512	24332 MODIFY SIGNAL RTE 1/MARKET ST	LUMP SUM	LUMP SUM	_____	_____	_____
0520	508	24430 DEMOLITION OF PAVEMENT FLEXIBLE	2,019.000 SY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000115614C01      Oversight/State Project No.: 0001-088-741,C501  
Order No.: J02      Federal Project No.: CMAQ-5111(439)

Contractor: \_\_\_\_\_

SECTION: 0001      REGULAR BID ITEMS

Cat Alt Set ID:      Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0530	507	24602 REMOVE EXIST. FENCE FE	95.000 LF	_____	_____	_____	_____
0540	510	24831 ADJUST EXIST.DROP INLET STRUCTURE 5-10	1.000 EA	_____	_____	_____	_____
0550	414	26127 DRY RIPRAP CL.I 26"	15.000 TON	_____	_____	_____	_____
0560	602	27022 TOPSOIL CLASS B 2"	0.370 ACRE	_____	_____	_____	_____
0570	603	27101 TEMPORARY SEED	37.000 LB	_____	_____	_____	_____
0580	603	27102 REGULAR SEED	58.000 LB	_____	_____	_____	_____
0590	603	27103 OVERSEEDING	46.000 LB	_____	_____	_____	_____
0600	603	27111 HYDRAULIC EROSION CONTROL PRODUCT TYPE 2	2,178.000 SY	_____	_____	_____	_____
0610	603	27112 HYDRAULIC EROSION CONTROL PRODUCT TYPE 3	1,851.000 SY	_____	_____	_____	_____
0620	603	27230 FERTILIZER NITROGEN - N	37.000 LB	_____	_____	_____	_____
0630	603	27231 FERTILIZER PHOSPHOROUS - P	26.000 LB	_____	_____	_____	_____
0640	603	27232 FERTILIZER POTASSIUM - K	26.000 LB	_____	_____	_____	_____
0650	603	27250 LIME	2.030 TON	_____	_____	_____	_____

## Schedule of Items

Proposal ID: C0000115614C01 Oversight/State Project No.: 0001-088-741,C501

Order No.: J02

Federal Project No.: CMAQ-5111(439)

Contractor: \_\_\_\_\_

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0660	606	27318 ROLLED EROSION CTRL PRODUCT EC-2 TYPE 1	36.000 SY	_____	_____	_____	_____
0670	303	27415 CHECK DAM ROCK TY. II	1.000 EA	_____	_____	_____	_____
0680	303	27430 SILTATION CONTROL EXCAVATION	171.000 CY	_____	_____	_____	_____
0690	303	27461 INLET PROTECTION TYPE B	11.000 EA	_____	_____	_____	_____
0700	303	27505 TEMP. SILT FENCE TYPE A	651.000 LF	_____	_____	_____	_____
0710	ATTD	27553 PERMANENT SWM FACILITY AS-BUILT DOCUMENTATION CONSTRUCTION RECORDS DOCUMENTATION	LUMP SUM	LUMP SUM	_____	_____	_____
0720	520	40003 1" WATER SERVICE LINE	23.000 LF	_____	_____	_____	_____
0730	520	40006 2" WATER SERVICE LINE	21.000 LF	_____	_____	_____	_____
0740	520	40041 4" DI WATER MAIN	15.000 LF	_____	_____	_____	_____
0750	520	40061 6" DI WATER MAIN	221.000 LF	_____	_____	_____	_____
0760	520	40081 8" DI WATER MAIN	122.000 LF	_____	_____	_____	_____
0770	520	40121 12" DI WATER MAIN	476.000 LF	_____	_____	_____	_____
0780	520	40161 16" DI WATER MAIN	4.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000115614C01 Oversight/State Project No.: 0001-088-741,C501

Order No.: J02

Federal Project No.: CMAQ-5111(439)

Contractor: \_\_\_\_\_

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0790	ATTD	40380 WATER MAIN 3" DI	4.000 LF	_____	_____	_____	_____
0800	520	40406 16" BEND	1.000 EA	_____	_____	_____	_____
0810	520	40460 16" REDUCER	1.000 EA	_____	_____	_____	_____
0820	520	41004 4" GATE VALVE & BOX	2.000 EA	_____	_____	_____	_____
0830	520	41006 6" GATE VALVE & BOX	6.000 EA	_____	_____	_____	_____
0840	520	41008 8" GATE VALVE & BOX	1.000 EA	_____	_____	_____	_____
0850	520	41012 12" GATE VALVE & BOX	8.000 EA	_____	_____	_____	_____
0860	510	41104 ADJUST EXIST. VALVE BOX	1.000 EA	_____	_____	_____	_____
0870	520	41820 FIRE HYDRANT	3.000 EA	_____	_____	_____	_____
0880	520	41830 1" AIR RELEASE VALVE & BOX	1.000 EA	_____	_____	_____	_____
0890	520	41968 1" WATER METER BOX & YOKE	1.000 EA	_____	_____	_____	_____
0900	ATTD	41982 WATER FACILITIES 2" WATER METER BOX AND YOKE	1.000 EA	_____	_____	_____	_____
0910	ATTD	41983 WATER FACILITIES 3" WATER METER VAULT	LUMP SUM	LUMP SUM	_____	_____	_____
0920	510	42765 ADJUST EXIST FRAME & COVER	1.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000115614C01 Oversight/State Project No.: 0001-088-741,C501

Order No.: J02

Federal Project No.: CMAQ-5111(439)

Contractor: \_\_\_\_\_

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0930	520	42846 6" SEWER CLEANOUT	4.000 EA	_____	_____	_____	_____
0940	520	45584 24" JACKED STEEL ENCASEMENT PIPE	99.000 LF	_____	_____	_____	_____
0950	509	45640 FLOWABLE BACKFILL UTILITY	6.000 CY	_____	_____	_____	_____
0960	701	50108 SIGN PANEL	142.250 SF	_____	_____	_____	_____
0970	700	50300 REMOVE EXISTING 1 POST SIGN STRUCTURE	10.000 EA	_____	_____	_____	_____
0980	700	50302 REMOVE EXISTING 2 POST SIGN STRUCTURE	1.000 EA	_____	_____	_____	_____
0990	700	50320 REMOVE EXISTING 1 POST SIGN PANEL	16.000 EA	_____	_____	_____	_____
1000	700	50322 REMOVE EXISTING 2 POST SIGN PANEL	1.000 EA	_____	_____	_____	_____
1010	700	50326 REMOVE EXISTING OVERHEAD SIGNAL SIGN PANEL	2.000 EA	_____	_____	_____	_____
1020	700	50340 RELOCATE EXISTING 1 POST GROUND MOUNTED SIGN PANEL	2.000 EA	_____	_____	_____	_____
1030	700	50430 SIGN POST STP-1, 2", 14 GAUGE	144.000 LF	_____	_____	_____	_____
1040	700	50432 SIGN POST STP-1, 2 3/16", 10 GAUGE	6.000 LF	_____	_____	_____	_____



Schedule of Items

Proposal ID: C0000115614C01 Oversight/State Project No.: 0001-088-741,C501

Order No.: J02

Federal Project No.: CMAQ-5111(439)

Contractor: \_\_\_\_\_

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1050	700	50434 SIGN POST STP-1, 2 1/2", 10 GAUGE	24.000 LF	_____	_____	_____	_____
1060	700	50436 SIGN POST STP-1, 2 1/2", 12 GAUGE	24.000 LF	_____	_____	_____	_____
1070	700	50485 CONCRETE SIGN FOUNDATION STP-1, TYPE A	14.000 EA	_____	_____	_____	_____
1080	700	50486 CONCRETE SIGN FOUNDATION STP-1, TYPE B	2.000 EA	_____	_____	_____	_____
1090	703	51185 TRAFFIC SIGNAL HEAD SECTION 12" HVS BACKPLATE	12.000 EA	_____	_____	_____	_____
1100	700	51607 14/7 CONDUCTOR CABLE	50.000 LF	_____	_____	_____	_____
1110	703	51933 REMOVE EXISTING POLE	1.000 EA	_____	_____	_____	_____
1120	703	51934 REMOVE EXISTING FOUNDATION	1.000 EA	_____	_____	_____	_____
1130	703	51935 REMOVE EXISTING SIGNAL HEAD	2.000 EA	_____	_____	_____	_____
1140	704	54032 TYPE B CLASS I PVMT LINE MRKG 4"	4,326.000 LF	_____	_____	_____	_____
1150	704	54037 TYPE B CLASS I PVMT LINE MRKG 8"	322.000 LF	_____	_____	_____	_____
1160	704	54042 TYPE B CLASS I PAVE. LINE MARKING 24"	652.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000115614C01 Oversight/State Project No.: 0001-088-741,C501

Order No.: J02

Federal Project No.: CMAQ-5111(439)

Contractor: \_\_\_\_\_

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1170	704	54101 PAVEMENT MARKING PERFORM 15' ROUTE SHIELD (1)	2.000 EA	_____	_____	_____	_____
1180	704	54101 PAVEMENT MARKING PERFORM 15' ROUTE SHIELD (I-95)	2.000 EA	_____	_____	_____	_____
1190	512	54105 ERADICATE EXIST. LINEAR PVMT MARKING	1,053.000 LF	_____	_____	_____	_____
1200	512	54106 ERADICATE EXIST. NONLINEAR PVMT MRKG	51.000 SF	_____	_____	_____	_____
1210	ATTD	54219 INLAID PAVEMENT MARKER ASPHALT	33.000 EA	_____	_____	_____	_____
1220	704	54392 PVMT MSG. MARK. "ONLY" TY B, CL. I, 6'	1.000 EA	_____	_____	_____	_____
1230	704	54402 PAVE. MESSAGE MARKING 10' CHARACTERS (NORTH & SOUTH)	20.000 EA	_____	_____	_____	_____
1240	512	54428 TEMP. PVMT MRKG, TY. A, 4"	615.000 LF	_____	_____	_____	_____
1250	512	54440 TEMP. PVMT MRKG, TY. A, 24"	76.000 LF	_____	_____	_____	_____
1260	512	54457 TEMP. PVMT SYMBOL MRKG SINGLE TURN ARROW TY. A	3.000 EA	_____	_____	_____	_____
1270	704	54574 PVMT SYMB MRKG SGL TURN ARROW TY B, CL I	10.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000115614C01

Oversight/State Project No.: 0001-088-741,C501

Order No.: J02

Federal Project No.: CMAQ-5111(439)

Contractor: \_\_\_\_\_

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1280	704	54577 PVMT SYMB MRKG DBL TURN ARROW THRU/LT OR RT TY B, CL I	5.000 EA				
1290	516	70000 DEMO. OF BLDG. D3	LUMP SUM	LUMP SUM			
1300	516	70000 DEMO. OF BLDG. D700	LUMP SUM	LUMP SUM			
1310	516	70000 DEMO. OF BLDG. D701	LUMP SUM	LUMP SUM			
1320	516	70000 DEMO. OF BLDG. D702	LUMP SUM	LUMP SUM			
1330	516	70000 DEMO. OF BLDG. D703	LUMP SUM	LUMP SUM			
1340	516	70000 DEMO. OF BLDG. D706	LUMP SUM	LUMP SUM			
1350	516	70000 DEMO. OF BLDG. D707	LUMP SUM	LUMP SUM			
1360	516	70000 DEMO. OF BLDG. D901	LUMP SUM	LUMP SUM			
1370	516	70000 DEMO. OF BLDG. D903	LUMP SUM	LUMP SUM			
1380	516	70000 DEMO. OF BLDG. D904	LUMP SUM	LUMP SUM			
1390	516	70000 DEMO. OF BLDG. D905	LUMP SUM	LUMP SUM			
1400	516	70000 DEMO. OF BLDG. D908	LUMP SUM	LUMP SUM			
1410	516	70000 DEMO. OF BLDG. D909	LUMP SUM	LUMP SUM			

Schedule of Items

Proposal ID: C0000115614C01      Oversight/State Project No.: 0001-088-741,C501  
 Order No.: J02      Federal Project No.: CMAQ-5111(439)

Contractor: \_\_\_\_\_

SECTION: 0001      REGULAR BID ITEMS

Cat Alt Set ID:      Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1420	516	70000 DEMO. OF BLDG. D910	LUMP SUM	LUMP SUM			
1430	516	70000 DEMO. OF BLDG. D913	LUMP SUM	LUMP SUM			
1440	516	70000 DEMO. OF BLDG. D914	LUMP SUM	LUMP SUM			
1450	516	70000 DEMO. OF BLDG. D915	LUMP SUM	LUMP SUM			
<b>Section: 0001</b>				<b>Total:</b>			
				<b>Total Bid:</b>			