

Schedule of Items

Proposal ID: CM423PM6122067 Oversight/State Project No.: PM46-964-F23, P401

Order No.: 411

Federal Project No.: PM04(516)

Contractor: \_\_\_\_\_

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	307	10011 HYDRAULIC CEMENT	1,040.000 TON	_____	_____	_____	_____
0020	310	10417 TACK COAT	4,662.000 GAL	_____	_____	_____	_____
0030	ATTD	16161 MODIFIED SINGLE SEAL	6,195.000 SY	_____	_____	_____	_____
0040	ATTD	16242 AGGR. BASE MATL. TY. I OR II NO. 21A OR 21B	671.150 TON	_____	_____	_____	_____
0050	315	16340 ASPHALT CONC. TY. SM-9.5D	2,959.960 TON	_____	_____	_____	_____
0060	315	16360 ASPHALT CONC. TY. SM-12.5E	1,264.210 TON	_____	_____	_____	_____
0070	ATTD	16368 PAVEMENT SHOULDER WEDGE PREP.	32,736.000 LF	_____	_____	_____	_____
0080	515	16522 FLEXIBLE PAVEMENT PLANING 0" - 2"	11,938.670 SY	_____	_____	_____	_____
0090	ATTD	16544 FULL DEPTH RECLAMATION FULL DEPTH RECLAMATION 10"	6,195.000 SY	_____	_____	_____	_____
0100	ATTD	16544 FULL DEPTH RECLAMATION FULL DEPTH RECLAMATION 9"	34,848.000 SY	_____	_____	_____	_____
0110	ATTD	24262 PORTABLE TEMPORARY RUMBLE STRIP ARRAY	21.000 DAY	_____	_____	_____	_____
0120	512	24265 MAINTENANCE OF TRAFFIC MAINTENANCE OF TRAFFIC	LUMP SUM	LUMP SUM	_____	_____	_____

Schedule of Items

Proposal ID: CM423PM6122067 Oversight/State Project No.: PM46-964-F23, P401

Order No.: 411

Federal Project No.: PM04(516)

Contractor: \_\_\_\_\_

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: \_\_\_\_\_ Cat Alt Mbr ID: \_\_\_\_\_

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0130	512	24282 FLAGGER SERVICE	479.000 HR	_____	_____	_____	_____
0140	512	24360 SAFETY UNIFORM FLAGGERS	44.000 HR	_____	_____	_____	_____
0150	508	24410 DEMOLITION OF PAVEMENT COMBINATION	563.000 SY	_____	_____	_____	_____
0160	704	54032 TYPE B CLASS I PVMT LINE MRKG 4"	8,103.000 LF	_____	_____	_____	_____
0170	704	54042 TYPE B CLASS I PAVE. LINE MARKING 24"	245.000 LF	_____	_____	_____	_____
0180	704	54395 PVMT MSG. MARK. "SCHOOL" TY B, CL I, 6'	1.000 EA	_____	_____	_____	_____
0190	512	54428 TEMP. PVMT MRKG, TY. A, 4"	8,123.000 LF	_____	_____	_____	_____
0200	512	54436 TEMP. PVMT MRKG, TY. A, 12"	125.000 LF	_____	_____	_____	_____
0210	704	54574 PVMT SYMB MRKG SGL TURN ARROW TY B, CL I	25.000 EA	_____	_____	_____	_____
<b>Section: 0001</b>				<b>Total:</b>	_____	_____	_____

Schedule of Items

Proposal ID: CM423PM6122067    Oversight/State Project No.: PM46-964-F23, P401  
 Order No.: 411    Federal Project No.: PM04(516)

Contractor: \_\_\_\_\_

SECTION: 0002    ALTERNATE ITEM

Cat Alt Set ID:    Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0220	ATTD	00306 SELECT MATERIAL ALTERNATE SHOULDER MATERIAL	1.000 TON	_____	_____	_____	_____
<b>Section: 0002</b>				<b>Total:</b>		_____	_____
				<b>Total Bid:</b>		_____	_____