

Schedule of Items

Proposal ID: C0000120900N01 Oversight/State Project No.: 9999-962-697,N501

Order No.: J43

Federal Project No.: HSIP-962-2(123)

Contractor: \_\_\_\_\_

SECTION: 0001 TRAFFIC ITEMS

Cat Alt Set ID: \_\_\_\_\_ Cat Alt Mbr ID: \_\_\_\_\_

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	513	00100 MOBILIZATION	LUMP SUM	LUMP SUM			
0020	ATTD	24262 PORTABLE TEMPORARY RUMBLE STRIP ARRAY	1,145.000 DAY				
0030	512	24272 TRUCK MOUNTED ATTENUATOR	1,070.000 HR				
0040	512	24281 ELECTRONIC ARROW BOARD	129.000 HR				
0050	512	24282 FLAGGER SERVICE	2,884.000 HR				
0060	701	50108 SIGN PANEL	5,404.000 SF				
0070	700	50300 REMOVE EXISTING 1 POST SIGN STRUCTURE	60.000 EA				
0080	700	50430 SIGN POST STP-1, 2", 14 GAUGE	8,099.000 LF				
0090	700	50432 SIGN POST STP-1, 2 3/16", 10 GAUGE	30.000 LF				
0100	700	50434 SIGN POST STP-1, 2 1/2", 10 GAUGE	63.000 LF				
0110	700	50436 SIGN POST STP-1, 2 1/2", 12 GAUGE	542.000 LF				
0120	700	50487 CONCRETE SIGN FOUNDATION STP-1, TYPE C	5.000 EA				

Schedule of Items

Proposal ID: C0000120900N01

Oversight/State Project No.: 9999-962-697,N501

Order No.: J43

Federal Project No.: HSIP-962-2(123)

Contractor: \_\_\_\_\_

SECTION: 0001 TRAFFIC ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0130	700	50488 CONCRETE SIGN FOUNDATION STP-1, TYPE D	705.000 EA	_____	_____	_____	_____
0140	700	50489 CONCRETE SIGN FOUNDATION STP-1, TYPE E	42.000 EA	_____	_____	_____	_____
0150	704	54048 TYPE B CLASS II PAVE. LINE MARKING 24"	3,312.000 LF	_____	_____	_____	_____
<b>Section: 0001</b>				<b>Total:</b>	_____	_____	_____
				<b>Total Bid:</b>	_____	_____	_____