

## Schedule of Items

Proposal ID: C0000106175C01

Oversight/State Project No.: 0687-083-857,C501

Order No.: J32

Federal Project No.: STP-083-1(062)

Contractor: \_\_\_\_\_

SECTION: 0001

REGULAR ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	513	00100 MOBILIZATION	LUMP SUM	LUMP SUM			
0020	517	00101 CONSTRUCTION SURVEYING CONSTRUCTION	LUMP SUM	LUMP SUM			
0030	301	00110 CLEARING AND GRUBBING	LUMP SUM	LUMP SUM			
0040	303	00120 REGULAR EXCAVATION	195.000 CY				
0050	ATTD	00367 REINFORCED SOIL SLOPE TY. B CASE 1, 0.5:1 SLOPE	643.000 SF				
0060	501	00591 CROSSDRAIN CD-2	45.000 LF				
0070	302	01150 15" PIPE	22.000 LF				
0080	302	01156 STORM SEWER PIPE 15"	4.000 LF				
0090	302	06150 15" END SECTION ES-1 OR 2	2.000 EA				
0100	302	07506 DROP INLET DI-5	1.000 EA				
0110	502	09126 ENERGY DISSIPATOR EG-1A	1.000 EA				
0120	414	09150 EROSION CONTROL STONE CLASS I, EC-1	2.800 TON				
0130	302	09165 PIPE SPILLOUT PS-2	1.000 EA				
0140	502	09225 PAVED FLUME PG-4	5.200 SY				

Schedule of Items

Proposal ID: C0000106175C01 Oversight/State Project No.: 0687-083-857,C501

Order No.: J32

Federal Project No.: STP-083-1(062)

Contractor: \_\_\_\_\_

SECTION: 0001 REGULAR ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0150	308	10128 AGGR. BASE MATL. TY. I NO. 21B	267.000 TON	_____	_____	_____	_____
0160	310	10417 TACK COAT	2.000 GAL	_____	_____	_____	_____
0170	315	10607 ASPHALT CONCRETE TY. SM-12.5A	44.000 TON	_____	_____	_____	_____
0180	515	10628 FLEXIBLE PAVEMENT PLANING 0" - 2"	19.000 SY	_____	_____	_____	_____
0190	315 ATTD	11070 SAW-CUT ASPH CONC FULL DEPTH	69.000 LF	_____	_____	_____	_____
0200	502	12030 STD. CURB CG-3	18.000 LF	_____	_____	_____	_____
0210	502	12032 RADIAL CURB CG-3	10.000 LF	_____	_____	_____	_____
0220	504	13232 GEOTEXTILE DRAINAGE FABRIC	18.000 SY	_____	_____	_____	_____
0230	505	13281 GUARDRAIL GR-MGS1A	157.000 LF	_____	_____	_____	_____
0240	505	13284 RADIAL GUARDRAIL GR-MGS1A	177.000 LF	_____	_____	_____	_____
0250	505	13286 GUARDRAIL TERMINAL GR-MGS2	1.000 EA	_____	_____	_____	_____
0260	505	13394 FIXED OBJECT ATTACH. GR-FOA-5	1.000 EA	_____	_____	_____	_____
0270	502	13460 MEDIAN BARRIER MB-7D	27.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000106175C01

Oversight/State Project No.: 0687-083-857,C501

Order No.: J32

Federal Project No.: STP-083-1(062)

Contractor: \_\_\_\_\_

SECTION: 0001 REGULAR ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0280	512	13495 TRAF. BARR. SER. CONC. SINGLE FACE PAR.MB-10A	340.000 LF	_____	_____	_____	_____
0290	ATTD	16260 LIQUID ASPHALT MATL. CRS- 2L	134.000 GAL	_____	_____	_____	_____
0300	511	24100 ALLAYING DUST	200.000 HR	_____	_____	_____	_____
0310	512	24152 TYPE 3 BARRICADE 8'	4.000 EA	_____	_____	_____	_____
0320	512	24160 TEMPORARY (CONSTRUCTION) SIGN	218.000 SF	_____	_____	_____	_____
0330	ATTD	24262 PORTABLE TEMPORARY RUMBLE STRIP ARRAY	40.000 DAY	_____	_____	_____	_____
0340	512	24278 GROUP 2 CHANNELIZING DEVICES	27,549.000 DAY	_____	_____	_____	_____
0350	512	24282 FLAGGER SERVICE	6,084.000 HR	_____	_____	_____	_____
0360	508	24430 DEMOLITION OF PAVEMENT FLEXIBLE	299.000 SY	_____	_____	_____	_____
0370	505	24600 REMOVE EXISTING GUARDRAIL	398.000 LF	_____	_____	_____	_____
0380	514	25507 FIELD OFFICE TY.III	21.000 MO	_____	_____	_____	_____
0390	ATTD	25565 BASELINE PROGRESS SCHEDULE	LUMP SUM	LUMP SUM	_____	_____	_____

Schedule of Items

Proposal ID: C0000106175C01 Oversight/State Project No.: 0687-083-857,C501

Order No.: J32

Federal Project No.: STP-083-1(062)

Contractor: \_\_\_\_\_

SECTION: 0001 REGULAR ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0400	ATTD	25567 PROGRESS SCHEDULE UPDATES	19.000 EA	_____	_____	_____	_____
0410	414	26127 DRY RIPRAP CL.I 26"	22.600 TON	_____	_____	_____	_____
0420	602	27024 TOPSOIL 3" TOPSOIL	0.140 ACRE	_____	_____	_____	_____
0430	603	27101 TEMPORARY SEED	23.000 LB	_____	_____	_____	_____
0440	603	27102 REGULAR SEED	25.000 LB	_____	_____	_____	_____
0450	603	27103 OVERSEEDING	20.000 LB	_____	_____	_____	_____
0460	603	27104 LEGUME SEED	1.000 LB	_____	_____	_____	_____
0470	603	27105 LEGUME OVERSEEDING	1.000 LB	_____	_____	_____	_____
0480	603	27111 HYDRAULIC EROSION CONTROL PRODUCT TYPE 2	581.000 SY	_____	_____	_____	_____
0490	603	27112 HYDRAULIC EROSION CONTROL PRODUCT TYPE 3	1,333.000 SY	_____	_____	_____	_____
0500	603	27230 FERTILIZER NITROGEN - N	15.000 LB	_____	_____	_____	_____
0510	603	27231 FERTILIZER PHOSPHOROUS - P	21.000 LB	_____	_____	_____	_____
0520	603	27232 FERTILIZER POTASSIUM - K	11.000 LB	_____	_____	_____	_____
0530	603	27250 LIME	1.000 TON	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000106175C01 Oversight/State Project No.: 0687-083-857,C501

Order No.: J32

Federal Project No.: STP-083-1(062)

Contractor: \_\_\_\_\_

SECTION: 0001 REGULAR ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0540	606	27318 ROLLED EROSION CTRL PRODUCT EC-2 TYPE 1	30.000 SY	_____	_____	_____	_____
0550	606	27325 ROLLED EROSION CTRL PRODUCT EC-3 TYPE 1	61.000 SY	_____	_____	_____	_____
0560	303	27410 CHECK DAM, ROCK TY. I	1.000 EA	_____	_____	_____	_____
0570	303	27415 CHECK DAM ROCK TY. II	7.000 EA	_____	_____	_____	_____
0580	303	27430 SILTATION CONTROL EXCAVATION	161.000 CY	_____	_____	_____	_____
0590	608	27440 MOWING	100.000 HR	_____	_____	_____	_____
0600	303	27451 INLET PROTECTION TYPE A	1.000 EA	_____	_____	_____	_____
0610	303	27505 TEMP. SILT FENCE TYPE A	794.000 LF	_____	_____	_____	_____
0620	303	27580 TEMP. SEDIMENT BASIN EXCAVATION	4.000 CY	_____	_____	_____	_____
0630	302	39011 HYDRO. CONTROL FEATURE Level Spreader	1.000 EA	_____	_____	_____	_____
0640	520	40002 3/4" WATER SERVICE LINE	100.000 LF	_____	_____	_____	_____
0650	510	41976 RELOC. EXIST. WATER METER & BOX	1.000 EA	_____	_____	_____	_____
0660	701	50108 SIGN PANEL	65.000 SF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000106175C01 Oversight/State Project No.: 0687-083-857,C501

Order No.: J32

Federal Project No.: STP-083-1(062)

Contractor: \_\_\_\_\_

SECTION: 0001 REGULAR ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0670	700	50430 SIGN POST STP-1, 2", 14 GAUGE	20.000 LF	_____	_____	_____	_____
0680	700	50460 CONC. FOUND. STP-2, TYPE A	1.000 EA	_____	_____	_____	_____
0690	700	50902 TRAFFIC SIGN Signing LS	1.000 EA	_____	_____	_____	_____
0700	703	51031 LOCAL CONTROLLER, TY. B	1.000 EA	_____	_____	_____	_____
0710	700	51170 ELECTRICAL SERVICE SE-5	1.000 EA	_____	_____	_____	_____
0720	703	51185 TRAFFIC SIGNAL HEAD SECTION 12" HVS BACKPLATE	12.000 EA	_____	_____	_____	_____
0730	700	51460 WOOD POLE CL. 4 40'	5.000 EA	_____	_____	_____	_____
0740	703	51507 VIDEO DETECTION CAMERA	2.000 EA	_____	_____	_____	_____
0750	703	51508 VIDEO DETECTION CABLE	2,100.000 LF	_____	_____	_____	_____
0760	703	51509 VIDEO DETECTION SYSTEM	1.000 EA	_____	_____	_____	_____
0770	700	51598 8/3 CONDUCTOR CABLE	2,100.000 LF	_____	_____	_____	_____
0780	700	51602 14/4 CONDUCTOR CABLE	2,100.000 LF	_____	_____	_____	_____
0790	703	51824 HANGER ASSEMBLY SW-1, ONE WAY	4.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000106175C01 Oversight/State Project No.: 0687-083-857,C501

Order No.: J32

Federal Project No.: STP-083-1(062)

Contractor: \_\_\_\_\_

SECTION: 0001 REGULAR ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0800	704	54032 TYPE B CLASS I PVMT LINE MRKG 4"	400.000 LF	_____	_____	_____	_____
0810	704	54075 TYPE B CLASS VI PVMT LINE MRKG 4"	390.000 LF	_____	_____	_____	_____
0820	512	54240 TEMP. PAVE. MARKER 1 WAY	36.000 EA	_____	_____	_____	_____
0830	512	54428 TEMP. PVMT MRKG, TY. A, 4"	200.000 LF	_____	_____	_____	_____
0840	512	54440 TEMP. PVMT MRKG, TY. A, 24"	20.000 LF	_____	_____	_____	_____
0850	512	54466 TYPE E TEMP. PVMT MRKG 6"	9,207.000 LF	_____	_____	_____	_____
0860	512	54542 TYPE D, CLASS III TEMP. PVMT MRKG 4"	6,617.000 LF	_____	_____	_____	_____
0870	512	54544 TYPE D, CLASS III TEMP. PVMT MRKG 8"	1,320.000 LF	_____	_____	_____	_____
0880	512	54548 TYPE D, CLASS III TEMP. PVMT MRKG 24"	73.000 LF	_____	_____	_____	_____
0890	404	60409 CONC. CLASS A4 MOD. LOW SHRINKAGE	107.100 CY	_____	_____	_____	_____
0900	404	60490 BRIDGE DECK GROOVING	340.000 SY	_____	_____	_____	_____
0910	404	60495 COVER DEPTH SURVEY	340.000 SY	_____	_____	_____	_____
0920	406	61711 CORROSION RESISTANT REINF. STEEL CL. I	26,950.000 LB	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000106175C01 Oversight/State Project No.: 0687-083-857,C501

Order No.: J32

Federal Project No.: STP-083-1(062)

Contractor: \_\_\_\_\_

SECTION: 0001 REGULAR ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0930	407	61812 STR.STEEL PLATE GIRDER ASTM A709 GRADE 50W	LUMP SUM	LUMP SUM			
0940	410	62034 RAILING, CPSR 2 RAIL	350.000 LF				
0950	PLAN	62534 BRIDGE SUPERSTRUCTURE ELASTIC INCLUSION 17"	31.000 SY				
0960	ATTD	62536 BRIDGE SUPERSTRUCTURE TEMPORARY GIRDER SUPPORT	LUMP SUM	LUMP SUM			
0970	401	64011 STRUCTURE EXCAVATION	1,336.000 CY				
0980	401	64015 SELECT BACKFILL ABUTMENT ZONE	1,523.000 TON				
0990	401	64032 GEOCOMPOSITE WALL DRAIN	81.000 SY				
1000	401	64036 PIPE UNDERDRAIN 6"	92.000 LF				
1010	404	65013 CONCRETE CLASS A3	162.800 CY				
1020	406	65200 REINF. STEEL	15,320.000 LB				
1030	413	67900 DISM.& REM. EX. STR. DISMANTLE AND REMOVE EXISTING STRUCTURE	LUMP SUM	LUMP SUM			
1040	402	67904 BRIDGE INCIDENTALS TEMPORARY RETAINING STRUCTURE	LUMP SUM	LUMP SUM			



Schedule of Items

Proposal ID: C0000106175C01      Oversight/State Project No.: 0687-083-857,C501

Order No.: J32

Federal Project No.: STP-083-1(062)

Contractor: \_\_\_\_\_

SECTION: 0001                      REGULAR ITEMS

Cat Alt Set ID:                      Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1050	430	67910 NBIS ACCESS, UNDER BRIDGE NBIS ACCESS, UNDER BRIDGE (STR. B43)	2.000 DAY	_____	_____	_____	_____
1060	413	68476 ENV. & WORK. PROTECTION ENVIRONMENTAL & WORKER PROTECTION	LUMP SUM	LUMP SUM	_____	_____	_____
1070	413	68492 MATERIAL DISPOSAL MATERIAL DISPOSAL	LUMP SUM	LUMP SUM	_____	_____	_____
<b>Section: 0001</b>				<b>Total:</b>	_____	_____	_____
				<b>Total Bid:</b>	_____	_____	_____