

## Schedule of Items

Proposal ID: C0000119588T01

Oversight/State Project No.: HSIP-963-528, N501

Order No.: H90

Federal Project No.: HSIP-963-3(070)

Contractor: \_\_\_\_\_

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	ATTD	24262 PORTABLE TEMPORARY RUMBLE STRIP ARRAY	225.000 DAY	_____	_____	_____	_____
0020	512	24272 TRUCK MOUNTED ATTENUATOR	600.000 HR	_____	_____	_____	_____
0030	512	24281 ELECTRONIC ARROW BOARD	50.000 HR	_____	_____	_____	_____
0040	512	24282 FLAGGER SERVICE	1,500.000 HR	_____	_____	_____	_____
0050	701	50108 SIGN PANEL	4,118.000 SF	_____	_____	_____	_____
0060	700	50300 REMOVE EXISTING 1 POST SIGN STRUCTURE	139.000 EA	_____	_____	_____	_____
0070	700	50302 REMOVE EXISTING 2 POST SIGN STRUCTURE	2.000 EA	_____	_____	_____	_____
0080	700	50320 REMOVE EXISTING 1 POST SIGN PANEL	3.000 EA	_____	_____	_____	_____
0090	700	50340 RELOCATE EXISTING 1 POST GROUND MOUNTED SIGN PANEL	1.000 EA	_____	_____	_____	_____
0100	700	50430 SIGN POST STP-1, 2", 14 GAUGE	891.000 LF	_____	_____	_____	_____
0110	700	50432 SIGN POST STP-1, 2 3/16", 10 GAUGE	42.000 LF	_____	_____	_____	_____
0120	700	50434 SIGN POST STP-1, 2 1/2", 10 GAUGE	108.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000119588T01 Oversight/State Project No.: HSIP-963-528, N501

Order No.: H90

Federal Project No.: HSIP-963-3(070)

Contractor: \_\_\_\_\_

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0130	700	50436 SIGN POST STP-1, 2 1/2", 12 GAUGE	4,174.000 LF	_____	_____	_____	_____
0140	700	50485 CONCRETE SIGN FOUNDATION STP-1, TYPE A	411.000 EA	_____	_____	_____	_____
0150	700	50486 CONCRETE SIGN FOUNDATION STP-1, TYPE B	8.000 EA	_____	_____	_____	_____
0160	ATTD	50900 TRAFFIC SIGN RETROREFLECTIVE SIGN POST STRIP	2,786.000 LF	_____	_____	_____	_____
0170	703	50902 TRAFFIC SIGN SOLAR PWRD FLASHING BEACON	2.000 EA	_____	_____	_____	_____
0180	704	54020 TYPE A PVMT LINE MRKG 4"	6,640.000 LF	_____	_____	_____	_____
0190	704	54048 TYPE B CLASS II PAVE. LINE MARKING 24"	1,990.000 LF	_____	_____	_____	_____
0200	704	54100 PAVEMENT MARKING THERMOPLASTIC RUMBLE STRIPS 4"	900.000 LF	_____	_____	_____	_____
0210	512	54105 ERADICATE EXIST. LINEAR PVMT MARKING	144.000 LF	_____	_____	_____	_____
0220	512	54106 ERADICATE EXIST. NONLINEAR PVMT MRKG	294.000 SF	_____	_____	_____	_____
0230	704	54399 PVMT MESSAGE MARK. R/R CROSSING TY B, CL II	1.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000119588T01

Oversight/State Project No.: HSIP-963-528, N501

Order No.: H90

Federal Project No.: HSIP-963-3(070)

Contractor: \_\_\_\_\_

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0240	704	54402 PAVE. MESSAGE MARKING STOP AHEAD, TY. B, CL II	2.000 EA	_____	_____	_____	_____
<b>Section: 0001</b>				<b>Total:</b>		_____	_____
				<b>Total Bid:</b>		_____	_____