

Schedule of Items

Proposal ID: C0000120615N01

Oversight/State Project No.: 9999-029-576, N501

Order No.: J07

Federal Project No.: NHPP-TS09(318)

Contractor: \_\_\_\_\_

SECTION: 0001 REGULAR ITEMS

Cat Alt Set ID: \_\_\_\_\_ Cat Alt Mbr ID: \_\_\_\_\_

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	303	00120 REGULAR EXCAVATION	106.000 CY	_____	_____	_____	_____
0020	ATTD	00180 UTILITY TEST PIT UNPAVED	18.000 EA	_____	_____	_____	_____
0030	ATTD	00181 UTILITY TEST PIT ASPHALT CONCRETE	21.000 EA	_____	_____	_____	_____
0040	308	10121 AGGR. BASE MATL. TY. I NO. 21A OR 21B	227.000 TON	_____	_____	_____	_____
0050	315	11070 SAW-CUT ASPH CONC FULL DEPTH	957.000 LF	_____	_____	_____	_____
0060	502	12020 STD. CURB CG-2	684.000 LF	_____	_____	_____	_____
0070	502	12022 RADIAL CURB CG-2	488.000 LF	_____	_____	_____	_____
0080	502	12030 STD. CURB CG-3	350.000 LF	_____	_____	_____	_____
0090	502	12600 STD. COMB. CURB & GUTTER CG-6	399.000 LF	_____	_____	_____	_____
0100	502	12610 RADIAL COMB. CURB & GUTTER CG-6	598.000 LF	_____	_____	_____	_____
0110	504	13108 CG-12 DETECTABLE WARNING SURFACE	121.000 SY	_____	_____	_____	_____
0120	504	13220 HYDRAULIC CEMENT CONC. SIDEWALK 4"	821.000 SY	_____	_____	_____	_____
0130	505	13280 GUARDRAIL GR-MGS1	200.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000120615N01

Oversight/State Project No.: 9999-029-576, N501

Order No.: J07

Federal Project No.: NHPP-TS09(318)

Contractor: \_\_\_\_\_

SECTION: 0001                      REGULAR ITEMS

Cat Alt Set ID:                      Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0140	505	13286 GUARDRAIL TERMINAL GR-MGS2	2.000 EA	_____	_____	_____	_____
0150	505	13287 GUARDRAIL END ANCHORAGE GR-MGS3	2.000 EA	_____	_____	_____	_____
0160	502	21020 MEDIAN STRIP MS-1	33.000 SY	_____	_____	_____	_____
0170	512	24272 TRUCK MOUNTED ATTENUATOR	1,536.000 HR	_____	_____	_____	_____
0180	512	24278 GROUP 2 CHANNELIZING DEVICES	1,822.000 DAY	_____	_____	_____	_____
0190	512	24279 PORTABLE CHANGEABLE MESSAGE SIGN	488.000 HR	_____	_____	_____	_____
0200	512	24281 ELECTRONIC ARROW BOARD	1,108.000 HR	_____	_____	_____	_____
0210	512	24282 FLAGGER SERVICE	702.000 HR	_____	_____	_____	_____
0220	ATTD	24355 POLICE PATROL UNIFORM FLAGGER	263.000 HR	_____	_____	_____	_____
0230	510	24500 REMOVE EXIST. ASPHALT	74.000 SY	_____	_____	_____	_____
0240	510	24500 REMOVE EXIST. MEDIAN STRIP MS-1	13.000 SY	_____	_____	_____	_____
0250	510	24500 REMOVE EXIST. SIDEWALK AND ENREANCE	474.000 SY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000120615N01

Oversight/State Project No.: 9999-029-576, N501

Order No.: J07

Federal Project No.: NHPP-TS09(318)

Contractor: \_\_\_\_\_

SECTION: 0001 REGULAR ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0260	510	24501 REMOVE EXIST. CONDUCTOR CABLE	15,707.000 LF	_____	_____	_____	_____
0270	510	24501 REMOVE EXIST. CURB AND GUTTER	1,373.000 LF	_____	_____	_____	_____
0280	510	24740 RECONSTRUCT EXIST. PATCH ASPHALT CONCRETE PAVEMENT	51.000 CY	_____	_____	_____	_____
0290	601	27000 SELECTIVE TREE REMOVAL TRIMMING AND CLEANUP	1.000 ACRE	_____	_____	_____	_____
0300	303	27451 INLET PROTECTION TYPE A	23.000 EA	_____	_____	_____	_____
0310	303	27461 INLET PROTECTION TYPE B	10.000 EA	_____	_____	_____	_____
0320	303	27505 TEMP. SILT FENCE TYPE A	100.000 LF	_____	_____	_____	_____
0330	ATTD	38930 CONCRETE FOUNDATION CF- 5	2.000 EA	_____	_____	_____	_____
0340	701	50108 SIGN PANEL	1,896.000 SF	_____	_____	_____	_____
0350	700	50206 SIGN POST WOOD 6" X 6"	71.000 LF	_____	_____	_____	_____
0360	700	50430 SIGN POST STP-1, 2", 14 GAUGE	51.000 LF	_____	_____	_____	_____
0370	700	50434 SIGN POST STP-1, 2 1/2", 10 GAUGE	60.000 LF	_____	_____	_____	_____

## Schedule of Items

Proposal ID: C0000120615N01

Oversight/State Project No.: 9999-029-576, N501

Order No.: J07

Federal Project No.: NHPP-TS09(318)

Contractor: \_\_\_\_\_

SECTION: 0001

REGULAR ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0380	700	50436 SIGN POST STP-1, 2 1/2", 12 GAUGE	152.000 LF	_____	_____	_____	_____
0390	700	50485 CONCRETE SIGN FOUNDATION STP-1, TYPE A	18.000 EA	_____	_____	_____	_____
0400	700	50486 CONCRETE SIGN FOUNDATION STP-1, TYPE B	4.000 EA	_____	_____	_____	_____
0410	703	51162 FLASHING BEACON FB-2	3.000 EA	_____	_____	_____	_____
0420	703	51163 FLASHER	3.000 EA	_____	_____	_____	_____
0430	700	51170 ELECTRICAL SERVICE SE-5	7.000 EA	_____	_____	_____	_____
0440	703	51184 TRAFFIC SIGNAL HEAD SECTION 12" LED	17.000 EA	_____	_____	_____	_____
0450	703	51185 TRAFFIC SIGNAL HEAD SECTION 12" HVS BACKPLATE	80.000 EA	_____	_____	_____	_____
0460	700	51212 PEDESTAL POLE PF-2 12'	141.000 EA	_____	_____	_____	_____
0470	700	51238 CONCRETE FOUNDATION SIGNAL POLE PF-8	88.000 CY	_____	_____	_____	_____
0480	700	51240 CONCRETE FOUNDATION PF- 2	88.000 EA	_____	_____	_____	_____
0490	ATTD	51425 SIGNAL POLE PEDESTAL POLE PF-2 15'	15.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000120615N01

Oversight/State Project No.: 9999-029-576, N501

Order No.: J07

Federal Project No.: NHPP-TS09(318)

Contractor: \_\_\_\_\_

SECTION: 0001 REGULAR ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0500	700	51475 SIGNAL MAST ARM POLE MP-3, TYPE A	3.000 EA	_____	_____	_____	_____
0510	700	51476 SIGNAL MAST ARM POLE MP-3, TYPE B1	2.000 EA	_____	_____	_____	_____
0520	700	51477 SIGNAL MAST ARM POLE MP-3, TYPE B2	2.000 EA	_____	_____	_____	_____
0530	700	51478 SIGNAL MAST ARM POLE MP-3, TYPE C	2.000 EA	_____	_____	_____	_____
0540	700	51485 MAST ARM 30'	2.000 EA	_____	_____	_____	_____
0550	700	51486 MAST ARM 40'	2.000 EA	_____	_____	_____	_____
0560	700	51487 MAST ARM 49'	2.000 EA	_____	_____	_____	_____
0570	700	51488 MAST ARM 60'	2.000 EA	_____	_____	_____	_____
0580	700	51489 MAST ARM 65'	2.000 EA	_____	_____	_____	_____
0590	700	51490 MAST ARM 70'	2.000 EA	_____	_____	_____	_____
0600	700	51491 MAST ARM 75' CASE 1 LOADING	2.000 EA	_____	_____	_____	_____
0610	700	51492 MAST ARM 75' CASE 2 LOADING	2.000 EA	_____	_____	_____	_____
0620	700	51600 14/2 CONDUCTOR CABLE	46,589.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000120615N01      Oversight/State Project No.: 9999-029-576, N501  
 Order No.: J07      Federal Project No.: NHPP-TS09(318)

Contractor: \_\_\_\_\_

SECTION: 0001      REGULAR ITEMS

Cat Alt Set ID:      Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0630	700	51607 14/7 CONDUCTOR CABLE	47,156.000 LF	_____	_____	_____	_____
0640	ATTD	51614 CONDUCTOR CABLE #10 AWG	450.000 LF	_____	_____	_____	_____
0650	ATTD	51614 CONDUCTOR CABLE #6 AWG	180.000 LF	_____	_____	_____	_____
0660	ATTD	51614 CONDUCTOR CABLE CAT 5E SHIELDED OUTDOOR CABLE	100.000 LF	_____	_____	_____	_____
0670	700	51615 14/1 ENCLOSED COND. CABLE	10,351.000 LF	_____	_____	_____	_____
0680	700	51700 14/2 CONDUCTOR CABLE SHIELDED	5,393.000 LF	_____	_____	_____	_____
0690	703	51826 HANGER ASSEMBLY SW-2, ONE WAY	25.000 EA	_____	_____	_____	_____
0700	703	51830 HANGER ASSEMBLY SM-3, ONE WAY	16.000 EA	_____	_____	_____	_____
0710	703	51832 HANGER ASSEMBLY SMB-1, ONE WAY	2.000 EA	_____	_____	_____	_____
0720	703	51838 HANGER ASSEMBLY SMB-3, ONE WAY	300.000 EA	_____	_____	_____	_____
0730	ATTD	51840 HANGER ASSEMBLY SMD-1	5.000 EA	_____	_____	_____	_____
0740	ATTD	51840 HANGER ASSEMBLY SMD-2	29.000 EA	_____	_____	_____	_____
0750	703	51912 LOOP SAW CUT 3/8"	3,197.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000120615N01

Oversight/State Project No.: 9999-029-576, N501

Order No.: J07

Federal Project No.: NHPP-TS09(318)

Contractor: \_\_\_\_\_

SECTION: 0001 REGULAR ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0760	703	51913 LOOP SAWCUT 5/8"	810.000 LF	_____	_____	_____	_____
0770	703	51935 REMOVE EXISTING SIGNAL HEAD	59.000 EA	_____	_____	_____	_____
0780	703	51936 REMOVE EXISTING CONTROLLER	2.000 EA	_____	_____	_____	_____
0790	703	51937 REMOVE EXISTING MANHOLE/JUNCTION BOX	3.000 EA	_____	_____	_____	_____
0800	703	51938 RELOCATE EXISTING SIGNAL HEAD	97.000 EA	_____	_____	_____	_____
0810	ATTD	51960 INSTALL CONTROLLER	2.000 EA	_____	_____	_____	_____
0820	ATTD	51961 MODIFY EXISTING CONTROLLER CABINET	46.000 EA	_____	_____	_____	_____
0830	ATTD	51962 RELOCATE EXISTING SIGN	19.000 EA	_____	_____	_____	_____
0840	ATTD	51963 REMOVE EXISTING CONTROLLER FOUNDATION	2.000 EA	_____	_____	_____	_____
0850	ATTD	51963 REMOVE EXISTING PEDESTAL POLE	34.000 EA	_____	_____	_____	_____
0860	ATTD	51963 REMOVE EXISTING PEDESTAL POLE FOUNDATION	34.000 EA	_____	_____	_____	_____
0870	ATTD	51963 REMOVE EXISTING SIGN PANEL	123.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000120615N01      Oversight/State Project No.: 9999-029-576, N501  
 Order No.: J07      Federal Project No.: NHPP-TS09(318)

Contractor: \_\_\_\_\_

SECTION: 0001      REGULAR ITEMS

Cat Alt Set ID:      Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0880	ATTD	52002 TRAFFIC SIGNALIZATION ACCESSIBLE PEDESTRIAN PUSHBUTTON STATION	551.000 EA	_____	_____	_____	_____
0890	ATTD	52002 TRAFFIC SIGNALIZATION APS MOUNTING EXTENDER 4" - 7"	2.000 EA	_____	_____	_____	_____
0900	ATTD	52002 TRAFFIC SIGNALIZATION APS MOUNTING EXTENDER 4" - 7" W/90 DEGREE ADAPTOR	2.000 EA	_____	_____	_____	_____
0910	ATTD	52002 TRAFFIC SIGNALIZATION APS MOUNTING EXTENDER 7" - 13"	41.000 EA	_____	_____	_____	_____
0920	ATTD	52002 TRAFFIC SIGNALIZATION APS MOUNTING EXTENDER 7" 13" W/90 DEGREE ADAPTOR	7.000 EA	_____	_____	_____	_____
0930	ATTD	52002 TRAFFIC SIGNALIZATION INSTALL UNINTERRUPTIBLE POWER SUPPLY	20.000 EA	_____	_____	_____	_____
0940	ATTD	52002 TRAFFIC SIGNALIZATION REMOVE AND DISPOSE EXISTING PUSHBUTTON	396.000 EA	_____	_____	_____	_____
0950	ATTD	52002 TRAFFIC SIGNALIZATION REPLACE HVSB BACKPLATE (3 SECTION)	10.000 EA	_____	_____	_____	_____
0960	ATTD	52002 TRAFFIC SIGNALIZATION REPLACE HVSB BACKPLATE (4 SECTION)	10.000 EA	_____	_____	_____	_____



Schedule of Items

Proposal ID: C0000120615N01

Oversight/State Project No.: 9999-029-576, N501

Order No.: J07

Federal Project No.: NHPP-TS09(318)

Contractor: \_\_\_\_\_

SECTION: 0001 REGULAR ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0970	ATTD	52002 TRAFFIC SIGNALIZATION REPLACE HVSB BACKPLATE (5 SECTION)	10.000 EA	_____	_____	_____	_____
0980	ATTD	52002 TRAFFIC SIGNALIZATION REPLACE LED MODULE 12"	10.000 EA	_____	_____	_____	_____
0990	ATTD	52002 TRAFFIC SIGNALIZATION RRFB W/O SOLAR PANEL (DOUBLE SIDED)	5.000 EA	_____	_____	_____	_____
1000	ATTD	52002 TRAFFIC SIGNALIZATION RRFB W/O SOLAR PANEL (SINGLE SIDED)	10.000 EA	_____	_____	_____	_____
1010	703	52404 PEDESTRIAN SIGNAL HEAD SP-9	198.000 EA	_____	_____	_____	_____
1020	704	54032 TYPE B CLASS I PVMT LINE MRKG 4"	935.000 LF	_____	_____	_____	_____
1030	704	54034 TYPE B CLASS I PVMT LINE MRKG 6"	9,863.000 LF	_____	_____	_____	_____
1040	704	54037 TYPE B CLASS I PVMT LINE MRKG 8"	100.000 LF	_____	_____	_____	_____
1050	704	54042 TYPE B CLASS I PAVE. LINE MARKING 24"	3,413.000 LF	_____	_____	_____	_____
1060	512	54105 ERADICATE EXIST. LINEAR PVMT MARKING	4,636.000 LF	_____	_____	_____	_____
1070	512	54106 ERADICATE EXIST. NONLINEAR PVMT MRKG	121.000 SF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000120615N01

Oversight/State Project No.: 9999-029-576, N501

Order No.: J07

Federal Project No.: NHPP-TS09(318)

Contractor: \_\_\_\_\_

SECTION: 0001

REGULAR ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1080	704	54571 PVTM SYMB MRKG THRU ARROW TY B, CL I	2.000 EA	_____	_____	_____	_____
1090	704	54574 PVTM SYMB MRKG SGL TURN ARROW TY B, CL I	6.000 EA	_____	_____	_____	_____
1100	704	54577 PVTM SYMB MRKG DBL TURN ARROW THRU/LT OR RT TY B, CL I	2.000 EA	_____	_____	_____	_____
1110	704	54585 PVTM SYMB MRKG DBL TURN ARROW, LT/RT TY B, CL I	2.000 EA	_____	_____	_____	_____
1120	704	54659 PVTM SYMB MRKG HELMETED BICYCLIST TY B CL I	4.000 EA	_____	_____	_____	_____
1130	700	55140 CONCRETE FOUNDATION LF- 1 TY. A	15.000 EA	_____	_____	_____	_____
1140	700	55385 ELECTRICAL SERVICE WORK PAD	7.000 EA	_____	_____	_____	_____
1150	700	55586 JUNCTION BOX JB-S1	4.000 EA	_____	_____	_____	_____
1160	700	55587 JUNCTION BOX JB-S2	40.000 EA	_____	_____	_____	_____
1170	700	55588 JUNCTION BOX JB-S3	2.000 EA	_____	_____	_____	_____
1180	700	55589 JUNCTION BOX JB-S4	2.000 EA	_____	_____	_____	_____
1190	700	56014 ELECT. SER. GRD. ELECTRODE 10'	14.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000120615N01

Oversight/State Project No.: 9999-029-576, N501

Order No.: J07

Federal Project No.: NHPP-TS09(318)

Contractor: \_\_\_\_\_

SECTION: 0001 REGULAR ITEMS

Cat Alt Set ID: \_\_\_\_\_ Cat Alt Mbr ID: \_\_\_\_\_

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1200	700	56022 1" METAL CONDUIT	110.000 LF	_____	_____	_____	_____
1210	700	56026 1 1/4" METAL CONDUIT	256.000 LF	_____	_____	_____	_____
1220	700	56028 1 1/2" METAL CONDUIT	30.000 LF	_____	_____	_____	_____
1230	700	56050 BORED CONDUIT 2"	2,265.000 LF	_____	_____	_____	_____
1240	700	56052 BORED CONDUIT 4"	723.000 LF	_____	_____	_____	_____
1250	700	56053 2" PVC CONDUIT	2,505.000 LF	_____	_____	_____	_____
1260	700	56054 3" PVC CONDUIT	3,537.000 LF	_____	_____	_____	_____
1270	700	56055 4" PVC CONDUIT	100.000 LF	_____	_____	_____	_____
1280	700	56200 TRENCH EXCAVATION ECI-1	7,160.000 LF	_____	_____	_____	_____
1290	700	56202 TRENCH EXCAVATION ECI-2	90.000 LF	_____	_____	_____	_____
1300	700	56205 TEST BORE	10.000 EA	_____	_____	_____	_____
1310	ATTD	59050 COMMUNICATION EQUIP. CCTV CAMERA DIGITAL W/POWER SUPPLY, SURGE PROTECTOR, AND CURVED ARM MOUNT	20.000 EA	_____	_____	_____	_____
1320	ATTD	59050 COMMUNICATION EQUIP. RADIO	2.000 EA	_____	_____	_____	_____

Section: 0001

Total: \_\_\_\_\_

**Total Bid:** \_\_\_\_\_.