

Schedule of Items

Proposal ID: C0000111238B02

Oversight/State Project No.: 0016-158-277, B602

Order No.: J47

Federal Project No.: HB1887SG

Contractor: _____

SECTION: 0001 REGULAR ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	513	00100 MOBILIZATION	LUMP SUM	LUMP SUM			
0020	517	00101 CONSTRUCTION SURVEYING CONSTRUCTION	LUMP SUM	LUMP SUM			
0030	303	00120 REGULAR EXCAVATION	32.000 CY				
0040	ATTD	09066 FRAME & COVER NS FRAME AND COVER	1.000 EA				
0050	308	10128 AGGR. BASE MATL. TY. I NO. 21B	287.000 TON				
0060	315	10607 ASPHALT CONCRETE TY. SM-12.5A	110.000 TON				
0070	515	10628 FLEXIBLE PAVEMENT PLANING 0" - 2"	800.000 SY				
0080	315	10642 ASPHALT CONCRETE TY. BM-25.0A	345.000 TON				
0090	504	13222 HYDRAULIC CEMENT CONC. SIDEWALK 7"	30.000 SY				
0100	512	24160 TEMPORARY (CONSTRUCTION) SIGN	500.000 SF				
0110	ATTD	24262 PORTABLE TEMPORARY RUMBLE STRIP ARRAY	20.000 DAY				
0120	512	24282 FLAGGER SERVICE	200.000 HR				

Schedule of Items

Proposal ID: C0000111238B02 Oversight/State Project No.: 0016-158-277, B602

Order No.: J47

Federal Project No.: HB1887SG

Contractor: _____

SECTION: 0001 REGULAR ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0130	512	24333 TEMPORARY TRAFFIC CONTROL SIGNAL NS TEMPORARY CONTROL TRAFFIC SIGNAL	LUMP SUM	LUMP SUM			
0140	606	27326 ROLLED EROSION CTRL PRODUCT EC-3 TYPE 2	27.000 SY				
0150	303	27417 CHECK DAM SEDIMENT RETENTION ROLL 18"	1.000 EA				
0160	303	27422 DEWATERING BASIN EC-8	2.000 EA				
0170	303	27430 SILTATION CONTROL EXCAVATION	1.000 CY				
0180	303	27461 INLET PROTECTION TYPE B	65.000 EA				
0190	303	27505 TEMP. SILT FENCE TYPE A	750.000 LF				
0200	520	40002 3/4" WATER SERVICE LINE	20.000 LF				
0210	520	40003 1" WATER SERVICE LINE	94.000 LF				
0220	520	40081 8" DI WATER MAIN	193.000 LF				
0230	520	41008 8" GATE VALVE & BOX	2.000 EA				
0240	520	41967 5/8" WATER METER BOX & YOKE	3.000 EA				

Schedule of Items

Proposal ID: C0000111238B02

Oversight/State Project No.: 0016-158-277, B602

Order No.: J47

Federal Project No.: HB1887SG

Contractor: _____

SECTION: 0001

REGULAR ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0250	520	42044 4" SANITARY SERVICE LATERAL CONNECTION	34.000 LF	_____	_____	_____	_____
0260	520	42100 10" SAN. SEWER PIPE	87.000 LF	_____	_____	_____	_____
0270	520	42755 SANITARY SEWER MANHOLE	24.100 LF	_____	_____	_____	_____
0280	520	42764 MANHOLE FRAME & COVER F&C-1	3.000 EA	_____	_____	_____	_____
0290	520	42845 4" SEWER CLEANOUT	2.000 EA	_____	_____	_____	_____
0300	701	50108 SIGN PANEL	12.000 SF	_____	_____	_____	_____
0310	700	50436 SIGN POST STP-1, 2 1/2", 12 GAUGE	60.000 LF	_____	_____	_____	_____
0320	700	50485 CONCRETE SIGN FOUNDATION STP-1, TYPE A	4.000 EA	_____	_____	_____	_____
0330	704	54032 TYPE B CLASS I PVMT LINE MRKG 4"	1,200.000 LF	_____	_____	_____	_____
0340	704	54100 PAVEMENT MARKING (24") Thermoplastic, Type B, Class II	40.000 LF	_____	_____	_____	_____
0350	512	54106 ERADICATE EXIST. NONLINEAR PVMT MRKG	1,240.000 SF	_____	_____	_____	_____
0360	404	60409 CONC. CLASS A4 MOD. LOW SHRINKAGE	77.900 CY	_____	_____	_____	_____
0370	404	60490 BRIDGE DECK GROOVING	239.000 SY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000111238B02 Oversight/State Project No.: 0016-158-277, B602

Order No.: J47

Federal Project No.: HB1887SG

Contractor: _____

SECTION: 0001

REGULAR ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0380	404	60495 COVER DEPTH SURVEY	239.000 SY	_____	_____	_____	_____
0390	406	61711 CORROSION RESISTANT REINF. STEEL CL. I	12,280.000 LB	_____	_____	_____	_____
0400	407	61822 STR. STEEL ROLLED BEAM ASTM A709 GRADE 50W	LUMP SUM	LUMP SUM	_____	_____	_____
0410	410	62034 RAILING, CPSR 2 RAIL	145.000 LF	_____	_____	_____	_____
0420	401	64011 STRUCTURE EXCAVATION	950.000 CY	_____	_____	_____	_____
0430	401	64015 SELECT BACKFILL ABUTMENT ZONE	790.000 TON	_____	_____	_____	_____
0440	401	64032 GEOCOMPOSITE WALL DRAIN	127.000 SY	_____	_____	_____	_____
0450	404	65013 CONCRETE CLASS A3	193.400 CY	_____	_____	_____	_____
0460	406	65200 REINF. STEEL	8,200.000 LB	_____	_____	_____	_____
0470	406	65211 CORROSION RESISTANT REINF. STEEL CL. I	15,370.000 LB	_____	_____	_____	_____
0480	401	66120 COFFERDAM	5.000 EA	_____	_____	_____	_____
0490	ATTD PLAN	66920 BRIDGE SUBSTRUCTURE NS CONCRETE CLASS A3 SUBFOOTER	75.000 CY	_____	_____	_____	_____
0500	413	67900 DISM.& REM. EX. STR. Remove Structure	LUMP SUM	LUMP SUM	_____	_____	_____

Schedule of Items

Proposal ID: C0000111238B02 Oversight/State Project No.: 0016-158-277, B602

Order No.: J47

Federal Project No.: HB1887SG

Contractor: _____

SECTION: 0001 REGULAR ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0510	PLAN	67904 BRIDGE INCIDENTALS NS Bridge Incidentals Temporary Shoring	LUMP SUM	LUMP SUM			
0520	430	67910 NBIS ACCESS, UNDER BRIDGE NS NBIS ACCESS UNDER BRIDGE STR NO 1800	2.000 DAY				
0530	413	68476 ENV.& WORK. PROTECTION PLAN	LUMP SUM	LUMP SUM			
0540	413	68492 MATERIAL DISPOSAL NS MATERIAL DISPOSAL NS MATERIAL DISPOSAL	LUMP SUM	LUMP SUM			
0550	512	68760 TRAF. BARR. SER. CONC. SINGLE FACE PARAPET MB- 10A	144.000 LF				
0560	ATTD	70515 ENVIR. PROTECTION TRANSPORTATION OF DISPOSAL OF PETROLEUM CONTAMINATED GROUNDWATER	8,100.000 GAL				
0570	ATTD	70520 ENVIR. PROTECTION MANAGEMENT OF PETROLEUM CONTAMINATED GROUNDWATER	LUMP SUM	LUMP SUM			
0580	ATTD	85145 TRUCK MOUNTED ATTENUATOR	100.000 HR				

Section: 0001 Total: _____

Total Bid: _____